



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:


- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>



QB 34 453




CAMBRIDGE AGRICULTURAL MONOGRAPHS

*Inorganic Plant Poisons
and Stimulants*

By Winifred E. Brenchley

YC 20922



CAMBRIDGE AGRICULTURAL MONOGRAPHS

**INORGANIC PLANT POISONS
AND STIMULANTS**

CAMBRIDGE UNIVERSITY PRESS

C. F. CLAY, MANAGER

London: FETTER LANE, E.C.

Edinburgh: 100 PRINCES STREET



London: H. K. LEWIS, 136 GOWER STREET, W.C.

London: WILLIAM WESLEY AND SON, 28 ESSEX STREET, STRAND

New York: G. P. PUTNAM'S SONS

Bombay and Calcutta: MACMILLAN AND CO., LTD.

Toronto: J. M. DENT AND SONS, LTD.

Tokyo: THE MARUZEN-KABUSHIKI-KAISHA

All rights reserved

INORGANIC PLANT POISONS AND STIMULANTS

BY

WINIFRED E. BRENCHELEY, D.Sc., F.L.S.

"
Fellow of University College, London
(Rothamsted Experimental Station)



Cambridge :
at the University Press

1914

9123
37

Cambridge:

PRINTED BY JOHN CLAY, M.A.

AT THE UNIVERSITY PRESS

Caric, Scott (Library)

TO THE
LIBRARY OF THE
UNIVERSITY OF CAMBRIDGE

PREFACE

DURING the last century great and widespread changes have been made in agricultural practice—changes largely associated with the increase in the use of artificial fertilisers as supplements to the bulky organic manures which had hitherto been used. The value of certain chemical compounds as artificial manures is fully recognised, yet many attempts are being made to prove the value of other substances for the same purpose, with a view to increase in efficiency and decrease in cost. The interest in the matter is naturally great, and agriculturists, botanists and chemists have all approached the question from their different standpoints. In the following pages an attempt is made to correlate the work that has been done on a few inorganic substances which gave promise of proving useful in agricultural practice. Much of the evidence put forward by different workers is conflicting, and it is clear that no definite conclusions can yet be reached. Nevertheless, examination of the evidence justifies the hope that results of practical value will yet be obtained, and it is hoped that the analysis and coordination of the available data put forward in this book will aid in clearing the ground for those investigators who are following up the problem from both the academic and the practical standpoints.

W. E. B.

ROTHAMSTED.

October 1914.

CONTENTS

CHAP.		PAGE
I.	INTRODUCTION	1
II.	METHODS OF WORKING	7
	I. Discussion of Methods	7
	1. Water cultures	7
	2. Sand cultures	8
	3. Soil cultures in pots	9
	4. Field experiments	9
	II. Details of Methods	10
III.	EFFECT OF COPPER COMPOUNDS	15
	I. Presence of Copper in Plants	15
	II. Effect of Copper on the Growth of Higher Plants	17
	1. Toxic effect	17
	(a) Toxic action of copper compounds alone in water cultures	17
	(b) Masking effect caused by addition of soluble substances to solutions of copper salts	20
	(c) Effect of adding insoluble substances to solutions of copper salts	22
	(d) Effect of copper on plant growth when present in soils	24
	(e) Mode of action of copper on plants	25
	2. Effect of copper on germination	27
	(a) Seeds	27
	(b) Spores and pollen grains	28
	3. Does copper stimulate higher plants?	28
	4. Action of copper on organs other than roots	30
	(a) Effect of copper sprays on leaves	30
	(b) Effect of solutions of copper salts on leaves	32
	III. Effect of Copper on Certain of the Lower Plants	33
	Conclusion	35

CHAP.		PAGE
IV.	EFFECT OF ZINC COMPOUNDS	36
	I. Presence of Zinc in Plants	36
	II. Effect of Zinc on the Growth of Higher Plants	38
	1. Toxic effect	38
	(a) Toxic action of zinc salts alone in water cultures	38
	(b) Effect of soluble zinc salts in the presence of nutrients	39
	(c) Effect of zinc compounds on plant growth when they are present in soils	41
	(d) Mode of action of zinc on plants	43
	2. Effect of zinc compounds on germination	43
	3. Stimulation induced by zinc compounds	45
	(a) Stimulation in water cultures	45
	(b) Stimulation in sand cultures	46
	(c) Increased growth in soil	46
	4. Direct action of zinc salts on leaves	47
	III. Effect of Zinc on Certain of the Lower Plants	48
	Conclusion	50
V.	EFFECT OF ARSENIC COMPOUNDS	51
	I. Presence of Arsenic in Plants	51
	II. Effect of Arsenic on the Growth of Higher Plants	52
	1. Toxic effect	52
	(a) Toxic action of arsenic compounds in water cul- tures in the presence of nutrients	52
	(b) Toxic effect of arsenic compounds in sand cultures	57
	(c) Toxic effect of arsenic when applied to soil cul- tures	57
	(d) Physiological considerations	59
	2. Effect of arsenic compounds on germination	60
	3. Do arsenic compounds stimulate higher plants?	61
	III. Effect of Arsenic Compounds on Certain of the Lower Plants	62
	1. Algae	62
	2. Fungi	63
	Conclusion	64
VI.	EFFECT OF BORON COMPOUNDS	65
	I. Presence of Boron in Plants	65
	II. Effect of Boron on the Growth of Higher Plants	67
	1. Toxic effect	67
	(a) Toxic action of boron compounds in water cultures	67
	(b) Toxic action of boron compounds in sand cultures	70

Contents

ix

CHAP.	PAGE
(c) Toxic action of boron compounds in soil experiments	71
2. Effect of boron compounds on germination	72
3. Does boron stimulate higher plants?	73
(a) Water cultures	73
(b) Sand cultures	73
(c) Soil cultures	74
III. Effect of Boron Compounds on Certain of the Lower Plants	76
Conclusion	77
VII. EFFECT OF MANGANESE COMPOUNDS	78
I. Presence of Manganese in Plants	78
II. Effect of Manganese on the Growth of Higher Plants	81
1. Toxic effect	81
(a) Toxic action of manganese compounds in the presence of soluble nutrients	81
(b) Toxic action of manganese compounds in sand cultures	82
(c) Toxic action of manganese compounds in soil cultures	82
2. Effect of manganese compounds on germination	84
3. Does manganese stimulate higher plants?	84
(a) Stimulation in water cultures	85
(b) Stimulation in soil cultures	86
III. Effect of Manganese Compounds on Certain of the Lower Plants	90
IV. Physiological Considerations of Manganese Stimulation	90
Conclusion	92
VIII. CONCLUSIONS	93
BIBLIOGRAPHY	97
INDEX OF PLANT-NAMES	107
GENERAL INDEX	109
LIST OF ILLUSTRATIONS	x

LIST OF ILLUSTRATIONS

FIG.	PAGE
1. Sketch illustrating water culture methods	12
2. Photograph. Barley grown with copper sulphate	<i>To face</i> 20
3. Curve. Ditto	21
4. Photograph. Peas grown with copper sulphate	<i>To face</i> 29
5. Curve. Ditto	29
6. Curve. Barley grown with zinc sulphate	40
7. Photograph. Peas grown with zinc sulphate	<i>To face</i> 40
8. Curve. Ditto	41
9. Photograph. Barley grown with arsenious acid	<i>To face</i> 54
10. Curve. Ditto	55
11. Curve. Peas grown with arsenious acid	55
12. Curve. Barley grown with arsenic acid	56
13. Curve. Barley grown with sodium arsenite	56
14. Curve. Peas grown with sodium arsenite	57
15. Curve. Barley grown with boric acid	69
16. Photograph. Peas grown with boric acid	<i>To face</i> 69
17. Curve. Barley grown with manganese sulphate	85
18. Photograph. Ditto	<i>To face</i> 86
19. Photograph. Peas grown with manganese sulphate	,, 86

CHAPTER I

INTRODUCTION

EVER since the physiological side of botany began to emerge from obscurity, the question of the relation between the nutrition and the growth of the plant has occupied a foremost position. All kinds of theories, both probable and improbable, have been held as to the way in which plants obtain the various components of their foods. But quite early in the history of the subject it was acknowledged that the soil was the source of the mineral constituents of the plant food, and that the roots were the organs by which they were received into the plant.

A new chapter in the history of science was begun when Liebig in 1840 first discussed the importance of inorganic or mineral substances in plant nutrition. This discussion led to a vast amount of work dealing with the problem of nutrition from many points of view, and the general result has been the sorting out of the elements into three groups, nutritive, indifferent, and toxic. Thus calcium, phosphorus, nitrogen and potassium are classed as nutritive, arsenic, copper and boron as toxic, and many others are regarded as indifferent.

Closer examination, however, shows that this division into three classes is too rigid. Now that experiments are more refined it has become evident that no such simple grouping is possible. It has been found that typical nutrient salts are toxic when they are applied singly to the plant in certain concentrations, the toxic power decreasing and the nutritive function coming into play more fully on the addition of other nutrient salts. For instance, Burlingham found that the typical nutrient magnesium sulphate in concentrations above $m/8192$ (m = molecular weight) is toxic to most seedlings, the degree of toxicity varying with the type of seedling and the conditions under which growth takes place. It will be shown in the following pages that even such a typical poison as boric acid may, under suitable conditions, increase plant growth just as if it were a nutrient. A review of the

whole subject leads one to conclude that in general both favourable and unfavourable conditions of nutrition are present side by side, and only when a balance is struck in favour of the good conditions can satisfactory growth take place. As indicated above, experiments have shown that the very substances that are essential for plant food may be, in reality, poisonous in their action, exercising a decidedly depressing or toxic influence on the plant when they are presented singly to the roots. This toxic action of food salts is decreased when they are mixed together, so that the addition of one toxic food solution to another produces a mixture which is less toxic than either of its constituents. Consequently a balanced solution can be made in which the toxic effects of the various foods for a particular plant are reduced to a minimum, enabling optimum growth to take place. Such a mixture of plant foods occurs in the soil, the composition of course varying with the soil.

While the earliest observations set forth the poisonous action of various substances upon plants, it was not long before investigators found that under certain conditions these very substances seemed to exert a beneficial rather than an injurious action. The poisons were therefore said to act as "stimulants" when they were presented to the plant in sufficiently great dilution. This stimulation was noticed with various plants and with several poisons, and a hypothesis was brought forward that attempted to reconcile the new facts with the old conceptions. Any poison, it was suggested, might act as a stimulant, if given in sufficiently small doses. It will be seen in the following pages that this is not universally true, such substances as copper, zinc, and arsenic failing to stimulate certain plants even in the most minute quantities so far tested.

Of recent years investigators in animal physiology have brought into prominence the striking effect of minute quantities of certain substances in animal nutrition, as for example iodine in the thyroid gland (see E. Baumann, 1895). This and other work has rendered it imperative to re-examine the parallel problems in plant physiology.

The words "stimulant" and "stimulation" themselves need more precise definition. As a matter of fact the "stimulation" noticed by one observer is not necessarily held to be such by another. Stimulation may express itself in various ways—the green weight and the general appearance of the fresh plant may be improved, the dry weight may be increased, the transpiration current may be hurried up, entailing increased absorption of water and food substances by the roots, assimilation processes may be encouraged. But these benefits are

not of necessity correlated with one another, e.g. a plant treated with a dilute solution of poison may look much healthier and weigh far more in the green state than an untreated plant, whereas the latter may prove the heavier in the dry state. To a market gardener to whom size and appearance is so important, stimulation means an improvement in his cabbages and lettuces in the green state, even though the increased weight is chiefly due to additional water absorbed under the encouragement of the stimulative agent, whereas to a scientific observer, the dry weight may give a more accurate estimate of stimulation in that it expresses more fully an increased activity in the vital functions of the plant whereby the nutritive and assimilative processes have gone on more rapidly, with a consequent increase in the deposition of tissue.

While stimulation expresses itself in the ways detailed above poisoning action also makes itself visible to the eye. Badly poisoned plants either fail to grow at all or else make very little or weak growth. Even when less badly affected the toxic action is well shown in some cases by the flaccidity of the roots, and in others by the formation of a "strangulation" near the crown of the root, which spreads to the stem, making it into a thin thread, while the leaves usually wither and die. If such plants as peas are able to make any shoot growth at all the roots show signs of a desperate attempt to put forth laterals. The primary root gets much thickened and then bursts down four sides, the tips of the laterals all trying to force their way through in a bunch, but failing to do so on coming in contact with the poison. Most curious malformations of the root arise from this strong effort of the plant to fight against adverse circumstances.

While all the inorganic substances examined in this monograph are toxic in high concentrations, some lead to increased growth in lower concentrations, while others apparently have no effect. In this sense all substances could be classed as toxins, even the nutrients. Thus the old distinction between toxin and nutrient has now lost its sharpness, but it does not lose all its significance. The old "nutrients" had certain definite characters in common, in that they were essential to plant growth, the growth being in a great degree proportional to the supply, a relatively large amount of the nutrients being not only tolerated but necessary. The substances dealt with more particularly in this book have none of these characters. Even those that cause increased growth do not appear to be essential, at any rate not in the quantities that potassium, phosphorus, nitrogen, &c., are essential,

while there is no evidence that growth is proportional to supply. The substances fall into two groups:

(1) Those that apparently become indifferent in high dilutions and never produce any increase in plant growth.

(2) Those that cause a small, but quite distinct, increased growth when applied in quantities sufficiently small.

The former group may be legitimately regarded as toxins; the latter present more difficulty and even now their function is not settled. It is not clear whether they stimulate the protoplasm or in some way hasten the metabolic processes in the plant, whether they help the roots in their absorbent work, or whether they are simple nutrients needed only in infinitesimal quantities. The two groups, however, cannot be sharply separated from one another. Indeed a substance may be put into one of these classes on the basis of experiments made with one plant alone and into another when a different plant is used, while it is quite conceivable that further experiments with other plants may abolish the division between the two groups altogether. It is even impossible to speak rigidly of toxicity. The addition of the inorganic food salts to solutions of a poison reduces the toxicity of the latter, so that the plant makes good growth in the presence of far more poison than it can withstand in the absence of the nutrients. This masking effect of the inorganic food salts upon the toxicity of inorganic plant poisons is paralleled by a similar action on organic toxic agents. Schreiner and Reed (1908) found that the addition of a second solute to a solution decreases the toxicity of that solution; further the plant itself may exercise a modifying influence upon the toxic agent. Water culture experiments were made upon the toxicity of certain organic compounds, with and without the addition of other inorganic salts. Arbutin, vanillin, and cumarin were definitely toxic and the toxicity decidedly fell off after the addition of sodium nitrate and calcium carbonate, especially with the weaker solutions of the toxins. Curiously enough, while weaker solutions of vanillin alone produced stimulation, the stimulating effect of this toxic agent disappeared entirely on the addition of the inorganic substances. The results showed that the addition of certain inorganic salts to solutions of toxic organic compounds was decidedly beneficial to the plant.

Another important problem has come to the front with regard to these toxic substances—How do these substances get into the plant? Are they all absorbed if they occur in the soil, or is there any discriminatory power on the part of the root? In other words, do the

roots perforce take in everything that is presented to their surfaces, or have they the power of making a selection, absorbing the useful and rejecting the useless and harmful?

Daubeny (1833) described experiments in which various plants, as radish, cabbage, *Vicia Faba*, hemp and barley were grown actually on sulphate of strontium or on soils watered with nitrate of strontium. No strontium could be detected in the ash of any of the plants save barley, and then only the merest trace was found. Daubeny concluded that the roots *were* able to reject strontium even when presented in the form of a solution. "Upon the whole, then, I see nothing, so far as experiments have yet gone, to invalidate the conclusion...that (the roots of plants do, to a certain extent at least, possess a power of selection, and that the earthy constituents which form the basis of their solid parts are determined as to *quality* by some primary law of nature, although their *amount* may depend upon the more or less abundant supply of the principles presented to them from without." Some years after, in 1862, Daubeny reverted to the idea, stating "I should be inclined to infer that the spongioles of the roots have residing in them some specific power of excluding those constituents of the soil that are abnormal and, therefore, unsuitable to the plant, but that they take up those which are normal in any proportions in which they may chance to present themselves¹." This, however, was not held to apply to such corrosive substances as copper sulphate. De Saussure had found that *Polygonum Persecaria* took up copper sulphate in large quantities, a circumstance which he attributed to the poisonous and corrosive quality of this substance, owing to which the texture of the cells became disorganised and the entrance of the solution into the vegetable texture took place as freely, perhaps, as if the plants had been actually severed asunder². Daubeny concluded that a plant is unable to exclude poisons of a corrosive nature, as this quality of the substance destroys the vitality of the absorbing surface of the roots and thus reduces it to the condition of a simple membrane which by

¹ This idea of a selectivity of the roots has been recently revived by Colin and Lavison (1910) who found that when peas were grown in the presence of barium, strontium or calcium salts no trace of barium could be found in the stem, strontium only occurred in small quantities, while calcium was present in abundance. They concluded that apparently salts of the two latter alkaline metals could be absorbed by the roots and transferred to the stem and other organs, but that this is not the case with salts of barium. They obtained similar results with other plants, beans, lentils, lupins, maize, wheat, hyacinth. Their proof is not rigid, and exception could be taken to it on chemical grounds.

² Vide Daubeny, *Journ. Chem. Soc.* (1862), p. 210.

endosmosis absorbs whatever is presented to its external surfaces, so that whenever abnormal substances are taken up by a living plant it is in consequence of some interference with the vital functions of the roots caused in the first instance by the deleterious influence of the agent employed.

In spite of the enormous amount of work that has been done on this subject of toxic action and stimulation it is yet too early to discuss the matter in any real detail. A voluminous literature has arisen around the subject, and in the present discussion some selection has been made with a view to presenting ascertained facts as succinctly as possible. No attempt has been made to notice all the papers; many have been omitted perforce; it would have been impossible to deal with the matter within reasonable length otherwise. A full and complete account would have demanded a ponderous treatise. This widespread interest on the part of investigators is fully justified, as the problems under discussion are not only of the highest possible interest to the plant physiologist, but hold out considerable promise for the practical agriculturist.

CHAPTER II

METHODS OF WORKING

I. DISCUSSION OF METHODS.

IN the course of the scattered investigations on plant poisons and stimulants, various experimental methods have been brought into use, but these all fall into the two main categories of water and soil cultures, with the exception of a few sand cultures which hold a kind of intermediate position, combining certain characteristics of each of the main groups.

The conditions of plant life appertaining to soil and water cultures are totally different, so different that it is impossible to assume that a result obtained by one of the experimental methods must of necessity hold good in respect of the other method. A certain similarity does exist, and where parallel investigations have been carried out this becomes evident, but it seems to be more or less individual, the plant, the poison and the cultural conditions each playing a part in determining the matter.

1. *Water cultures.*

This method of cultivation represents the simplest type of experiment. Its great advantage is that the investigator has absolute control over all the experimental conditions. Nutritive salts and toxic substances can be supplied in exact quantities and do not suffer loss or change by interaction with other substances which are beyond control. Any precipitates which may form in the food solution are contained within the culture vessel and are available for use if needed. The results are thus most useful as aids in interpreting the meaning of those from the field experiments, the results of the one method frequently dovetailing in with those of the other in a remarkable way. The disadvantage of the water culture method is that it is more or less unnatural, as the roots of the plants are grown in a medium quite unlike that which they meet in

nature, a liquid medium replacing the solid one, so that the roots have free access to every part of the substratum without meeting any opposition to their spread until the walls of the culture vessel are reached. The conditions of aeration are also different, for while the plant roots meet with gaseous air in the interstices of the soil, in water cultures they are dependent upon the air dissolved in the solution, so that respiration takes place under unusual conditions. It is possible that the poverty of the air supply can be overcome by regular aeration of the solution, resulting in decided improvement in growth, as L. M. Underwood (1913) has shown in recent work on barley in which continued aeration was carried out.

2. *Sand cultures.*

This method has the advantage over water cultures in that the environment of the plant roots is somewhat more natural, but on the other hand the work is cumbersome and costly, while the conditions of nutrition, watering, &c., are less under control than in the water cultures. Sand cultures represent an attempt to combine the advantages of both soil and water cultures, without their respective disadvantages. Generally speaking perfectly clean sand is used varying in coarseness in different tests, and this is impregnated with nutritive solutions suitable for plant growth. The sand is practically insoluble and sets up no chemical interaction with the nutritive compounds, while it provides a medium for the growth of the plant roots which approximates somewhat to a natural soil. It is probable, however, that a certain amount of adsorption or withdrawal from solution occurs, whereby a certain proportion of the food salts are affiliated, so to speak, to the sand particles and are so held that they are removed from the nutritive solution in the interspaces and are not available for plant food, the nutritive solution being thus weakened. The same remark applies to the poisons that are added, so that the concentration of the toxic substance used in the experiment does not necessarily indicate the concentration in which it is presented to the plant roots. On the other hand, undue concentration of the solution is apt to occur on account of the excessive evaporation from the surface of the sand. The sand particles are relatively so coarse in comparison with soil particles that the water is held loosely and so is easily lost by evaporation, thus concentrating the solution at the surface, a condition that does not apply in soil work. With care this disadvantage is easily overcome as it is possible to weigh the pots regularly and to make up the evaporation loss by the addition of water.

3. *Soil cultures in pots.*

In this case the conditions of life are still more natural, as the plant roots find themselves in their normal medium of soil. But the investigator has now far less control, and bacterial and other actions come into play, while the nutrients and poisons supplied may set up interactions with the soil which it is impossible to fathom. This method is useful in the laboratory as it is more convenient for handling and gives more exact quantitative results than plot experiments. Also the pots can be protected from many of the untoward experiences that are likely to befall the crops in the open field. The conditions are somewhat more artificial, as the root systems are confined and the drainage is not natural, but on the whole the results of pot experiments are very closely allied to those obtained in the field by similar tests.

4. *Field experiments.*

These make a direct appeal to the practical man, but of the scientific methods employed the field experiments are the least under control. The plants are grown under the most natural conditions of cultivation it is possible to obtain, and for that reason much value has been attached to such tests. Certainly, so far as the final practical application is concerned, open field experiments are the only ones which give information of the kind required. But from the scientific point of view one very great drawback exists in the lack of control that the investigator has over the conditions of experiment. The seeds, application of poison, &c., can all be regulated to a nicety, but the constitution of the soil itself and the soil conditions of moisture, temperature and aeration introduce factors which are highly variable. No one can have any idea of the composition of the soil even in a single field, as it may vary, sometimes very considerably, at every step. Further, no one knows the complicated action that may or may not occur in the soil on the addition of extraneous substances such as manures or poisons. Altogether, one is working quite in the dark as to knowledge of what is going on round the plant roots. It is impossible to attribute the results obtained to the direct action of the poison applied. While the influence may be direct, it may also happen that certain chemical and physical interactions of soil and poison occur, and that the action on the plant is secondary and not primary, so that a deleterious or beneficial result is not necessarily due to the action of the toxic or stimulating substance directly on the plant, but it may be an indirect effect induced possibly by an increase or decrease in the available plant food, or to some

other physiological factor. Consequently great care is needed in interpreting the results of field experiments without the due consideration of those obtained by other methods.

II. DETAILS OF METHODS.

Many details of the sand and soil culture methods have been published by various investigators, e.g. Hiltner gives accounts of sand cultures, while the various publications issued from Rothamsted deal largely with the soil experiments. As this is the case, and as all crucial experiments have always been and must always be done in water cultures, it is only necessary to give here full details of these.

The great essential for success in water culture work is *strict attention to detail*. Cleanliness of apparatus and purity of reagents are absolutely indispensable, as the failure of a set of cultures can often be traced to a slight irregularity in one of these two directions. Purity of distilled water is perhaps the greatest essential of all. Plant roots are extraordinarily sensitive to the presence of small traces of deleterious matter in the distilled water, especially when they are grown in the absence of food salts. Ordinary commercial distilled water is generally useless as the steam frequently passes through tubes and chambers which get incrustated with various impurities, metallic and otherwise, of which slight traces get into the distilled water. Loew (1891) showed that water which contained slight traces of copper, lead or zinc derived from distilling apparatus exercised a toxic influence which was not evident in glass distilled water. This poisonous effect was removed by filtering through carbon dust or flowers of sulphur. Apparently only about the first 25 litres of distilled water were toxic, in the later distillate the deleterious substance was not evident.

The best water to use is that distilled in a jena glass still, the steam being passed through a jena glass condenser. For work on a large scale, however, it is impossible to get a sufficient supply of such water, while the danger of breakage is very great. Experiments at Rothamsted were made to find a metallic still that would supply pure water. While silver salts are very injurious to plant growth it was found that water that had been in contact with *pure* metallic silver had no harmful action. Consequently a still was constructed in which the cooling dome and the gutters were made of pure silver without any alloy, so placed that the steam impinged upon the silver dome, condensed into the silver gutter and was carried off by a glass tube into the receptacle.

Such water proved perfectly satisfactory so long as any necessary repairs to the still were made with pure silver, but a toxic action set in directly ordinary solder was employed. More recently a new tinned copper still has been employed with good results, but this is somewhat dangerous for general purposes, as in the event of the tin wearing off in any place, copper poisoning sets in at once. The water is always filtered through a good layer of charcoal as a final precaution against impurity.

In the Rothamsted experiments no attempt is made to carry on the cultures under sterile conditions. Bottles of 600 c.c. capacity are used, after being thoroughly cleaned by prolonged boiling (about four hours) followed by washing and rinsing. The bottles are filled with nutritive solution and the appropriate dose of poison, carefully labelled and covered with thick brown paper coats to exclude the light from the roots and to prevent the growth of unicellular green algae. The corks to fit the bottles are either used brand new or, if old, are sterilised in the autoclave to avoid any germ contamination from previous experiments. Lack of care in this respect leads to diseased conditions due to the growth of fungi and harmful bacteria. Two holes are bored in each cork, one to admit air, the other to hold the plant, and the cork is cut into two pieces through the latter hole.

The seeds of the experimental plants are "graded," weighed so that they only vary within certain limits, e.g. barley may be .05—.06 gm., peas .3—.35 gm., buckwheat .02—.03 gm. In this way a more uniform crop is obtained. Great care is needed in selecting the seeds, the purest strain possible being obtained in each case. With barley it has always proved possible to get a pure pedigree strain, originally raised from a single ear. In this way much of the difficulty due to the great individuality of the plants is overcome, though that is a factor that must always be recognised and reckoned with. The seeds are sown in damp sawdust—clean deal sawdust, sifted and mixed up with water into a nice crumbly mass—and as soon as they have germinated and the plantlets are big enough to handle they are put into the culture solutions. Barley plants are inserted in the corks with the aid of a little cotton wool (non-absorbent) to support them, care being taken to keep the seed above the level of the water, though it is below the cork. With peas it is impossible to get a satisfactory crop if the seed is below the cork, as the plant is very prone to bacterial and fungal infection in its early stages, and damp cotyledons are fatal for this reason. Consequently the mouths of the bottles are covered with stout cartridge paper, the pea root being inserted through a hole in the paper, so that the

root is in the liquid while the cotyledons rest on the surface. As soon as sufficient growth has been made the papers are replaced by corks, the remnants of the seeds still being kept on top in the air. Other




Fig. 1. Diagrammatic sketches showing methods of setting up water cultures.

- A. a. Seedling of cereal.
- b. Cork bored with two holes, and cut into two pieces through one hole.
- c. Food solution.
- B. a. Pea seedling.
- b. Paper shield which supports the seedling.
- c. Brown paper cover over bottle of food solution.

plants are treated according to their individual needs and mode of germination (Fig. 1).

The constitution of the nutritive solution is important, and it is becoming more and more evident that different plants have different

optima in this respect. For several years a solution of medium strength was used, containing the following:

Potassium nitrate	1.0 gram
Magnesium sulphate5 "
Sodium chloride5 "
Calcium sulphate5 "
Potassium di-hydrogen phosphate5 "
Ferric chloride04 "
Distilled water	to make up 1 litre.

This is an excellent solution for barley plants, giving good and healthy growth. While peas grew very well in it, they showed some slight signs of over-nutrition. A weaker solution is being tested which gives very good results. Peas grow very strongly in it and it also seems to be sufficiently concentrated to allow barley to carry on its growth long enough for the purposes of experiment. The solution is as follows:

Sodium nitrate5 gram
Potassium nitrate2 "
Potassium di-hydrogen phosphate.1 "
Calcium sulphate1 "
Magnesium sulphate1 "
Sodium chloride1 "
Ferric chloride04 "
Distilled water	to make up 1 litre.

The latter solution was made up so that the quantity of phosphoric acid and potash approximated more or less to the amount of those substances found by analysis in an extract made from a good soil.

The experiments are usually carried on for periods varying from 4—10 weeks, six weeks being the average time. Careful notes are made during growth and eventually the plants are removed from the solutions, the roots are washed in clean water to remove adherent food salts, and then the plants are dried and weighed either separately or in sets. In order to reduce the error due to the individuality of the plants, five, ten or even twenty similar sets are grown in each experimental series, the mean dry weight being taken finally. Also the same experiment is repeated several times before any definite conclusions are drawn.

Another method of water cultures is used by some investigators, in which the experiments only last for a few hours or days, usually 24—48 hours. While such experiments may not be without value for determining the broader outlines of toxic poisoning, they fail to show the finer details. The effect of certain strengths of poison is not

always immediate. Too great concentrations kill the plant at once; too weak solutions fail to have any appreciable immediate action and so appear indifferent. Between the two extremes there exists a range of concentrations of which the effect varies with the plant's growth. A solution may be of such a nature and strength that at first growth is seriously checked, though later on some recovery may be made, while it is also possible that a concentration which is apparently indifferent at first may prove more or less toxic or stimulant at a later date, according to circumstances. Consequently too much stress must not be laid upon the results of the short time experiments with regard to the ultimate effect of a poison upon a particular plant.

An examination of the various experimental methods shows that while no one of them is ideal, yet each of them has a definite contribution to make to the investigation of toxic and stimulant substances. Each method aids in the elucidation of the problem from a different standpoint, and the combination of the results obtained gives one a clearer picture of the truth than could be obtained by one method alone. Water cultures, with their exactitude of quantitative control lead on by way of sand cultures to pot cultures, and these to field experiments in which the control is largely lost, but in which the practical application is brought to the front.

CHAPTER III

EFFECT OF COPPER COMPOUNDS

I. PRESENCE OF COPPER IN PLANTS.

COPPER has been recognised as a normal constituent of certain plants for at least a century, so much so that in 1816 Meissner brought out a paper dealing solely with the copper content of various plant ashes. The ash of *Cardamomum minus*, of the root of *Curcuma longa*, and of "Paradieskörner¹," amongst others, were tested and all yielded copper in very small quantity. Meissner was led to conclude that copper is widespread in the vegetable kingdom, but that it exists in such minute traces that its determination in plants is exceedingly difficult. In 1821 Phillips made an interesting observation as to the effect of copper on vegetation. Some oxide of copper was accidentally put near the roots of a young poplar, and soon after the plant began to fail. The lower branches died off first, but the harm gradually spread to the topmost leaves. As a proof that copper had been absorbed by the plant the record tells that the blade of a knife with which a branch was severed was covered with a film of copper where it had been through the branch, and the death of the plant was attributed to the absorbed copper.

After this preliminary breaking of the ground little more seems to have been done for some sixty years, but from about 1880 till the present day the association of copper with the vegetable kingdom has been actively investigated in its many aspects. Dieulafait (1880) showed that the quantity of copper present in the vegetation is largely determined by the nature of the soil, which thus affects the ease with which the element can be detected and estimated. Copper was shown to exist in all plants which grow on soils of "primary origin" ("roches de la formation primordiale"), the proportion being sufficient to enable

¹ These are "grains of Paradise," Guinea grains, or melegueta pepper. They are the seeds of *Amomum melegueta* and *A. Granum-Paradisi*, N.O. Zingiberaceae.

it to be recognised with certainty in one gram of ash, even by means of the ammonia reaction. Samples of white oak from the clay soils, and plants from the dolomitic horizons also gave evidence of copper in one gram of ash, though less was present than in the first case considered, but with plants grown on relatively pure chalk 100 grams of ash had to be examined before copper could be recognised with certainty.

E. O. von Lippman found traces of copper in beets, beet leaves, and beet products; Passerini estimated as much as $\cdot 082\%$ copper in the stem of chickpea plants, though he regarded this figure as too high; Hattensaur determined $\cdot 266\%$ CuO in the total ash of *Molinia caerulea* ($\cdot 006\%$ of total plant, air-dried).

After this Lehmann (1895, 1896) carried out more exhaustive studies on the subject of detecting and estimating the copper in various articles of food: wheat, rye, barley, oats, maize, buckwheat, and also in various makes of bread; potatoes, beans, linseed, salads, apricots and pears; cocoa and chocolate. He found that only in those plants which are grown on soil rich in copper does the copper reach any considerable value, a value which lies far above the quantity present in an ordinary soil. Plants from the former soils contained as much as 83—560 mg. Cu in 1 kilog. dry substance, whereas ordinarily the plants only contained from a trace to 20 mg. Apparently the species of the plants concerned seems to be of less importance for their copper content than is the copper content of the soil. The deposition of copper (in wheat, buckwheat and paprika) is chiefly in the stems and leaves, little being conveyed to the fruits and seeds, so that a high content of copper in the soil does not necessarily imply the presence of much copper in the grain and seed. The metal is variously distributed among the tissues, the bark of the wood being the richest of the aerial parts in that substance. The form in which the copper exists in the plant is uncertain and it is suggested that an albuminous copper compound possibly exists.

Vedrödi (1893) tackled the problem at about the same time as Lehmann but from a rather different standpoint. He ratifies the statement as to the absorption of copper by plants, and going still further he states that in some cases the percentage of copper found in the seed may be four times as great as that occurring in the soil on which the plants grow, quoting one instance in which the soil contained $\cdot 051\%$ CuO and the seed $\cdot 26\%$ CuO. It is assumed that copper must play some physiological rôle in the plant, but no explanation of this action is yet forthcoming. Lehmann criticised Vedrödi's figures of the copper content of certain plant ashes, and the latter replied in a further

paper (1896) in which he brings most interesting facts to light. The quantity of copper in any species of plant varies with the individuals of that species, even when grown on the same soil, in the same year, and under similar conditions. The copper content of certain plants is put forward as a table, the years 1894 and 1895 being compared, and enormous differences are to be noticed in some cases. A quotation of the table will illustrate this more clearly than any amount of explanation.

Milligrams of copper in 1 kilog. dry matter.

	1894		1895	
	min.	max.	min.	max.
"Seeds"				
Winter wheat	80	710	200	680
Summer wheat	190	630	190	230
Maize	60	90	10	30
Barley	80	120	10	70
Oats	40	190	40	200
Buckwheat	160	640	150	160
"Fisolen" (Beans)	160	320	110	150
Linseed	120	150	110	150
Peas	60	100	60	110
Soy Beans	70	100	70	80
Lupins	80	190	70	290
Mustard seed	70	130	60	70
Paprika pods	790	1350	230	400

II. EFFECT OF COPPER ON THE GROWTH OF HIGHER PLANTS.

1. *Toxic effect.*

(a) *Toxic action of copper compounds alone in water cultures.*

The method of water cultures has been largely applied to determine the relation of copper compounds to plants. Twenty years ago (1893) Otto discovered the extreme sensitiveness of plants to this poison when grown under such conditions, as he found that growth was very soon checked in ordinary distilled water which on analysis proved to contain minute traces of copper. Controls grown in tap water gave far better plants, but this superiority was attributed partly to the minute traces of mineral salts in the tap water, and not only to the absence of the copper which occurred in the distilled water.

Tests made at Rothamsted have carried this point still further. *Pisum sativum*, *Phaseolus vulgaris*, *Triticum vulgare*, *Zea japonica*, *Tropeolum Lobbianum*, sweet pea (American Queen), nasturtium, and

cow pea—the first three of these being the species used by Otto—were grown in (1) ordinary distilled water, which was found to contain traces of copper, (2) glass distilled water, for about a month, till no more growth was possible owing to the lack of nutriment. In every single case the root growth was checked in some degree in the ordinary distilled water, the roots seeming to the eye to be less healthy and less well developed. In *Pisum*, *Tropeolum* and *Zea*, the shoot growth of the coppered plants appeared stronger than that of the controls, and this was borne out when the dry weights of the plants were obtained. In every other case the coppered plants were inferior, root and shoot, to those grown in the pure water. With the first three plants it appears that while the toxic water has a bad effect on the roots, yet the growth of the shoots is increased. The idea suggests itself that this apparent stimulation is in reality the result of a desperate struggle against adverse circumstances. The roots are the first to respond to the action of the poison, as they are in actual contact; their growth is checked, and hence the water absorption is decreased. No food is available in the water supply from the roots, so the plant is entirely dependent on the stores laid up in the seed and on the carbon it can derive from the air by photo-synthesis carried on by the green leaves. The result of the root checking in these particular cases seems to be so to stimulate the shoots by some physiological action or other, that this process of photo-synthesis is hastened, more carbon being converted into carbo-hydrates, so that the shoot development is increased, yielding a greater weight of dry matter. In each of the other cases observed the shoot was obviously not stimulated to increased energy by the poison, and so the whole plant fell below the normal.

Other experiments showed that barley roots are peculiarly sensitive to the presence of minute traces of copper, as very little root growth took place in the copper distilled water, and root growth was also entirely checked by the presence of one part per million copper sulphate in the pure glass distilled water. Yet again, one litre of pure distilled water was allowed to stand on a small piece of pure metallic copper foil (about $1\frac{1}{2}'' \times \frac{1}{2}''$) for an hour, and even such water exercised a very considerable retarding influence upon the root-growth, checking it entirely in some instances.

Some years before True and Gies published their results, Coupin (1898) had grown wheat seedlings in culture solutions with the addition of copper salts for several days in order to find the fatal concentrations of the different compounds. Taking toxic equivalent as meaning "the

minimum weight of salt, which, dissolved in 100 parts of water, kills the seedling," the results were as follows:

	Toxic equivalent	Containing copper
Copper bromide (CuBr_2)	·004875	·001387
Copper chloride ($\text{CuCl}_2 \cdot 2\text{aq.}$)	·005000	·001865
Copper sulphate ($\text{CuSO}_4 \cdot 5\text{aq.}$)	·005555	·001415
Copper acetate ($\text{Cu}(\text{C}_2\text{H}_3\text{O}_2)_2 \cdot \text{aq.}$)	·005714	·001820
Copper nitrate ($\text{Cu}(\text{NO}_3)_2 \cdot 6\text{aq.}$)	·006102	·001312

These numbers appear to be very close, so Coupin considered that it might be permissible to regard the differences as due to the impurities in the salts, and to the water of crystallisation which may falsify the weights, so that under these conditions one may believe that all these salts have the same toxicity. This is considerable, and is evidently due to the copper ion, the electro-negative ion not intervening with such a feeble dose. A recalculation of these toxic equivalents to determine the actual amount of copper present in each, gives results that are fairly approximate, but it is difficult to accept this hypothesis in view of other work in which different salts of the same poison are proved to differ greatly in their action on plant growth.

Kahlenberg and True (1896), working with *Lupinus albus*, found that the various copper salts, as sulphate, chloride and acetate, were similar in their action upon the roots. Plants placed in solutions of these salts of varying strengths for 15—24 hours showed that in each case 1/25,600 gram molecule killed the root, while with 1/51,200 gram molecule the root was just alive. These workers discuss their results from the standpoint of electrolytic dissociation, and concur in the opinion that the positive ions of the toxic salt are exceedingly poisonous.

The toxicity of the positive ion was again set forth by Copeland and Kahlenberg (1900). Their water culture experiments were carried on in glass vessels coated internally with paraffin to avoid solution of glass, and in tests with seedlings of maize, lupins, oats and soy beans it was found that such metals as copper, iron, zinc and arsenic were almost always fatal to the growth of plants. As a general rule those metals whose salts are toxic, themselves poison plants when they are present in water. The assumption made was that the injury to plants when cultivated in the presence of pure metals depends on the tendency of the metal to go into solution as a component of chemical compounds and on the specific toxicity of the metallic ion when in solution.

(b) *Masking effect caused by addition of soluble substances to solutions of copper salts.*

Experiments were carried on with barley, in which the plants were grown in the various grades of distilled water indicated above, both with and without the addition of nutrient salts. It was found that the presence of the nutrients exercises a very definite masking effect upon the action of the poisonous substance, so that the deleterious properties of the toxic substance are materially reduced. Later work, in which known quantities of such toxic salts as copper sulphate were added to pure distilled water showed that in the presence of nutrient salts a plant is able to withstand the action of a much greater concentration of poison. For instance, a concentration of 1 : 1,000,000 copper sulphate alone stops all growth in barley, but, if nutrient salts are present, a strength of 1 : 250,000 (at least four times as great) does not prevent growth, though the retarding action is very considerable (Figs. 2 and 3).

These later Rothamsted results fit in very well with those obtained ten years ago (1903) by True and Gies in their experiments on the physiological action of some of the heavy metals in mixed solutions. Plants of *Lupinus albus* were tested for 24—48 hours with different solutions in which the roots were immersed. Given the same strength of the same poison, the addition of different salts yielded varying results. For instance, with copper chloride as the toxic agent, the addition of magnesium chloride did not affect the toxicity, calcium chloride decreased it, while sodium chloride slightly increased the poisonous action. Calcium sulphate with copper sulphate enabled a plant to withstand four times as much copper as when the latter was used in pure solution. Calcium salts in conjunction with those of copper proved generally to accelerate but not to increase growth, but with silver salts they did not cause any improvement. Perhaps this amelioration is in inverse proportion to the activity of the heavy metals. With a complex mixture consisting of five salts—copper sulphate and salts of sodium, magnesium, calcium and potassium, all except calcium being present in concentrations strong enough to interfere with growth if used alone—it was shown that “as a result of their presence together, not only is there no addition of poisonous effects, but a neutralisation of toxicity to such degree as to permit in the mixed solutions a growth-rate equal to or greater than that seen in the check culture.” If the concentration of the copper salts was increased, the




Fig. 2. Photograph showing the action of copper sulphate on barley in the presence of nutrient salts. (March 5th—April 19th, 1907.)

1. Glass distilled water.
2. Copper distilled water.
3. $1/12,500$ copper sulphate.
4. $1/25,000$ " "
5. $1/50,000$ " "
6. $1/100,000$ " "
7. $1/250,000$ " "
8. $1/500,000$ " "
9. $1/1,000,000$ " "

70 1000
Algebra

other salts remaining the same, the poisonous activity of the copper became greater than could be neutralised by the other salts. If the copper remained the same and the other salts were diminished by half (i.e. below toxic concentration) the neutralising action of the added salts was markedly less, and the growth rate *never exceeded* that of the




Fig. 3. Curve showing the dry weights of a series of barley plants grown in the presence of copper sulphate and nutrient salts. (March 13th—May 3rd, 1907.)

NOTE. In each scale of concentrations represented in the curves a convenient intermediate strength is selected as a unit, and all other concentrations in the series are expressed in terms of that unit. Thus, with 1/1,000,000 as the unit a scale of concentrations might run thus:

10	1/100,000
4	1/250,000
2	1/500,000
1	1/1,000,000
0.5	1/2,000,000
0.1	1/10,000,000
0.05	1/20,000,000
0	Control.

control. This was apparently due to the action of the unneutralised copper. The indications are that the conspicuously effective part of the molecule is the cation or metal, and that the anion plays little or no part in causing the toxicity; in such great dilutions the metals act as free ions. The hypothesis is put forward that interior physiological modifications are responsible for the observed differences in growth rate, the cell processes being so affected as to bring about different results on cellular growth; in other words, the growth rate represents the physiological sum of oppositely acting stimuli or of antagonistic protoplasmic changes where mixtures of salts occur. This is really an extension of Heald's idea that the toxic effect of a poison is due partly to changes in the turgescence of the cell, a sudden decrease causing retardation or inhibition of growth, and partly to a direct action on the protoplasm, which differs in different plants with the same salt. Heald (1896) went so far as to suggest that the poisonous action is a mere matter of adaptation and adjustment, since toxic substances are not usually present in soil, but this assertion is too sweeping to be accepted in its entirety, although it probably holds good to a certain extent with some species of plants.

Kahlenberg and True (1896) found that the addition of an organic substance produced the same effect as the addition of some nutrient salt, in that it reduced the toxicity of the copper salt, e.g. in the presence of sugar and potassium hydrate the lupins were able to withstand a concentration of 1/400 copper sulphate, part of which reduction of toxicity is attributed to the sugar.

(c) *Effect of adding insoluble substances to solutions of copper salts.*

Other investigators have shown that the presence of insoluble substances has a similar effect in reducing toxicity to an even greater degree. True and Oglevee (1904, 1905) again used *Lupinus albus* as a test plant in the presence of solutions of various poisons in pure distilled water, copper sulphate, silver nitrate, mercuric chloride, hydrochloric acid, sodium hydroxide, thymol and resorcinol all coming under consideration. Clean sea sand, powdered Bohemian glass, shredded filter paper, finely divided paraffin wax and pure unruptured starch grains were respectively added to the solutions, and seedlings were suspended over glass rods so that their roots were in the solutions for 24—48 hours. The solids varied in their action on the different poisons; while the toxic influence of mercuric chloride was reduced by sand and crushed glass, the action of silver nitrate was modified by nearly

all the solids. Lupin roots proved unable to withstand an exposure of 24 hours to a concentration of copper sulphate of 1 molecular weight in 60,000 litres of water (i.e. about 1 part by weight $\text{CuSO}_4 \cdot 5\text{H}_2\text{O}$ in 240.4 parts water), but the addition of solids caused a great decrease in toxicity. When the amount of copper was diminished an advantage was regularly obtained in favour of the cultures containing the solid bodies. On the whole the ameliorating action of solids is more clearly marked with dilute solutions of strong poisons than with relatively concentrated solutions of weaker poisons. As a general rule, filter paper and potato starch grains exert a more marked modifying action than the denser bodies, such as sand, glass or paraffin.

Breazeale (1906) tested the same point with extracts of certain soils which proved toxic to wheat seedlings grown in them as water cultures. The toxicity was wholly or partly removed by the addition of such substances as carbon black, calcium carbonate or ferric hydrate. Other experiments showed that the toxic substances of ordinary distilled water are removed by ferric hydrate and carbon black, and further that the latter substance will take out copper from copper solutions, rendering them far less poisonous.

Further corroboration of True and Oglevee's work was obtained by Fitch (1906) who worked in a similar way with fungi, arriving at the general conclusion that insoluble substances in a solution act as agents of dilution or absorption whereby poisonous ions or molecules are in some way removed. He found that $n/256$ of copper sulphate in beet concoction exercised a stimulating effect on *Penicillium glaucum*, but the addition of fine glass to the solution increased the stimulation, while large or medium sized pieces did not have the same effect.

This action of solid bodies in reducing the deleterious effects of poisonous solutions is attributed to the process of "adsorption" whereby a layer of greater molecular density is formed on the surfaces of solids immersed in solutions. The solids presumably withdraw a certain proportion of poisonous ions or molecules from the body of the solution (retaining them in a molecularly denser layer over their own surfaces), so that the toxic properties of the solution are reduced owing to the withdrawal of part of the poison from the field of action. In some cases this reduction may be so great as to relieve the solution of its toxic properties, or even to cause an abnormal acceleration to replace a marked retardation. Also, if the solution is of such a dilution as to cause acceleration of growth in plants, the addition of insoluble substances may increase this acceleration. The progressive addition of

quantities of solids causes progressive dilution of the toxic medium, the underlying cause of these results being the gradual removal of molecules or ions from the solutions by the insoluble body present.

Fitch's results are also in accordance with the well-known fact that the physical condition and properties of the added solid play a considerable part in determining its efficacy as an adsorbing agent.

(d) *Effect of copper on plant growth when present in soils.*


As has already been shown the toxic property of copper with regard to plants was recognised almost as soon as that element was found to occur in the vegetable kingdom, but little notice was taken of the discovery for many years. In 1882 F. C. Phillips asserted, as the result of experiments with various cultivated flowering plants, including geraniums, coleas, ageratum, pansies, &c., that under favourable conditions plants will absorb small quantities of copper by their roots, and that such compounds exercise a distinctly retarding influence even if in very small amount, while if large quantities are present they tend to check root formation, either killing the plants outright or so far reducing their vitality as seriously to interfere with nutrition and growth. Two years later Knop confirmed both the absorption and the toxicity of copper by his experiments on maize.

Jensen (1907) worked with "artificial" soils, under sterile conditions, using finely ground quartz flour for his medium and wheat for a test plant, parallel experiments being carried on with solutions. Every precaution was taken to ensure sterility—the corks were boiled first in water and then in paraffin, the seeds were sterilised in 2% copper sulphate solution for $\frac{3}{4}$ hour, washed in sterilised water, planted in sterilised sphagnum, the transplanting being done in a sterile chamber into sterilised solutions. The criteria used to determine the toxic and stimulation effects were the total transpiration, average length of sprout, the green weight and dry weight of plants. The results obtained with the different substrata showed that it does not follow that a salt highly toxic in solution is equally so in soil, or that one which holds a relatively high toxic position in soil should occupy the same relative position in solution cultures. For instance, while in soil cultures nickel compounds were the most toxic of all the substances tried, in solution cultures silver compounds were more poisonous than nickel. The range of concentrations, both fatal and accelerating, was found to be much greater in solution than in soil cultures.

In the sand cultures the toxicity of the copper sulphate was found

to decrease as the ratio of the quartz sand to the poisonous solution increased, provided that a water content suitable for growth was present. Jensen states that the fatal concentration of copper sulphate in solution cultures is approximately $\frac{1}{10}$ th that of the fatal concentration in his artificial soil.

When copper salts are added to soil a complication at once sets in due to the double decomposition which is always likely to occur when any soluble salt is added to soil. The reaction may be graphically expressed as follows, in a much simplified form—



Haselhoff (1892) extracted several lots of 25 kgm. soil, each with 25 litres of water in which quantities of mixed copper salts varying from 0—200 mg. had been dissolved, the mixture consisting of three parts copper sulphate and one part copper nitrate. This operation was repeated 15 times, the soils being allowed to drain thoroughly after each treatment, so that altogether each 25 kgm. soil was extracted with 375 litres water. The drainage waters were analysed, so that the amount of copper absorbed by the soils could be estimated. It was found that by extracting with water containing such soluble copper salts as sulphate and nitrate, the food salts of the soil, especially those of calcium and potassium, were dissolved and washed out, copper oxide being retained by the soil. In this way a double action was manifest, whereby the fertility of the soil was reduced by the loss of plant food, while its toxicity was increased by the accumulation of copper oxide. So long as the soil contained a good supply of undissolved calcium carbonate the harmful action of the copper-containing water was diminished, but as soon as the store was exhausted by solution and leaching, the toxic influence became far more evident.

(e) *Mode of action of copper on plants.*

Quite early in the investigations on the effect of copper on plants the question arose as to its mode of activity—whether the toxicity was merely due to some mechanical action on the root from outside, whereby the absorptive power of the root was impaired, or whether the poisonous substance was absorbed into the plant, so acting directly on the internal tissues. Gorup-Besanez made definite experiments towards ascertaining the truth of these theories as far back as 1863, endeavouring first of all to see whether the plants take up any appreciable quantity of poisons which exist in the soil as mixtures or combinations and which

are capable of solution by the cell-sap. Salts of arsenic, copper, lead, zinc and mercury were intimately mixed with soil, 30 grams of the poison being added to 30·7 cubic decimetres of soil, two plants separated by a partition being grown on this quantity. The test plants were *Polygonum Fagopyrum*, *Pisum sativum*, *Secale cereale* and *Panicum italicum*, and all the plants developed strongly and normally except the last named. The *Panicum* developed very badly coloured leaves in an arsenic-containing soil, and the plants were killed soon after they started in soils containing copper. After harvesting, the crops were analysed and no trace of copper was found in any one of the experimental plants by the methods adopted. Also the absorption capacity of different soils for different poisons was shown to vary, for basic salts are absorbed, while acids may pass completely through the soil into the drainage water.

These results obtained by Gorup-Besanez are possibly not altogether above criticism, for later workers showed that copper was absorbed to some extent by plants grown in water cultures, and if that is so it seems unlikely that no absorption should take place from soil. Nevertheless, the absorption is very slight, for apparently living protoplasm is very resistant to copper osmotically. Otto showed that beans, maize and peas can have their roots for a long time in a relatively concentrated solution of copper sulphate, and yet take up very little copper indeed, but analyses do reveal slight traces after a sufficient interval of time of contact has elapsed. Berlese and Sostegni indicate that the roots of plants grown in water culture in the presence of bicarbonate of copper showed traces of copper.

Verschaaffelt (1905) devised an ingenious method of estimating the toxic limits of plant poisons, though it is rather difficult to see how the method can be put to practical use with water culture and soil experiments. Living tissues increase in weight when put into water on account of the absorption of water. Dead tissues do not, as they have lost their semi-permeable characteristics, so a decrease in weight takes place owing to part of the water passing out. This principle is applied by Verschaaffelt to determine the "mortal limit" of external agents in their action on plant tissues. Root of beetroot, potato tuber, aloe leaves, and parts of other plants rich in sugar all came under review. The parts were cut into small pieces weighing about 3—5 grams, dried with filter paper, weighed, and plunged into solutions of copper sulphate of varying strengths from ·001—·004 gm. mol. per litre, and left for 24 hours. After drying and again weighing

all were heavier owing to the absorption of water. The pieces were then immersed in pure water for another period of 24 hours, when after drying and weighing, those from the weaker strengths of copper sulphate (·001—·002) had absorbed yet more water, while those from higher concentrations (·003—·004) had lost weight. So the author assumes that for such pieces of potato the limit of toxicity lies between ·002 and ·003 gm. mol. copper sulphate per litre.

These experiments may possibly give some indication as to the action of copper salts on plant roots. So long as the solution of copper salt is dilute enough, the absorption layer of the root, acting as a semi-permeable membrane and upheld by the resistant protoplasm, is able to keep the copper out of the plant and to check its toxicity. As soon as a certain limit is reached the copper exercises a corrosive influence upon the outer layer of the root whereby its functions are impaired, so that it is no longer able efficiently to resist the entry of the poison. As the concentration increases it is easy to conceive that the harmful action should extend to the protoplasm itself, so that the vital activities of the plants are seriously interfered with and growth is entirely or partially checked, death ensuing in the presence of sufficiently high concentrations.

2. Effect of copper on germination.

The action of copper on the germination of seeds, spores and pollen grains has attracted a certain amount of attention, and although the results are apparently contradictory this is probably due to the different plant organs with which the observers have worked.

(a) Seeds.

Miyajima (1897) showed that the germinating power of such seeds as *Vicia Faba*, *Pisum sativum*, and *Zea Mays* was partly destroyed by a 1% solution of copper¹, *Zea Mays* being the most resistant and *Vicia Faba* the least resistant of the three. Micheels (1904-5) stated that water distilled in a tinned copper vessel was more favourable for germination than water from a non-tinned vessel. He suggests that this is due to copper being present in the water in a colloidal form in which the particles are exceedingly small and maintain themselves in the liquid by reason of a uniform disengagement of energy in all directions, to which energy the influence on germinating seeds must be

¹ The English translation in *Just Bot. Jahresber.* speaks only of a "solution of copper," and in no case is the specific compound mentioned.

attributed, the nature of the suspended substance determining whether the influence be favourable or not. It is questionable, however, whether Micheels was really dealing with a true colloidal solution of copper or with a dilute solution of some copper salt produced by oxidation of the copper vessel from which his distilled water was obtained.

(b) *Spores and pollen grains.*

Miani (1901) brought fresh ideas to bear upon the problem of the action of copper on living plant cells, in that he sought to attribute the toxic or stimulant effects to an oligodynamic action, i.e. spores and pollen grains were grown in hanging drop cultures in pure glass distilled water with the addition of certain salts or traces of certain metals. While the salts are known to be often disadvantageous to germination, Nägeli had asserted that the latter often exerted an oligodynamic action. In some cases pure copper was placed for varying times in the water from which the hanging drop cultures were eventually made, or tiny bits of copper were placed in the drop itself. Various kinds of pollen grains were tested, and as a rule, pollen was only taken from one anther in each experiment, though occasionally it was from several anthers of the same flower. It was generally found that the germination of pollen grains or *Ustilago* spores was not hindered by the use of coppered water or by the presence of small bits of copper in the culture solution. The only cases in which some spores or pollen grains were more or less harmed were those in which the water had stood over copper for more than two weeks, and even so the deleterious effect was chiefly noticeable when the pollen itself was old or derived from flowers in which the anther formation was nearly at an end. As a rule germination was better in the presence of copper, whether in pure water or food solution, the stimulus being indicated both by the greater number of germinated grains and by the regular and rapid growth of the pollen tubes. Miani attributes this favourable action to the mere presence of the copper, corroborating Nägeli's idea of an oligodynamic action.

3. *Does copper stimulate higher plants?*

From the foregoing review it is evident that it is the toxic action of copper that is most to the front, so far as the higher plants are concerned, and that little or no evidence of its stimulative action in great dilution has so far been discussed. Kanda dealt with this question, with the deliberate intention of obtaining such evidence,



Fig. 4. Photograph showing the action of copper sulphate on pea plants in the presence of nutrient salts. (Oct. 3rd—Dec. 20th, 1912.)

1.	Control.	
2.	1/50,000	copper sulphate.
3.	1/100,000	" "
4.	1/250,000	" "
5.	1/500,000	" "
6.	1/1,000,000	" "
7.	1/2,500,000	" "
8.	1/5,000,000	" "
9.	1/10,000,000	" "
10.	1/20,000,000	" "

if it existed. He worked with *Pisum sativum*, var. *arvense*, *Pisum arvense*, *Vicia Faba*, var. *equine* Pers, and *Fagopyrum esculentum* Mönch, which were grown in glass distilled water, without any food salts, so that the plants were forced to live on the reserves in the seeds, which were carefully graded to ensure uniformity of size. It was found that in water cultures copper sulphate solutions down to $\cdot 00000249\%$ (about 1 in 40,160,000) are harmful to peas, and still further down to $\cdot 0000000249\%$ (about 1 in 4,016,000,000) the copper salts act as a poison rather than as a stimulant. Against this, however, is the statement that in certain soils copper sulphate acts as a stimulant when it




Fig. 5. Curve showing the mean values of the dry weights of four series of pea plants grown in the presence of copper sulphate and nutrient salts. (Oct. 8rd—Dec. 20th, 1912.)

is added in solution. Jensen again could obtain no stimulation with copper sulphate.

The Rothamsted experiments go to uphold Kanda's statements as to the failure of copper sulphate to stimulate plants grown in water cultures. Peas are perhaps slightly more resistant to the greater strengths of copper sulphate than are barley and buckwheat, for while 1/100,000 proves mortal to the latter, peas will struggle on and fruit in 1/50,000, though this strength is very near the limit beyond which no growth can occur (Fig. 4). As a general rule, with barley the depression caused by the poison is still evident with 1/5,000,000 and 1/10,000,000, though occasionally these doses act as indifferent doses, no sign of

stimulation appearing in any single instance. With peas again, even 1/20,000,000 copper sulphate is poisonous, although to the eye there is little to choose between the control plants and those receiving poison up to a concentration of one part in $2\frac{1}{2}$ million (Fig. 5). In the case of buckwheat the matter is still undecided, as in some experiments apparent stimulation is obtained with 1 in $2\frac{1}{2}$ or 1 in 5 million copper sulphate, while in others a consistent depression is evident, even when the dilution is carried considerably below this limit. The reason for the variation with this particular plant is so far unexplained.

Yet, in spite of all the accumulated evidence as to the consistent toxicity of copper salts in great dilution, the possibility still remains that the limit of toxicity has not yet been reached, and that a stimulating concentration does exist, so that it is still uncertain whether beyond the limits of toxicity copper salts act as indifferent or stimulative agents.

4. *Action of copper on organs other than roots.*

The bulk of the work on the relations of copper with the life-processes of plants has dealt with those cases in which the metal has been supplied to the roots in some form or other, and many of the results may be said to apply more strictly to the theoretical, or rather to the purely scientific aspects of the matter, than to the practical everyday life of the community. This statement is hardly correct, in that the two lines of work are so inextricably interwoven that the one could not be satisfactorily followed up without a parallel march of progress along the other. In practice, copper has proved remarkably efficient as a fungicide when applied as sprays in the form of Bordeaux mixture to infested plants and trees. Observations on the action of the fungicide have shown that the physiological processes of the treated plants are also affected to some degree, and a number of interesting theories and results have been put forward.

(a) *Effect of copper sprays on leaves.*

Frank and Krüger (1894) treated potato plants with a 2% Bordeaux mixture, and obtained a definite improvement in growth, which they attributed to the direct action of the Bordeaux mixture upon the activities of the plant. The effect of the copper was most marked in the leaves, and was chiefly indicated by increase in physiological activity rather than by morphological changes. The structure of the sprayed leaves was not fundamentally changed but they were thicker and

stronger in some degree, while their life was lengthened. Apparently, treatment increased the chlorophyll content, and, correlated with this, was a rise in the assimilatory capacity, more starch being produced. Rise in transpiration was also observed. While the leaves were the organs most affected, a subsidiary stimulation occurred in the tubers, since the greater quantity of starch produced required more accommodation for its storage. In different varieties the ratio of tuber formation on treated and untreated plants was 19 : 17 and 17 : 16. In discussing the meaning of this stimulation these writers, following the custom then in vogue, were inclined to hold that it was due to a catalytic rather than to a purely chemical action, an idea similar to one which later on came much into prominence in connection with the work of Bertrand's school on manganese, boron and other substances.

The imputed increase in photo-synthesis seems to have met with approval and acceptance, but nevertheless it did not pass unchallenged. Ewert (1905) brought forward a detailed discussion and criticism of the assumption that green plants when treated with Bordeaux mixture attain a higher assimilation activity than untreated plants. His experiments were made to test the effects of differing conditions of life on plants treated in various ways, and his conclusions lead him to assert that "instead of the organic life of the plant being stimulated by treatment with Bordeaux mixture it is rather hindered."

While Frank and Krüger indicated a rise in transpiration when copper compounds were applied to the *leaves* as sprays, Hattori (1901) attributed part of the toxic effect of copper salts, when applied to the *roots*, to a weakening action on the transpiration stream, and he maintained that the toxic effect of the copper salts is therefore connected with the humidity of the air. No further confirmation or refutation of this statement has so far come to light.

In certain plants the application of cupric solutions as sprays causes a slight increase in the quantity of sugar present in the matured fruits. Chuard and Porchet (1902, 1903) consider that such a modification in the ripe fruit during the process of maturation occurs in all plants which ripen their fruits before leaf-fall begins. Injection of solutions of copper salts into the tissues of such plants as the vine causes more vigorous growth, more intense colour and greater persistence of the leaves; in other words the copper acts as a stimulant to all the cells of the organism. A similar effect is produced by other metals such as iron or cadmium. By injecting small quantities of cupric salts into the branches of currants an acceleration of the maturation of the fruits was caused, identical

with that obtained by the application of Bordeaux mixture to the leaves. If the quantity of copper introduced into the vegetable organism was augmented, the toxic action of the metal began to come into play. These investigators attributed the stimulus, as shown by the earlier maturation of the fruits, to a greater activity of all the cells of the organism and not to an excitation exercised only on the chlorophyll functions.

(b) *Effect of solutions of copper salts on leaves.*

Treboux (1903) demonstrated the harmful action of solutions of copper salts on leaves by means of experiments on shoots of *Elodea canadensis*. The activity of photo-synthesis was measured by the rate of emission of bubbles of oxygen. On placing the shoots first in water, then in $N/1,000,000$ copper sulphate ($\cdot 0000159\%$), there was a reduction from 20 to 15 or 16 bubbles in 5 minutes. On replacing in water there was an increase to 18, but not to 20, indicating a permanent injury. With $N/10,000,000$ copper sulphate there was little or no reduction in the number of bubbles. This experiment had an interesting side issue in that it was noticed that not only the concentration, but also the quantity of fluid was concerned in the toxic action, indicating that both the proportion and the actual amount of poison available play their part. For instance, with a shoot 10 cm. long in 100 c.c. solution the plants were only slightly affected by $\cdot 000015\%$ copper sulphate, but in 500 c.c. solution the shoots were killed after some days in $\cdot 0000015\%$ copper sulphate, a concentration only one-tenth as great.

While it is evident that copper sprays have a definite action upon green leaves, whether favourable or unfavourable, the question arises as to the means whereby the copper obtains access to the plant in order to take effect. Dandeno found that solutions of copper sulphate were absorbed by the leaves of *Ampelopsis*, forming a brown ring. Generally speaking inorganic salts in solution are absorbed through both surfaces of the leaves, whether the leaves are detached or not, provided the surrounding atmospheric conditions are favourable, the absorption being usually more ready through the lower surface. Dilute solutions applied in drops stimulate the leaf tissue in a ring, whereas if the solutions are concentrated the entire area covered by the drop is affected. Too concentrated solutions of copper sulphate applied to leaves caused scorching, but if this was avoided while the solution was still strong enough to cause a darkening of green colour after a time, Dandeno considered that

the action was probably of the nature of a stimulus to growth, and produced a better development of chlorophyll and protoplasm in the region where the tissues appeared dark to the naked eye, a conclusion which tallies very closely with that of Frank and Krüger.

Amos (1907-8) experimented to see whether the application of Bordeaux mixture affected the assimilation of carbon dioxide by the leaves of plants, and whether any stimulation was produced. Brown and Escombe's methods and apparatus were used and the summarised results indicate that the application of Bordeaux mixture to the leaves of plants diminishes the assimilation of carbon dioxide by those leaves for a time. The effect gradually passes off, whatever the age of the leaves may be. The suggestion is made that the stomata are blocked by the Bordeaux mixture, so that less air diffuses into the intercellular spaces and less carbon dioxide comes into contact with the absorptive surfaces. If this hypothesis is correct, the physiological slackening of assimilation is not due to the toxic action of the copper in the Bordeaux mixture, but to a mechanical hindrance due to blocking of the stomata.

III. EFFECT OF COPPER ON CERTAIN OF THE LOWER PLANTS.

On turning to the lower plants, especially to some species of fungi, one notices a striking contrast in their behaviour to that of the higher plants. Some species of fungi have the power of living and flourishing in the presence of relatively large quantities of copper compounds, or even of copper or bronze in the solid state. Dubois (1890) found that concentrated solutions of copper sulphate, neutralised by ammonia, which were used for the immersion of gelatine plates used in photography, showed white flocculent masses resembling the mycelium of *Penicillium* and *Aspergillus*, which grew rapidly and fructified in Raulin's solution, but which remained as mycelium in cupric solutions. The mould proved capable of transforming copper sulphate into malachite in the presence of a piece of bronze, but it was found that the presence of the latter was not essential for the conversion into basic carbonate. The same result was obtained if the culture liquid was put in contact with a body which prevented it from becoming acid, fragments of marble acting in this way. Copper sulphate solution in the presence of the mould produced a *green* deposit on the marble, while without the fungus the solution simply evaporated leaving a blue stain of copper sulphate.

Trabut (1895) found that on treating smutty wheat with a 2% solution of copper sulphate he obtained a mass of flocculent white mycelium, whose surface was soon covered with aerial branches bearing pale rose-coloured spores, and he gave the provisional name of *Penicillium cupricum* to the species. On preparing nutritive solutions by steeping a handful of wheat in water for 24 hours, and then adding various amounts of copper sulphate to them, *Penicillium* was found to vegetate quite well until the amount of copper sulphate reached $9\frac{1}{2}$ grams in 100 c.c., after which the seedlings with spores did not develop at all. De Seynes tested this *Penicillium* more exhaustively with different culture media under various conditions and decided that Traabut was right in only assigning the name *P. cupricum* provisionally, as the mould reverts to the form *P. glaucum* when seeded in a natural medium, indicating that *P. cupricum* has not an autonomous existence, but is *P. glaucum* which modifies the colour of its conidia under the influence of copper sulphate, in the same way that it often modifies them in other media. It is noticeable that the mycelium arising from the germination of conidia of *P. cupricum* in a normal medium has a very poor capacity for producing reproductive organs, but this diminished activity is attributed not to a special deleterious action of the copper sulphate but to the impulse given to the vegetative functions, at the expense of the reproductive, when the spores are seeded in a richer medium than the solutions of copper sulphate which serve as the soil for *P. cupricum*.

Ono found that *Aspergillus* and *Penicillium* are retarded in growth in the higher concentrations of copper sulphate, but that they are stimulated by weaker strengths. The range of stimulating concentrations is given as from .0015%—.012%, the biggest crop being obtained with both moulds in the strongest of these solutions. Hattori gives the optimum as being considerably lower for the two fungi mentioned, *Penicillium* being at its best in a solution of .008% and *Aspergillus* in .004%. A. Richter (1901) opposes this absolutely so far as *Aspergillus niger* is concerned. In his experiments copper appears invariably as a depressant, all concentrations from 1/150 to 1/150,000,000 giving growth below the normal, no stimulative action ever being observed. Zinc however proved to be a definite stimulant and in a mixture of copper and zinc salts in appropriate concentrations the toxic effect of the copper was completely paralysed by the stimulating action of the zinc, 1/200,000 zinc salt paralysing or overcoming the copper salt at 1/1125.

Ono states that the optimal quantity of such poisons as copper salts is lower for algae than for fungi, copper failing to stimulate algae at

dilutions which were the most favourable to the growth of fungi. Bokorny indicates that silver and copper salts work harm in unusually dilute solutions.

Attempts have been made to utilise the poisonous action of copper on algae in clearing ponds of those plants. Lindsay (1913) describes experiments carried on in a reservoir infested with *Spirogyra*. A quantity of copper sulphate sufficient to make a solution of 1/50,000,000 was found necessary to kill off the *Spirogyra*, but it is suggested that the solution was probably weaker before it reached the algae, owing to the currents of fresh water. *Anabaena* needed 1/10,000,000 before it was killed off, while *Oscillatoria* is less sensitive still, 1/5,000,000 usually representing the mortal dose, though 1/4,000,000 was necessary in some instances. Algae seem to be peculiarly sensitive to the copper sulphate, far more so than the higher plants, as *Nuphar lutea*, *Menyanthes trifoliata*, and *Polygonum amphibium* grew in the water unharmed by the addition of the poisonous substance. For some unexplained reason it seems that "the concentration of copper sulphate necessary to kill off the algae in the laboratory is five to twenty times as great as that needed to destroy the same species in its natural habitat."

Conclusion.

Altogether, after looking at the question from many points of view, one is forced to the conclusion that under most typical circumstances copper compounds act as poisons to the higher plants, and that it is only under particular and peculiar conditions and in very great dilutions that any stimulative action on their part can be clearly demonstrated.

CHAPTER IV

EFFECT OF ZINC COMPOUNDS

I. PRESENCE OF ZINC IN PLANTS.

THE presence of zinc in the ash of certain plants has been recognised for many years, especially in so far as the vegetation of soils containing much zinc is concerned. Risse, before 1865, stated that most plants when grown on such soils prove to contain greater or less quantities of zinc oxide. He states that the soil at Altenberg, near Aachen, is very rich in zinc, which rises as high as 20 % in places. The flora of the soil is very diversified and zinc has been determined qualitatively in most and quantitatively in some of the plants. *Viola tricolor* and *Thlaspi alpestre* are most characteristic under such circumstances, both showing such constant habit changes that they resemble new species, while other plants such as *Armeria vulgaris* and *Silene inflata* are peculiarly luxuriant. Risse's figures of the zinc content of these four plants may prove of interest. The figures are based on the dry weights, air dried.

Thlaspi alpestre, var. *calaminaria*.

Root	6.28 % ash,	0.167 % ZnO,	1.66 % ZnO in ash.
Stem	11.75 % "	0.385 % "	3.28 % " "
Leaves	11.45 % "	1.50 % "	13.12 % " "
Flowers	8.49 % "	0.275 % "	3.24 % " "

Viola tricolor.

Root	5.59 % ash,	0.085 % ZnO,	1.52 % ZnO in ash.
Stem	10.55 % "	0.065 % "	0.62 % " "
Leaves	9.42 % "	0.110 % "	1.16 % " "
Flowers	7.66 % "	0.075 % "	0.98 % " "

Armeria vulgaris.

Root	4.74% ash,	0.17% ZnO,	3.58% ZnO in ash.
Stem	5.37% „	0.02% „	0.37% „ „
Leaves	9.36% „	0.11% „	1.17% „ „
Flowers	6.08% „	0.07% „	1.15% „ „

Silene inflata.

Root	2.71% ash,	0.02% ZnO,	0.74% ZnO in ash.
Stem	11.43% „	0.22% „	1.92% „ „
Leaves			
Flowers			

Freytag (1868) carried out various experiments on the influence of zinc oxide and its compounds on vegetation, and found that all plants are capable of absorbing zinc oxide by their roots when grown on soils containing such oxide. Generally speaking the zinc is deposited chiefly in the leaves and stems, very little being found in the seeds, such minute traces occurring that he stated that the seeds must be harmless for men and animals. The general content of ZnO in plants is given as .5—1.0% of ash, except in the abnormal case of plants growing on calamine.

Lechartier and Bellamy (1877) demonstrated the presence of zinc in such food substances as wheat, American maize, barley and white haricots, but they failed to find it in maize stems and beetroot, so they cautiously concluded that if it does occur in the latter cases it must be far less in quantity than in the former. Hattensaur (1891) analysed the ash of *Molinia caerulea* and discovered the presence of copper, manganese, zinc and lead, zinc oxide forming .265% of the total ash, (.006% of the air dried plant).

Jensch (1894) observed that the flora on calamine soils was somewhat scanty, the chief plants that came under his notice being *Taraxacum officinale*, *Capsella Bursa-pastoris*, *Plantago lanceolata*, *Tussilago Farfara*, and *Polygonum aviculare*, all of which showed certain morphological peculiarities. Generally speaking the growth of these plants on the calamine soils was weak and poor, the stems and leaves being very brittle. Jensch found that the roots were deformed and showed a tendency towards a plate-like superficial spread of root. The leaves of *Tussilago* were uneven in shape and lacked the white hairs on the under side, the flower stalks were twisted, while the flowers themselves were a deep saturated yellow colour. The stems of *Polygonum aviculare* were much thickened at the nodes, the leaves weak and rolled in character, while the flowers were long-stalked, the calyces being usually of a

purple red colour. The following figures are given for the quantities of zinc carbonate (ZnCO_3) in the ash of these two plants:—

Tussilago Farfara.

Root	Leaf-stalk	Leaf-blade
2.51%—3.26% =1.629%—2.115%.	1.75%—1.63% 1.136%—1.058%.	2.90%—2.83% ZnCO_3 1.882%—1.836% ZnO .

Polygonum aviculare.

Root	Stem	Leaves
1.77%—1.93% =1.148%—1.252%.	2.25%—2.86% 1.46%—1.856%.	1.24%—1.49% ZnCO_3 .804%—.967% ZnO .

Other analyses of plants from zinc soils as against controls from normal soils indicated the high water and high ash content of the zinc plants, though the dry matter was low, and it is suggested that the increase of the ash may be connected with a stimulation caused by the zinc salts, unless it is due to phosphoric-acid hunger, since the calamine soils concerned are very deficient in phosphorus.

Javillier (1908 c) corroborated the early statements of Risse as to the presence of considerable quantities of zinc in certain species of *Viola*, *Thlaspi* and *Armeria*, and also he cited a list of other plants in which zinc occurs in some quantity. Javillier, however, is of opinion that zinc oxide, like the oxides of iron and manganese, is very common in plant ash, being present in all plant organs. Zinc is specially abundant in Coniferae, where it is probably characteristic, as is the presence of manganese in the ash and manno-cellulose in the wood. The so-called "calamine" plants show great powers of accommodation to large amounts of zinc.

Klopsch (1908) analysed 17 species of plants grown on soil in the vicinity of zinc works, and showed that the plants evidently absorb small quantities of zinc from their surroundings. He also regarded zinc as a normal constituent of certain plants.

II. EFFECT OF ZINC ON THE GROWTH OF HIGHER PLANTS.

1. Toxic effect.

(a) Toxic action of zinc salts alone in water cultures.

In comparison with copper little work has been done with regard to the action of soluble zinc salts alone on higher plants when grown in water cultures. Freytag (1868) stated that zinc salts must be very dilute if the plants are not to be harmed, and that for zinc sulphate the concentrations must not be more than 200 mg. per litre (=1/5000).

Baumann (1885) carried out further experiments and concluded that zinc salts are far more toxic than Freytag suspected, 44 mg. zinc sulphate per litre¹ killing plants of 13 species belonging to 7 families (Coniferae excepted). The various plants withstand the action of the zinc salts in different degrees, the same concentration killing off the species in different times. With the 44 mg. zinc sulphate the following results were obtained :—

Trifolium pratense	killed in 16 days
Spergula arvensis	" 21 "
Hordeum vulgare	" 30 "
Vicia sativa	" 31 "
Polygonum Fagopyrum	" 60 "
Beta vulgaris	" 76 "
Onobrychis sativa	" 194 "

With still less poison, 22 mg. zinc sulphate per litre, all the species mentioned were eventually killed with the exception of *Onobrychis sativa*, while 4.4 mg. zinc sulphate seemed to be harmless for all the plants tested except *Raphanus sativus*, which is evidently exceptionally sensitive to this toxic substance.

Jensen (1907) again indicated the poisonous action of zinc salts and also found that a relatively small reduction of toxicity was obtained by the addition of finely-divided quartz to the solutions.

(b) *Effect of soluble zinc salts in the presence of nutrients.*

Krauch (1882) grew various plants in the presence of nutrient solutions and quantities of zinc sulphate varying from .1 to .8 gm. per litre (= 1/10,000 to 8/10,000). Barley proved to be very sensitive, even to the weakest strength of the poison, as the plants soon showed reddish flecks, while all were dead within six weeks, the control plants without zinc remaining quite healthy. Certain grasses took longer to kill than barley, those with .4 gm. zinc sulphate per litre dying in about seven weeks, while 13 weeks elapsed before the others were killed. Even after this length of time the plants with .1 gm. zinc sulphate per litre still survived, although in a very sickly condition. With willow, again, even .1 gm. zinc sulphate per litre made the plants very sickly after four weeks, growth being weak, the leaves yellow, and the roots brownish. In this case the solutions were renewed, but the plants treated with zinc compounds were dead within eight weeks from the start, the controls being very healthy.

¹ 44 mg. $\text{ZnSO}_4 \cdot 7\text{H}_2\text{O}$ = 10 mg. Zn = 1/22,727 $\text{ZnSO}_4 \cdot 7\text{H}_2\text{O}$ approx.

The next year (1883) Storp repeated these experiments made by Krauch and corroborated his results fully. Barley and grasses (timothy and others) grown in solutions of zinc sulphate, both with and without nutrients, soon lost their green colour and became covered with rusty brown flecks, the barley dying within 14 days, and the grasses soon after. With willow, too, the toxic action was again manifested.

True and Gies (1903) showed that the addition of calcium salts in appropriate concentrations reduced the toxicity of zinc salts considerably, a result similar to that which they obtained for copper.

Recent experiments at Rothamsted have shown that zinc sulphate is very toxic to barley, though the plant is able to make some slight




Fig. 6. Curve showing the mean value of the dry weights of ten series of barley plants grown in the presence of anhydrous zinc sulphate and nutrient salts. (March 2nd—May 8th, 1911.)

amount of growth even in the presence of a solution of the anhydrous salt ZnSO_4 as strong as $1/5000$, rapid improvement occurring as the concentration decreases to $1/2,500,000$ or less (Fig. 6). On the whole the higher strengths of zinc sulphate are less poisonous to peas than they are to barley. At a concentration of 1 in $\frac{1}{4}$ or 1 in $\frac{1}{2}$ million in different experiments the growth was nearly as good as with the control plants, though it consistently lagged a little way behind until a dilution of $1/10,000,000$ was reached (Figs. 7 and 8). Incidentally it is very striking to see the desperate efforts that badly poisoned pea plants make to reproduce themselves. Growth of the roots is nearly always checked



Fig. 7. Photograph showing the action of anhydrous zinc sulphate on pea plants in the presence of nutrient salts. (Sept. 30th—Dec. 20th, 1912.)

- | | | |
|----|-------------|----------------|
| 1. | Control. | |
| 2. | 1/5,000 | zinc sulphate. |
| 3. | 1/10,000 | „ „ |
| 4. | 1/50,000 | „ „ |
| 5. | 1/100,000 | „ „ |
| 6. | 1/250,000 | „ „ |
| 7. | 1/500,000 | „ „ |
| 8. | 1/1,000,000 | „ „ |
| 9. | 1/2,500,000 | „ „ |

in advance of that of the shoots, probably on account of the contact of the roots with the poison. In the greater strengths of such poisons as zinc and copper sulphate root growth is checked from the outset, but usually a very little shoot growth is made, and one frequently obtains ridiculous little plants about an inch high bearing unhappy and diminutive flowers, which are occasionally replaced by equally unhappy and miniature fruits. The same thing has also been noticed when unsuccessful attempts have been made to introduce spinach as a test plant for water cultures.




Fig. 8. Curve showing the mean values of the dry weights of nine series of pea plants grown in the presence of anhydrous zinc sulphate and nutrient salts. (May 18th—June 28th, 1910.)

(c) *Effect of zinc compounds on plant growth when they are present in soils.*

As soon as the presence of zinc in members of the vegetable kingdom was established the question arose as to its effect upon both the plant and the soil.

Gorup-Besanez (1863) grew plants in soil with which 30 grams of metallic poisons such as CuSO_4 , ZnSO_4 , HgO , were intimately mixed with 30.7 litres ("cubik Decimeter") of soil¹. On analysing the ash of *Secale cereale*, *Polygonum Fagopyrum*, and *Pisum sativum* after six months growth he failed to detect the presence of zinc in any one of the three. As the results varied with different poisons on different plants he concluded that the absorption capacity of the various kinds of

¹ This is equivalent to about .1 % of poison.

soils for different poisons varies, that basic salts are absorbed, while the acid salts may pass completely through the soil in the drainage water.

Freytag (1868) stated that zinc is retained by the soil in the form of oxide, which is derived from dilute zinc compounds as they filter through the soil, by decomposition by the salts of the soil. For field earth the limit of absorption of zinc oxide from zinc sulphate is between 21 %—24 % of the earth.

F. C. Phillips (1882) corroborated Freytag's statement as to the absorption of small quantities of zinc by the roots of plants, but he states as a fact that both lead and zinc may enter plant tissues without causing any disturbance in the growth, nutrition or functions of the plants, a conclusion that is obviously incorrect or at least incomplete in view of later work on the subject. His choice of plants was certainly unusual, including geraniums, coleas, ageratums and pansies, the poison used being zinc carbonate.

Holdefleiss (1883) stated that in spite of a soil content of 2 % zinc the vegetation was not in any way harmed, clover fields and meadow lands on zinc soil presenting a normal appearance. This observation was quite inconclusive, as the author proceeds to say that of the plants that were able to absorb zinc salts without disadvantage the most luxuriant were the so-called zinc plants—the exceptions that prove the rule. Two years later Baumann showed that such insoluble zinc salts as the carbonate and sulphide in the soil cannot hurt plants. These salts are certainly dissolved to some extent by water containing CO_2 , but solution is hindered by the constitution of the soil. He also found that the various kinds of soil act differently upon zinc solutions, the absorptive power of pure humus soils ("reinem Humusboden") for zinc solutions being the strongest. Clay and chalk soils also decompose such solutions energetically, while poor sandy soils have only a weak power of absorption. This selectivity of absorption may account for the difference in the toxicity of zinc salts to plants in the various soils.

Storp (1883) experimented to determine the changes in the various characters of the soil by the action of zinc salts on it, and he makes the remarkable statement that in some soils the presence of zinc generates free sulphuric acid, which is particularly injurious to plant life. Grasses, young oaks and figs showed a decrease in dry weight, nitrogen and fat, as the quantity of zinc compounds increased in the water added to the soil. Both the quality and the quantity of the crop were adversely affected. This decrease in the dry weight due to the presence of zinc

was confirmed by Jensch later on, and also by Nobbe, Baessler and Will (1884), who state that both lead and zinc compounds work disadvantageously to vegetation even when they are present in such small quantities that the plants are outwardly sound, the harmful action appearing in the decrease of dry weight. Contrary to Baumann's opinion, zinc carbonate is said to be one of the salts that exercises this insidious poisonous action. Storp (1883) noticed that the direct poisonous action of zinc compounds is largely destroyed by their admixture with soil, but he suggests that a secondary cause of harm is introduced by the accumulation of insoluble zinc salts, so that the fertility of the soil is impaired to the detriment of the vegetation.

Ehrenberg (1908) throws out a suggestion that zinc is specially harmful to plant life when it occurs in conjunction with ammonia, but no further evidence has come to light.

(d) *Mode of action of zinc on plants.*

The reason for the toxicity of zinc salts when present in soil forced itself upon the attention of some of the early investigators in this field. Freytag (1868) put forward the hypothesis that the zinc oxide is partly or exclusively absorbed by the roots on account of the cell walls of the root being corroded by the very thin layer of zinc salts lying in contact with it—the same theory as has been held with regard to copper. He stated also that the quantity of zinc oxide taken up by the plant through its roots is strictly limited, not being proportional to the quantity occurring in the soil, but varying between narrow limits. Krauch (1882) found himself unable to accept another hypothesis which at one time found favour, i.e. that the zinc salts kill the plants by coagulating the protoplasm. If this were so, he argued, no plants at all could grow upon soils containing zinc, and he was content to leave the cause as one yet to be explained. Even at the present time, thirty years after, we know very little more about the physiological cause of the toxicity of zinc.

2. *Effect of zinc compounds on germination.*

In the course of his investigations on the influence of zinc on vegetation Freytag just touched upon the question of seed germination. According to his statement the presence of zinc oxide in the soil does not exercise much influence upon germination and the growth processes of plants. Little zinc is stored up in seeds and on this account seeds originating from plants containing zinc germinate quite normally and

do not seem to be affected by the peculiar nutritive conditions of the parent plants.

In certain cases light seems to have something to do with the harm zinc compounds work on plants. Storp found that when clover seeds were germinated in the dark on filter paper moistened with water containing .025 gm. ZnO per litre (added in the form of zinc sulphate) no deleterious action was observed. Barley seeds were soaked for four days in (a) distilled water, (b) water with .9 gm. ZnO per litre, which was frequently changed. These seeds were then placed in the dark on filter papers soaked respectively with water and with the solution containing ZnO. So long as no light was admitted, for a period of eleven days, germination was uniform in both sets, but directly the covers were removed the growth of the seeds with zinc ceased almost entirely, and they did not assume the green colour taken on by the unpoisoned seedlings. With maize the germination was retarded by zinc even in the dark, but the harmful action of light on the plants with zinc was again established. These results seem to indicate that the formation and activity of chlorophyll is impaired by the toxic agent, and this hypothesis is borne out by the fact that in many fungi and non-assimilating higher plants the toxic action of zinc is not evident.

Micheels (1906) approached the matter from a totally different standpoint, seeking to discover what influence the valency of a metal has upon the toxicity of its salts. In each of a series of experiments 1000 c.c. of $\frac{1}{2}$ decinormal solution of sodium chloride in pure distilled water were used, with the addition of varying strengths of calcium sulphate. Grains of wheat, which previously had been soaked in distilled water, were placed in the solutions, and it was found that the stronger the calcium sulphate solution (up to $\frac{1}{8}$ normal—the limit of experiment), the better the growth. The calcium sulphate was then replaced by salts of other bivalent metals, as zinc, lead and barium, with analogous results, the quantity necessary to obtain the maximum development varying with one and another; with zinc, $n/128$ gave the maximum. In this case the toxic action of both sodium chloride and zinc sulphate on germination were considerably reduced by their mutual presence—a result which fits in perfectly with what is known as to the masking effect of soluble substances upon toxic action. The same fact obtains in the animal kingdom, where Loeb and others have found that the toxicity of solutions of sodium chloride for marine animals is reduced by the introduction of salts of the bivalent metals.

3. Stimulation induced by zinc compounds.

While the toxic action of zinc on the higher plants is so obvious that it forced itself upon the attention of investigators at an early date, the question of possible stimulus is so much more subtle that it has only come into prominence during the last twelve years, during which time an extraordinary amount of experimental work has been done with regard to it. One investigator, Gustavson, was somewhat in advance of his time, for as long ago as 1881 he hinted at the possibility that zinc, aluminium and other substances might act as stimulants or rather as accelerators. He indicated that the rôle of certain mineral salts in the plant economy is to enter into combination with the existing organic compounds, the resulting product of the reaction aiding in the formation of yet other purely organic compounds which ordinarily require for their formation either a very high temperature or a long time—in other words, such a mineral salt acts as a kind of accelerator.

This work was apparently not followed up immediately, but it evidently contains the germ of the "catalytic" hypothesis of which so much has been made during recent years.

The work dealing with zinc as a stimulant to plant growth has yielded such various and apparently contradictory results that the question cannot yet be regarded as settled—it is even still more or less uncertain whether zinc compounds act as stimulants, or whether they are merely indifferent at concentrations below the toxic doses.

(a) Stimulation in water cultures.

True and Gies (1903) suspended seedlings of *Lupinus albus* for 24–48 hours with their roots in solutions of zinc sulphate and calcium sulphate ($m/256$)¹, and found that while zinc sulphate alone at $m/8192$ retarded growth, yet with $m/2048$ $ZnSO_4$ and $m/256$ calcium sulphate growth was more than twice as rapid as in controls grown in water, indicating a marked stimulation. The presence of the calcium exercised a definite ameliorating influence, reducing the toxicity of zinc to one-sixteenth at most. The hypothesis put forward is that interior physiological modifications are responsible for the observed differences in growth rate, the cell processes being so affected as to bring about different results on cellular growth—i.e. that where mixtures of salts are concerned growth rate represents the physiological sum of oppositely acting stimuli or of antagonistic protoplasmic changes.

¹ m probably = gram molecular weight.

Kanda (1904) found that peas were stimulated in dilute solutions of zinc sulphate in the absence of nutrients, the optimum concentration being between $\cdot 00000287\%$ and $\cdot 000001435\%$ (about 1 in 34,840,000 and 1 in 69,700,000), higher concentrations being poisonous when the solutions were changed every four days. Jensen (1907) stated that he obtained no stimulation at all with water cultures, even in a solution as dilute as $n/100,000$ (about 1 in 1,239,000), but he suggested that it was quite possible that in proper concentration the zinc sulphate might prove to be a stimulant.

Javillier (1910) grew wheat in nutritive solutions with quantities of zinc salts containing from $1/5,000,000$ — $1/250,000$ zinc, and found that the dry weight of the plant was increased in so far as the stems and leaves were concerned, though it remained uncertain whether a similar increase occurred in the grain.

A consideration of the Rothamsted experiments shows that up to the present time there is no conclusive evidence that zinc sulphate acts as a stimulant to barley grown in water cultures. As a general rule the growth of those plants with $1/5,000,000$ ZnSO_4 approximates closely to that of the controls. Beyond this the growth varies in different experiments. In some cases lower concentrations from $1/5,000,000$ to $1/50,000,000$ seem to cause some slight improvement in comparison with the normal, indicating a possible stimulus, but this improvement is not at all well marked. In other cases these great dilutions are apparently indifferent, neither a poisonous nor a stimulative action being exerted on the growth of the plant (Fig. 6). With peas some increase has been obtained with $1/20,000,000$, and although the rise is only slight, yet it is possible that it may indicate the setting in of a stimulus which would make itself more strongly felt with still weaker concentrations (Fig. 7).

(b) *Stimulation in sand cultures.*

While Jensen denied stimulation in wheat grown in water cultures even when the solutions were as dilute as $n/100,000$ zinc sulphate, yet he found increase of growth with the same plant in artificial soil (quartz flour) to which much stronger solutions of zinc sulphate, from $5n/10,000$ — $n/10,000$, had been added.

(c) *Increased growth in soil.*

Nakamura (1904) dealt with a few plants of agricultural importance, adding $\cdot 01$ gram anhydrous zinc sulphate to 2300 grams air-dried soil.

The marked individuality in the response of the various plants to the poison is very striking. *Allium* showed signs of increased growth throughout; *Pisum* was apparently improved in the early stages of growth, but when the dry weights were taken at the end of the experiment no increase manifested itself in the weights of the plants treated with zinc; with *Hordeum* the same quantity of zinc exercised a consistently injurious action. These results with peas and barley corroborate those obtained in the Rothamsted experiments with water cultures in that zinc sulphate proved to be less toxic to peas than to barley.

Kanda found that both peas and beans when grown in soil as pot cultures were improved by larger quantities of zinc sulphate than when they were treated as water cultures—a result in full accordance with current knowledge.

Wheat is evidently peculiarly sensitive to the effects of zinc compounds under differing conditions. Javillier (1908 c) pointed out that while wheat is very susceptible to the toxic action of zinc, yet it can benefit by the presence of sufficiently small quantities of the compounds of the metal. Rice is another cereal that is said to respond to the action of zinc sulphate, as Roxas, working in pot cultures with soil both with and without the addition of nutritive salts, obtained an acceleration of growth on the addition of $m/1000$ zinc sulphate, a quantity so remarkably great that it might be expected to act as a toxic rather than as a stimulant.

With phanerogams the zinc question is not only concerned with the effect of the metal upon germination, but also with its effect upon the later growth of the green plants, and on the physiological functions involving the construction of substances at the expense of mineral elements and the carbon dioxide of the air. Javillier holds that the indications are that zinc would prove to be profitable if applied to crops as a “complementary” manure.

4. *Direct action of zinc salts on leaves.*

Dandeno (1900) applied zinc sulphate in drops to the leaves of *Ampelopsis*, and found that the solution was not all absorbed by the leaf, but that a slight dark ring of a yellow colour was produced, and he was induced to think that some local stimulation was produced if the salt was presented in sufficient dilution.

Klopsch (1908) discussed the effect on plant growth of zinc derived from industries producing zinc fumes. Zinc oxide from the fumes is deposited on the leaves, and Klopsch stated that the rain and dew containing

dissolved zinc compounds find entrance to the tissues by way of the stomates and work injury to the plants. Against this, however, it must be remembered that these same fumes also contain other substances which are admittedly harmful to plant life, and so the deleterious effect may be partly or even chiefly due to these substances rather than to the zinc. Yet it is probable that at least some of the depreciation is due to the zinc. Treboux (1903) tested the effect of zinc sulphate on shoots of *Elodea canadensis*. If the shoots were placed in $n/100,000$ ($= \cdot 000016\%$) zinc sulphate no reduction of assimilation (as observed by counting the number of oxygen bubbles emitted per minute) took place, and replacement in water apparently had no effect either way. When however the shoots were placed in (1) water, (2) $\cdot 00008\%$ zinc sulphate, (3) fresh $\cdot 00008\%$ zinc sulphate, (4) water again, it was found that while the first solution of zinc sulphate had apparently no effect on assimilation, yet during the second immersion a gradual reduction in assimilation set in, which reduction was continued after the return to pure water, so that the toxic action of the zinc sulphate upon the shoots was clearly demonstrated.

III. EFFECT OF ZINC ON CERTAIN OF THE LOWER PLANTS.

Among the fungi, one species stands out in special prominence on account of the great amount of work that has been done on it with regard to its reactions to zinc salts. *Aspergillus niger* = *Sterigmatocystis nigra* van Tgh was used as a test plant by Raulin (1869), who evidently considered that zinc was an essential primary constituent of the food solutions of the fungi, $\cdot 07$ parts zinc sulphate being added to each 1500 parts of water. In his experiments he tested (1) ordinary nutritive solution, (2) nutritive solution with various salts added, as zinc sulphate, (3) nutritive solution and salts (as 2) and also powdered porcelain. (2) gave a crop of *Aspergillus* about 3.1—3.5 times better than (1), while (3) was even better still. Sulphate of iron also proved stimulating in its action, but Raulin stated that zinc cannot replace iron, as both are essential.

Ono (1900) determined the relation between the weight of the mould crop in grams and the quantity of sugar used up in the presence of varying amounts of zinc sulphate. The amount of sugar used was always greater in the crops with $\cdot 0037$ — $\cdot 0297\%$ zinc sulphate by weight than in the control crops, indicating a stimulation caused by zinc.

Richter (1901) carried out rather similar experiments. When grown in solutions without and with 1/700,000 gram molecule zinc sulphate the dry weights of the mould were practically the same for the first two days, then the dry weight of the zinc crop shot ahead for a day or two, a depression setting in on the fifth day. Without zinc a less increase took place, and a similar drop was noticeable about the sixth day. The conclusion drawn is that the stimulation due to the zinc occurs chiefly in the first few days and also that the rise in the sugar consumed is more rapid at first with the moulds treated with zinc. Concentrations above 1/600 are harmful, but in weaker solutions zinc is a definite stimulant.

Coupin (1903) re-investigated some of Raulin's work under more antiseptic conditions in order to see what substances were really needed by the mould and whether certain elements declared essential were really so. He concluded that iron and zinc are of no use in the nutrition of *Sterigmatocystis nigra*, but that the zinc retards the development of mycelium when food is abundant, killing it if it is badly nourished. This denial of stimulation was controverted by Javillier (1907) who re-tested Raulin's solution with extreme care, growing *Sterigmatocystis* in

- (a) normal Raulin's solution with zinc,
- (b) Raulin's solution without zinc.

The ratio of crops *a/b* varied from 2.3—3.1 in four experiments, vindicating the favourable action of zinc. With regard to the optimum value for zinc the mould seemed to be perfectly indifferent to the presence of medium quantities but very sensitive to extremes, the maximum weights being reached in dilutions between 1/10,000,000 and 1/250,000, while quantities above 1/25,000 were toxic in their action. At a dilution of 1/50,000,000 stimulation was still evident, though in a less degree than with the optimal concentrations.

Javillier maintains that zinc is fixed by the fungus, the whole of the zinc present in dilute solutions being taken up, only part being utilised in stronger solutions. The value of accordance between the quantity of zinc fixed and the quantity supplied decreases rapidly with increase of concentration. *Sterigmatocystis* is able to fix without harm a quantity of zinc equal to more than 1/1100 of its weight. Zinc is regarded as a catalytic element, as essential to the well-being of the plant as are the more obvious nutrients, carbon, sulphur, phosphorus, &c., in spite of the minute traces in which it occurs.

A few tests on yeasts made by Javillier showed that with vegetative yeasts zinc has a specific action, a consistent increase occurring in the amount of yeast formed and in the amount of sugar consumed as the quantity of zinc increased from 0—1/10,000,000—1/10,000. With ferment yeast, however, zinc exerted no appreciable action. These results lend force to the conclusion of Richards (1897) who carried out experiments on fungi with various nutritive media with the addition of certain salts of zinc, nickel, manganese, iron, &c. He considered that his general results showed that the fact of a chemical stimulation of certain metallic salts upon the growth of fungi is established, although it must not be considered without further investigations that all fungi react in the same degree to the same reagent.

Conclusion.

As matters stand at the present day, it appears that it is still uncertain whether higher plants grown in water cultures are susceptible to stimulation by zinc salts. If a stimulus does exist, it must be at exceedingly great dilutions, but further evidence is needed. In soil cultures, however, the fact of increased growth seems to be more firmly established, certain species responding to zinc salts when used as manure, though no increase has been obtained with other species. It must always be remembered that the action may be an indirect one. The soil is very complex in its constitution, and it is impossible to determine the exact action of the added poison upon it, so that a stimulating effect need not necessarily be due to a direct action of a substance upon the plant, but it may be the result of more favourable conditions for life induced by the action of the substance upon the soil.

Among the fungi the stimulation of *Aspergillus niger* by minute traces of zinc compounds seems to be well proved, though again it does not necessarily follow that all fungi will react in the same way to zinc.

CHAPTER V

EFFECT OF ARSENIC COMPOUNDS

I. PRESENCE OF ARSENIC IN PLANTS.

THE occurrence of arsenic as an occasional constituent of plants has been recognised for many years. Chatin (1845) found that if a plant were supplied with arsenical compounds at the roots arsenic was absorbed, but that it was distributed unequally to the various tissues. The greatest accumulation of the element was in the floral receptacle and the leaves, while it was scarce in the fruits, seeds, stems, roots and petals. E. Davy (1859) commented on the presence of arsenic in plants cultivated for food. He grew peas in pots and watered them for a short time with a saturated aqueous solution of arsenious acid, the application being then discontinued. The plants, apparently uninjured by the treatment, flowered and formed seeds. On analysis arsenic was readily detected in all parts of the plant, including the seeds. Other analyses revealed the presence of the element in cabbage plants (from pots) and turnips (from field), both of which had been manured with superphosphate containing some amount of arsenic. This absorption of arsenic by the roots of plants was further established by Phillips (1882).

Various physiological workers have pointed out that this element is frequently or usually present in animal tissues. Cerný (1901) reached the general conclusion that minimal traces of arsenic can occur in animal organisms, but that these play no part in the organism and indeed are not constant in their occurrence. Bertrand (1902) established its presence in minute quantities in the thyroid glands of the ox and pig, hair and nails of the dog, and the feathers of the goose. Gautier and Clausmann (1904) realised the constant presence of arsenic in human tissues and recognised that it must inevitably be introduced into the body with the food. This led them to estimate the arsenic present in various animal and vegetable foods, some of their results being given in the following table.

Arsenic per 100 parts fresh substance in μ gr. (=thousandth part of a milligram)¹.

Wheat (Victoria—complete grain)	·7
„ (from Franche Comté)	·85
White bread	·71
Whole green cabbage	·2
Outside leaves of cabbage	·0 (absent)
Green haricots	·0 „
Turnip	·36
Potatoes	1·12

Arsenic was also found in wine and beer and in considerable quantities in sea water and various kinds of salt. Since it cannot be found in some things even in the least traces, the authors conclude that it is incorrect to say that the element is always present or that it is essential to all living cells.

S. H. Collins (1902) found that barley is able to absorb relatively large quantities of arsenic. The plants were grown in pots on soil which originally contained a certain amount of the substance, and various combinations of arsenic acid, arsenious acid and superphosphate were added. Particulars and details are not given by the author, except that arsenic was detected by Reinsch's test in the grains from all the experimental pots, and in one case (not specified) in the upper and lower halves of the straw and in the threshed ears. The analyses of the soil at the close of the experiments showed the presence of 7—22 parts arsenious acid per million.

Wehmer (1911) quotes references to the occurrence of arsenic in *Vitis vinifera*. The element was detected in the ash of the must and its presence was attributed to treatment of the plants with arsenical compounds. In this connection it is interesting to note the observation of Swain and Harkins (1908), who, while acknowledging the absorption of arsenic from the soil by many plants, yet indicate that in the case of those plants which are exposed to smelter smoke the arsenic is deposited on the vegetation, and is not absorbed by the latter from the soil.

II. EFFECT OF ARSENIC ON THE GROWTH OF HIGHER PLANTS.

1. *Toxic effect.*

(a) *Toxic action of arsenic compounds in water cultures in the presence of nutrients.*

The poisonous action of arsenic on plants has long been recognised. Chatin (1845) gave accounts of tissues poisoned by strong arsenical

¹ 0 μ gr., 1=0·0001 mg.

solutions. Nobbe, Baessler and Will (1884) carried on water culture experiments with buckwheat, oats, maize and alder, and found that arsenic was a particularly strong poison for these plants. When small quantities of arsenious acid (As_2O_3) were added to the food solutions, growth was measurably hindered by a concentration of 1/1,000,000 As (reckoned as As). The element only appears in plants in very small quantity and can never be detected in notable quantities. The aerial organs show the effect of arsenical poisoning by intense withering, interrupted by periods of recovery, but eventually followed by death. It was also found that if plant roots were exposed to the action of arsenical solutions for a short period, say ten minutes, and then were transferred to normal food solutions, the action of the poison was delayed, but eventually hindering of growth or death occurred, according to the strength of the poison used in the first solution.

At the same time that Nobbe, Baessler and Will were establishing the great toxicity of the lower oxide of arsenic, Knop (1884) was carrying the matter a step further by comparing the action of arsenious and arsenic acid and their derivatives on plant growth. He established the fact that while arsenious acid is a strong poison for maize plants, arsenic acid in small quantities is not toxic to the roots and that the plants can produce flowers and fruit in its presence. Arsenic acid applied as potassium arsenate proved to be harmful to young maize seedlings if the solutions contained .05—1 gm. arsenic acid per litre ($= 1/20,000$ arsenic acid). If however the plants were allowed to form 10—15 leaves in a pure food solution and then when strongly rooted were transferred to a solution of .05 gm. arsenic acid per litre, they were found to grow strongly and develop big healthy leaves. Careful measurements indicated that the development is unchecked by the addition of the poison, though arsenic was determined in the ash of the treated plants.

Stoklasa (1896, 1898) tested the effect of arsenic compounds on plant growth with special attention to their comparative relation to phosphoric acid. He corroborated Knop's statement as to the greater toxicity of arsenious acid and arsenites in comparison with arsenic acid and arsenates, stating that 1/100,000 mol. wt. arsenious acid per litre causes definite trouble in plants, while with arsenic acid 1/1000 mol. wt. per litre first shows a noticeable toxicity. Water culture experiments were made with and without phosphoric acid, in each case with and without the addition of arsenic and arsenious acid. It was found that the arsenic acid was unable to replace the phosphoric acid, the plants decaying in the flower in the absence of the latter. In the complete absence of

Effect of Arsenic Compounds

phosphoric acid, arsenic acid causes a strong production of organic substances up to the flowering time. The following figures were obtained with maize:—

·002 gm. As_2O_3 with P_2O_5	2·84 gm. dry wt.
·005 gm. " " "	2·37 "
·01 gm. As_2O_3 " "	67·32 "
·40 " " " "	64·13 "
·03 " As_2O_3 without P_2O_5	39·98 "
·07 " " " "	42·13 "
normal solution " "	12·93 "
" " with "	65·84 "

Comparative experiments with the two arsenical oxides showed that varying times were required to kill different plants. Young seedlings were brought into solutions containing 1/10,000 mol. wt. arsenious acid (=·019 gm. As_2O_3 per litre) and the plants died in a very short time.

<i>Hordeum distichum</i>	46 hours
<i>Polygonum Fagopyrum</i>	84 "
" <i>Persecaria</i>	90 "

With ten times the strength of arsenic acid (1/1000 mol. wt. =·23 gm. per litre) the plants took much longer to kill.

<i>Hordeum distichum</i>	24·5 days
<i>Polygonum Fagopyrum</i>	40 "
" <i>Persecaria</i>	42 "

Various experiments have been carried on at Rothamsted with peas and barley. With arsenious acid on barley a depressing influence is manifest even at a concentration of 1/10,000,000, while no growth at all is possible with 1/10,000 and upwards. Apparently the toxic action on the root ceases at a higher strength than on the shoot, as with 1/1,000,000 and less the dry weight of the root remains practically constant. At this same strength the shoots look better than the controls, but this is not apparent in the dry weights (Figs. 9 and 10). With peas the depression is again evident to 1/10,000,000, but the plants are more sensitive to the higher concentrations, as no growth can take place in the presence of 1/250,000 arsenious acid (Fig. 11). A striking difference is observed with arsenic acid on barley, as apparently this does not act as a toxic even with such comparatively great concentrations as 1/100,000, though possibly the shoot is slightly depressed by this strength (Fig. 12).



Fig. 9. Photograph showing the action of arsenious acid on barley in the presence of nutrient salts. (March 16th—May 9th, 1911.)

1.	Control.		
2*.	1/50,000	arsenious acid.	
2.	1/100,000	"	"
3.	1/150,000	"	"
4.	1/200,000	"	"
5.	1/250,000	"	"
6.	1/500,000	"	"
7.	1/1,000,000	"	"
8.	1/5,000,000	"	"
9.	1/10,000,000	"	"
10.	1/25,000,000	"	"
11.	1/50,000,000	"	"

With sodium arsenite the dilutions were carried further, to $1/250,000,000$, but this still depressed barley to some extent (Fig. 13).




Fig. 10. Curve showing the mean value of the dry weights of ten series of barley plants grown in the presence of arsenious acid and nutrient salts. (March 16th—May 9th, 1911.)




Fig. 11. Curve showing the mean value of the dry weights of ten series of pea plants grown in the presence of arsenious acid and nutrient salts. (June 8th—July 21st, 1910.)

With peas the results vary somewhat in the different tests, the depression with $1/2,500,000$ and less being usually slight, though occasionally it is much more strongly marked (Fig. 14). In a single series with sodium arsenate barley was apparently unaffected by a concentration

Effect of Arsenic Compounds

of $1/1,000,000$, but from this point down to $1/250,000,000$ a constant depression showed itself, which was paralleled by a similar depression in




Fig. 12. Curve showing the mean value of the dry weights of ten series of barley plants grown in the presence of arsenic acid and nutrient salts. (Feb. 28th—April 24th, 1911.)




Fig. 13. Curve showing the mean value of the dry weights of ten series of barley plants grown in the presence of sodium arsenite and nutrient salts. (Feb. 10th—April 18th, 1913.)

the sodium arsenite series from $1/25,000,000$ to $1/250,000,000$, the curves grading downwards instead of up towards the normal. With peas sodium

arsenate has little or no action, though it is just possible that the rather irregular curves indicate a very slight depression below the normal throughout.

(b) *Toxic effect of arsenic compounds in sand cultures.*

Comparatively few tests seem to have been made as to the action of arsenical solutions in sand cultures. Stoklasa (1898) repeated his water culture work, using sand as a medium, and found analogous results by the two methods, i.e. that arsenites are far more toxic than arsenates, and also that the degree of toxicity of a salt varies with the plant to




Fig. 14. Curve showing the mean value of the dry weights of ten series of pea plants grown in the presence of sodium arsenite and nutrient salts. (June 27th—Aug. 10th, 1911.)

which it is applied, as was shown by the fact that different plants lived for varying times when treated with similar strengths of solution.

(c) *Toxic effect of arsenic when applied to soil cultures.*

Daubeney (1862) watered barley plants with a solution of arsenious acid, 1 ounce in 10 gallons, five times in succession, and found that the crop arrived at maturity about a fortnight earlier than the untreated part of the crop, though the amount harvested was rather less. With turnips four waterings had no effect upon the time of maturity, but again the crop was slightly decreased. The analyses made indicated that no arsenic was taken into the tissues, but that it merely adhered to the external surfaces.

Gorup-Besanez (1863) mixed 30 grams arsenious acid with 30·7 litres¹ soil, growing two plants on this quantity of earth. Most of his experimental plants (*Polygonum Fagopyrum*, *Pisum sativum*, and *Secale cereale*) developed normally, but *Panicum italicum* died soon after the plants appeared above the surface, the leaves being very badly coloured. Analyses by Marsh's test showed no trace of arsenic in 20 grams dry matter from *Secale cereale*, but in 148 grams *Polygonum Fagopyrum* the presence of arsenic was evident, though the mirror formed was weak. With such a large proportion of arsenious acid in the soil it seems hardly conceivable that the plants were not injured to some extent, and also it is probable that with more careful analyses arsenic would have been detected in those instances in which its presence was denied. Yet it must be remembered that Davy (1859) had treated pea plants in pots with a *saturated* solution of arsenious acid for a short time and had stated that the plants were uninjured. Thus both Gorup-Besanez and Davy concur in the opinion that *Pisum sativum* is indifferent to relatively large quantities of arsenious acid when presented in the soil, whereas the Rothamsted experiments show that in water cultures the plant is extremely sensitive even to minute traces of the substance. It is possible that the arsenic in the solution added to the soil enters into combination with other substances, forming insoluble compounds, thus being removed from the sphere of action and rendered unable to affect plant life. If this be so, the apparent immunity of certain plants to arsenious acid is explained. F. C. Phillips (1882), in his experiments on various flowering plants, such as geraniums, coleas and pansies, found that compounds of arsenic in the soil exercised a distinct poisoning influence, tending, when present in large amount, to check the formation of roots, so that the vitality of the plant was so far reduced as to interfere with nutrition and growth, or even to kill it outright. He also stated that traces of arsenic were found in all the plants grown upon the poisoned soil.

In this connection it is interesting to note that a certain proportion of arsenic is frequently present in the superphosphate used as manure. In view of the known toxicity of arsenical compounds to plant life the question arose as to whether superphosphate manuring would exercise a detrimental influence on account of its arsenic content. Experiments carried out by Stoklasa (1898), however, indicate that there is not sufficient arsenic in maximum doses of superphosphate to exercise a toxic action in the field.

¹ 30 grams arsenious acid to 30·7 "cubik Decimeter" soil = about ·1 %.

(d) *Physiological considerations.*

The physiological action of arsenic compounds on plant life early attracted the attention of investigators. Chatin (1845) put forward some rather curious and unexpected considerations with regard to this action. He stated that the effect of arsenic on plant growth is determined more by the constitution and temperament of individual plants than by their age, and that apparently difference in the sex of plants is of no significance. The chief determining agent, however, is the species, and Chatin found that as a general rule Cryptogams are more sensitive than Phanerogams, and Monocotyledons than Dicotyledons, as is shown by the fact that under treatment the former perish first. Some extreme exceptions exist, though, as *Mucor mucedo* and *Penicillium glaucum* will grow on moist arsenious acid, whereas leguminous plants are killed by an arsenical solution in a few hours. Chatin held the view that elimination of the poison succeeded its absorption, and that this elimination is complete if the plant lives long enough. Here again the species exerts a great influence on the excretory functions of the plants. Lupins and Phaseolus are presumably able to eliminate in six weeks all the arsenious acid they can absorb without dying. Most Dicotyledons need 3—5 months, while Monocotyledons retain traces of poison for six months after its absorption. Lichens are said to eliminate it more slowly still. Again, woody species are longer in freeing themselves than herbaceous, and young plants carry out the elimination more easily than old plants. The excretory function is influenced by other physiological factors such as dryness and season. The toxic effects and elimination are supposed to act inversely and parallel, the absorbed arsenious acid combining with alkaline bases, making a very soluble salt which is excreted by the roots. Calcium chloride is given as the antidote to arsenious acid, all soluble acid being "neutralised" by it. This view of the elimination of arsenic apparently did not gain much support, as no further references to the matter have so far come to light. In view of the work of some modern investigators (Wilfarth, Römer and Wimmer) on the excretion of salts by plant roots, the idea may prove of fresh interest. Chatin also found that moving or still air influenced the working of the poison, indicating that the external physical conditions affect the toxic action considerably. Nearly forty years later Nobbe, Baessler and Will found that, if transpiration were hindered by placing plants in a dark or moist room, it was possible to keep

the plants turgescient in arsenic solutions for a long time without thereby increasing the toxic effect later on. The poisonous action proceeds from the roots, of which the protoplasm is disorganised and the osmotic action hindered. Finally, in the presence of sufficient of the poison, the root dies without growth.

Stoklasa (1896, 1898) again found that phanerogamic plants can withstand arsenic poisoning for some time in the dark or in CO_2 -free air, provided that glucose is given in the food solution. The arsenic poisoning is at its maximum during carbon assimilation by means of chlorophyll. The toxic action of arsenious and arsenic acids, especially in phanerogams, is due to injury to the chlorophyll activity. The destruction of the living molecule is far more rapid in the chlorophyll apparatus than in the protoplasm of the plant cell.

Thus it seems that the physiological cause of the toxicity of arsenic is partly a direct action on the root protoplasm, whereby its osmotic action is hindered, and partly a detrimental action upon those functions which are directly concerned with the elaboration processes of nutrition.

2. *Effect of arsenic compounds on germination.*

In view of the great toxicity of arsenic to plants in their various stages of development, one would naturally expect to find a similar action with regard to the germination of the seeds. Davy (1859) casually mentioned cases in which watering with arsenical solutions or dipping seeds in arseniated water prevented germination. Heckel (1875) found that arsenious acid checks germination and kills the embryo at relatively feeble doses, '25 gm. to 90 gm. water¹. Guthrie and Helms (1903-4-5) carried out a systematic series of experiments to test the effect of arsenic compounds upon different farm crops. Various amounts of arsenious acid were added to soil in pot experiments, and the seeds of the several crops were then sown. With barley, wheat and rye 0.10% arsenious acid had little or no effect on germination, while an increase in the poison exercised a retarding action. Maize could withstand 0.40% arsenious acid without retardation being perceptible. The aftergrowth with the different crops varied considerably. The wheat plants with 0.10% arsenious acid grew all right at first, but later on they developed weakly. The toxic action increased rapidly as the strength of the poison rose in the different

¹ In the present state of our knowledge such a concentration seems relatively strong!

pots. Barley proved even more sensitive than wheat, for even 0.05% arsenious acid affected the growth adversely. After a time the plants with 0.05—0.06% recovered and grew strongly, though not so well as the controls, but those with 0.10% practically died off. Rye behaved in the reverse way from wheat. The plants with 0.10% were slightly checked at first but later recovered and made growth quite equal to the check plants. Growth was stunted with 0.20% arsenious acid, and the plants were killed with 0.30%, so that rye is far less sensitive than barley. With maize the growth was slightly affected with 0.05% As_2O_3 , and increasingly so with greater quantities. It was also found that the action of 0.8% As_2O_3 was strongly adverse to the germination of all plants, and that above this strength germination was altogether prevented.

The results show very clearly how impossible it is to draw any general conclusions with regard to the action of arsenic compounds on plants, as they emphasise the strong individuality of the species in their reaction.

3. *Do arsenic compounds stimulate higher plants?*

The question of stimulation due to arsenic does not seem to have engaged the attention of investigators to any extent. Water culture experiments at Rothamsted have so far yielded negative results, and no stimulation has yet been obtained with any plant, with the possible exception of white lupin with sodium arsenite. In a single series a stimulus was suggested, beginning to make itself felt at 1/500,000, rising to an optimum at 1/10,000,000. No stress can be laid on this result, as it is never safe to draw any certain conclusions without several repetitions of the same experiment. With arsenic acid on barley a possible stimulus is sometimes indicated to the eye, the plants being fine and of a particularly healthy dark colour, but this is not corroborated by the dry weights. Additional tests were made with peas and barley, treated with sodium arsenite and arsenate, the dilutions being carried down to 1/250,000,000, but no evidence of stimulus was obtained, so that it hardly seems possible that arsenic can act as a stimulative agent for these two plants when grown in water cultures. It had been thought that the failure to find a stimulation point hitherto might be due to the too great concentration of the toxic substance rather than to the actual inability of the poison to stimulate, but this hypothesis must now be dismissed so far as these plants are concerned.

III. EFFECT OF ARSENIC COMPOUNDS ON CERTAIN OF THE LOWER PLANTS.

1. *Algae.*

Loew (1883) was sceptical concerning the specific toxicity of arsenic for plant protoplasm. He was convinced that arsenic and arsenious acid were poisonous to algae, not because of their specific character as arsenical compounds, but because of their acid nature, algae being peculiarly sensitive to any acid, and he maintained that these substances were not more poisonous than vinegar or citric acid. He placed various species of *Spirogyra* in solutions of .2 gm. potassium arsenate per litre water (1/5000), and found that the algae grew well without making any abnormal growth in a fortnight, showing hardly one dead thread. Some of this alga was then transferred to a 1/1000 solution of potassium arsenate. This suited it excellently and it increased and the appearance under the microscope was very fresh and strong, which was attributed more to the potash than to the arsenic acid. Loew maintained that for the lower animals and for many of the lower plants arsenic in the form of neutral salts is not a poison. When the differentiation of the protoplasm into certain organs reaches a specific degree in the higher plants, then the poisonous action of the arsenic compounds comes into play.

Knop (1884) found that certain unicellular green algae grew luxuriantly in a neutral solution supplied with potassium arsenate. Bouilhac (1894) concerned himself chiefly with the possibility of the replacement of phosphates by arsenates. He recognised that the influence of arsenic is not the same on all species of plants, so he confined his attention to certain of the algae. *Stichococcus bacillaris* Naegeli was found to live and reproduce itself in a mineral solution containing arsenic acid. Even in the presence of phosphoric acid the arsenic acid favours growth, the best dose being about 1/1000. The arsenic acid is capable of partly replacing phosphoric acid. Other species of algae, *Protococcus infusionum*, *Ulothrix tenerrima*, and *Phormidium Valderianum* invaded the original culture of *Stichococcus* from the atmosphere, but with no arsenic or phosphoric acid their development was poor. The jars with arsenic compounds were invaded by still more species which grew strongly. Under these conditions it is evident that these algae are capable of assimilating arsenic, and the addition of arsenic acid to a solution free from phosphoric acid is sufficient to enable these algae to live satisfactorily, the arsenates in this case replacing the phosphates. Ono (1900) found that algae are favourably influenced by small doses of

poisons, the optimal quantity for algae being lower than that for fungi. *Protococcus* showed a possible stimulus when grown in concentrations of potassium arsenate varying from $\cdot 00002$ — $\cdot 0005\%$. This possible stimulus is interesting in view of the failure to observe stimulation in higher plants by minute traces of arsenic.

2. Fungi.

The effect of arsenic on fungi is of special interest in that it has a direct bearing upon hygienic and commercial interests. Gosio (1892, 1897, 1901) found that certain of the fungi, *Mucor mucedo* and *Aspergillus glaucum*, will grow on various arsenic compounds and exercise a reducing influence on them. These moulds attack all oxygen compounds of arsenic including copper arsenite, and develop arsenical gases. Sulphur compounds of arsenic are not influenced by these fungi. The same moulds would, if cultivated in soil containing arsenic, develop hydrogen arsenide. *Penicillium glaucum* has such a strong and definite action on arsenic compounds that he states that there is no doubt of the possibility of poisoning by arsenical gas in a room hung with paper containing arsenic. The compounds are so extraordinarily potent that if a mouse is placed in a vessel in which the mould is strongly developed in the presence of arsenic, it dies in a few seconds. *Penicillium brevicaulis* uses the element in its development as a food substance. If material containing arsenic is placed in contact with dead fungi no reaction occurs. The life activity of the mould is evidently necessary for the reaction by which the arsenic-containing gases are liberated. Csapodi (1894) put forward the earlier results of Gosio and noted that the so-called arsenical fungicides do not only fail to kill the mould fungi but actually favour their development. This action explains why wall-paper containing arsenic is so disadvantageous in a room. Abba (1898) severely tested Gosio's method of detecting arsenic by means of growths of *Penicillium brevicaulis*, whereby arsenic gases are liberated, vindicating the method completely, and establishing the test as an exceptionally delicate one. Segale (1904) applied the same method to the detection of the presence of arsenic in animal tissues.

Ono (1900) grew *Penicillium* cultures with solutions of potassium arsenate and found no important differences either of depression or stimulation. Orlowski (1902-3) stated that small doses of arsenic ($1/1000$ — $1/100\%$ Sodium arsen—¹) stimulate the growth of *Aspergillus*

¹ The exact compound is not specified in the abstracted paper, $1/1000$ — $1/100\%$ Natr. Ars. being given.

niger, larger doses up to 1/8 % retard growth, while 1/6 % kills. Spores of the fungus taken from soil containing arsenic are said to possess an immunity against arsenic, in that they germinate in the presence of an arsenic content which rapidly kills control fungi. This immunity is not specific for arsenic, but extends also to other poisons. The chemical composition and water content are not altered.

Conclusion

The toxic effect of arsenic upon higher plants is much more marked with arsenious acid and its compounds than with arsenic acid and its derivatives. No definite evidence of stimulation has yet been obtained with any arsenic compound, however great the dilution at which it is applied. With certain algae a stimulus may occur, and it is possible that arsenic acid is capable of replacing phosphoric acid to some extent under certain conditions. With fungi the toxic effect of great concentrations is marked with certain species, but there are others which are capable of living happily on arsenical compounds and of liberating highly poisonous arsenic gas.

CHAPTER VI

EFFECT OF BORON COMPOUNDS

I. PRESENCE OF BORON IN PLANTS.

THE first claim to the discovery of boron in plants was put forward in 1857 by Wittstein and Apoiger, who carried out investigations on the Abyssinian *Saoria* (seeds of *Maasa* or *Maessa picta*, N.O. Primulaceae¹). In the course of analyses a crystalline mass was obtained which was found to contain chlorine, phosphoric acid, lime, and boric acid. The discovery apparently attracted little attention and for about another thirty years the matter was again allowed to sink into oblivion. Then it came to the front again, and from 1888 onwards one investigator after another demonstrated the presence of boron in various plants.

In 1888 Baumert detected boron in French, German, and Spanish wines without exception, while E. O. von Lippman (1888) demonstrated it in sugar must and also in the leaves and root of the sugar beet. In the latter case the reactions were so definite that the presence of more than a minimal amount of boric acid was conjectured.

Crampton (1889) tested various fruits, but while he found boron in every part of the watermelon, he could get no reaction with apples or with certain samples of sugar cane. He predicted, however, that the occurrence of boron would prove to be more general in the plant kingdom than had previously been supposed. The next year (1890) Hotter extended the work on fruits, testing for boron in the fruits, leaves, and twigs of certain plants, and finding it in the apple, pear, cherry, raspberry, fig, and others. His results indicated that fruits are relatively rich in boron. Later on (1895) Hotter carried his experiments further, and he stated that stone fruits are richer in boric acid than are berries and pomes. The accumulation of boron is in the fruit itself, the other parts of the plant containing little. The quantities of boric acid found in the ash of the various fruits ranged from 58% in the "Autumn

¹ According to Engler's classification this plant belongs to N.O. *Myrsinaceae*.

signs of poisoning in that, even with the weakest strengths, the lower leaves were flecked with brown, especially at the edges, while with the greater strengths the lower leaves were dead and the flecking had extended to the upper leaves. In eleven days from the start the plants with 1/1000 boric acid were completely dead, while the other plants showed more or less signs of poisoning. The dry matter and ash decreased steadily with the increase in the boric acid, while the boric acid per 100,000 parts of dry matter increased steadily from 8 to 557 parts. Similar experiments were carried on with potassium borate and with borax; the results showed that, weight for weight, borax is less toxic than potassium borate, which in turn is less toxic than boric acid, while at a strength of 1/100,000 there is little to choose between the three poisons. Similar results were obtained with maize; plants treated with boric acid or potassium borate yielded about 2300 parts boric acid in 100,000 parts dry matter. The general conclusion arrived at by Hotter was that the effect is not so much that of a general poisoning as of a bleaching of parts of the leaf, mere traces of boron being harmless. The cause of injury is local inhibition of assimilation and killing of roots in stronger concentrations. Increase of the strength of boron raises the toxicity until 1/1000 practically inhibits increase in dry substance. The boron was found to be fairly evenly distributed through sound and affected organs.

Kahlenberg and True (1896) worked with seedlings of *Lupinus albus* L., limiting their experiments to those of 15—24 hours in duration. Various combinations of boron and other substances were tested. With boric acid alone 2/25 gram molecule per litre killed the plants, with 1/25 they were apparently just alive, while 1/100 and less had no injurious effect. Boromannitic acid was possibly more poisonous than the boric acid, while a combination of boric acid and cane sugar proved slightly less toxic. The short duration of these experiments limited their scope considerably, as with certain concentrations the toxic action would not become evident within the prescribed limits of time.

Agulhon (1910 a) worked with sterile nutrient solutions, and found that the higher strengths of boric acid hindered growth, 200 mg. boric acid per litre rendering growth impossible. He supported Hotter's idea that the toxic action affects the roots and the formation of chlorophyll, and he stated that the plants are less green as the dose of boron increases, plants growing in doses of above 10 mg. per litre being yellowish. In other experiments he found that




Fig. 16. Photograph showing the action of boric acid on pea plants in the presence of nutrient salts. (Sept. 30th—Dec. 20th, 1912.)

- | | | |
|----|---------------|-------------|
| 1. | Control. | |
| 2. | $1/5,000$ | boric acid. |
| 3. | $1/10,000$ | " " |
| 4. | $1/25,000$ | " " |
| 5. | $1/50,000$ | " " |
| 6. | $1/100,000$ | " " |
| 7. | $1/250,000$ | " " |
| 8. | $1/500,000$ | " " |
| 9. | $1/1,000,000$ | " " |

at 100 mg. boric acid per litre life seems impossible for the plant. The roots seem to be more adversely affected by toxic doses than do the shoots. In control plants Agulhon determined the stem/root ratio as 6, with a little boron as 7, while the ratio rose to 13 as the dose of the poison increased to 50—100 mg. boron per litre.

The Rothamsted experiments show that boric acid is definitely poisonous to barley down to a strength of $1/250,000$ (Fig. 15), the depressing effect frequently being evident at much smaller concentrations, while peas can withstand far more of the poison, the limit of toxicity being about $1/25$ — $1/50$ thousand (Fig. 16). With the greater strengths of poison the lower leaves of both barley and peas are badly damaged. In barley the leaves turn yellow with big brown spots, giving the leaves




Fig. 15. Curve showing the mean value of the dry weights of ten series of barley plants grown in the presence of boric acid and nutrient salts. (May 1st—June 20th, 1911.)

a curious, mottled appearance, while with peas the poisoning seems to begin at the tip and edge of the leaves, spreading inwards, without, however, showing the large spots as in barley. So far as chemical tests go at present, it is very probable that boron is deposited in the leaves in the same way as manganese, and that this is the cause of the degeneration. As with manganese, the lower leaves are attacked first, and the trouble spreads upwards, one leaf after another being involved. These observations fit in very well with those of Hotter, and the hypothesis of direct boron poisoning gains support from the fact that in dilutions which produce stimulation of the shoot the leaves show hardly any sign of dying off, even after prolonged growth in the solutions. With barley the effects of boron can be seen in the leaves

in concentrations as low as $1/2,500,000$, and it may be significant that this is the point at which the depressant action of boric acid entirely ceases in many cases.

Tests with white lupins gave no conclusive results, as for some reason it proved very difficult to get satisfactory plants in water cultures. When they are grown under such conditions the roots always tend to get more or less diseased and covered with slime, probably fungal in nature. In the presence of much boric acid the roots remain in a much healthier condition, which suggests that the acid has in this case a strong antiseptic action, and protects the roots. With high concentrations the lower leaves of the plant are badly affected, just as with peas and barley, turning brown and withering at an early date. Various experiments have been made with yellow lupins, but these again are very difficult to grow well in water cultures, as they are apt to drop their leaves for no apparent reason. Generally speaking, the evidence goes to prove that boric acid is toxic down to a concentration of about 500 parts in 25 million. It is difficult to get a true control with which to make comparisons as the plants without boric acid are encumbered with the slime on their roots, which naturally interferes with normal growth, while the plants in the presence of boric acid have the unfair advantage due to the probable antiseptic action of the boron. The effect of the boron poisoning is again evident in the dying off of the lower leaves, which become flaccid and drooping and finally drop off. The lupins grown with boron are very active in the putting forth of lateral roots, so much so that the cortex of the roots is split along the line of emergence of the laterals, which are very numerous and crowded.

(b) *Toxic action of boron compounds in sand cultures.*

Agulhon (1910 a) moistened 2 kgm. pure sand with 500 c.c. nutritive solution for each pot, and boron was added at the rate of 0, 0.1, 1, 10, and 50 mg. boric acid per litre of nutritive solution. Twenty wheat seeds were sown in each pot, and after twelve days the healthy plants in the first four pots were 6—8 cm. high, but those with the maximum amount of boron showed yellowish leaves only 3 cm. long. After three months' growth the plants were harvested, when those with most boron were found to have died after making about 10 cm. growth. The toxic doses in sand proved to be weaker than those in water cultures, probably because evaporation from the surface of the sand caused concentration of the poisonous liquid.

(c) *Toxic action of boron compounds in soil experiments.*

Long before any experimental work was done with boron in water cultures, the poisonous properties of the substance were recognised with regard to plants growing in soil. Peligot (1876) grew haricots in porous earthenware pots, the plants being watered by rain and by solutions, each containing about 2 grams per litre of such substances as borax, borate of potassium, and boric acid, other pots receiving various fertilisers, as potassium nitrate, sodium nitrate, &c. This quantity of boron completely killed off the plants receiving it, whether it was applied as free or combined boric acid, while the fertilised plants completed their development well. On this account the deleterious action was attributed to the boric acid and not to the sodium or potassium base supplied. Peligot hinted at the improbability of a substance like boron, which is so poisonous to plants, being really innocuous to human beings when it is used as a preservative for foods.

Nakamura (1903) also found that borax is harmful in pot cultures if present in large quantities, 50 mg. borax per kgm. of soil exerting a very injurious influence, while even 10 mg. per kgm. did some damage. Agulhon (1910 c) found that the toxic doses of boric acid in soil cultures approached those in nutritive solutions rather than in sand cultures, a phenomenon that he attributed to the fact that the boric acid was fixed by the soil, probably as insoluble borate of calcium, so that the surface concentration obtained with sand cultures was avoided. He found that the ash of plants grown with excess of boron contained more than the normal amount of boron, while the weight of ash per 100 dry matter was also increased. He concluded that the plant thus suffers an over-mineralisation and in consequence an augmentation of its hold on water, so that the fresh weight of the plant may indicate a more favourable action of the boric acid than does the dry weight. Other investigators (Fliche and Grandeau 1874) had found the same increase in the proportion of ash in chestnut trees grown on too calcareous soil, so Agulhon concluded that one is here dealing with a general reaction of plants to an excess of a useful element.

Other experiments were carried on in the open field, maize being grown on control plots and on plots receiving 2 gm. boron per square metre. At first the latter plants were behind, the dose being too strong. Eventually, however, they pulled up level and the dry weights from the two plots proved to be nearly the same, the fresh weights being identical. Maize is evidently far less sensitive to boron poisoning than

are peas and oats, for with these one-half the original amount of boron (= 1 gm. per sq. metre) proved toxic.

Interesting results were obtained (Agulhon 1910 a) by repeated experiments with the same soil containing boron. It was found that sand or soil containing a proportion of boron which is lethal or toxic to a first culture will allow much better growth with a second and subsequent crops. Repeated experiments on the same soil may show the change from a lethal dose to a toxic one, thence to an indifferent and finally to an optimum concentration. Furthermore (Agulhon 1910 b) the very plants may accustom themselves to greater quantities of boron, the increased power of resistance being transmitted. He concluded from his experiments that the progeny of the second generation of maize were able to withstand quantities of boron that were toxic to control plants¹. Agulhon once again emphasised the fact that for toxic doses of boron the first symptom is the more or less marked disappearance of chlorophyll, though the aerial parts are not affected so soon as the roots.

2. *Effect of boron compounds on germination.*

One of the first indications that boron compounds affect the germination of seeds was given by Heckel (1875) who found that germination was retarded for 1—3 days by weak solutions of borates (.25 gm. to 20 gm. water), and was stopped altogether by stronger solutions (.60 gm. to 20 gm. water). Archangeli (1885) tested the germination of a variety of seeds of Leguminosae, Gramineae, and of *Cannabis*, *Iberis*, *Raphanus*, *Collinsia*, and *Linum* in the presence of boric acid. The seeds were placed in bowls with solutions of .25, .5, and 1 % boric acid at temperatures ranging from 16°—23° C. The bowls were covered with glass plates to prevent evaporation and consequent increase of concentration, controls in spring water being dealt with under similar conditions. 1 % boric acid was found to check germination altogether, and the weaker the concentration the less was the process hindered. Morel soaked seeds of haricots and wheat in various solutions of boric acid, and found that germination was generally hindered or inhibited. The deleterious action diminishes as the strength of the solution or the time

¹ "Il apparaît donc que les graines fournies par des plantes ayant crû en présence d'une quantité de bore élevée présentent une accoutumance vis-à-vis de cet élément; les plants auxquels elles donnent naissance semblent non seulement faire un meilleur emploi des petites doses de bore qui leur sont offertes, mais encore supportent les doses toxiques plus facilement que les plants témoins, issus de graines non accoutumées."

of contact diminishes, but solutions of the same concentration do not act equally on all seeds. Boric acid and borax proved to be similar in their action qualitatively.

The deleterious effect of strong doses of boric acid on germination was confirmed by Agulhon (1910 a), the higher quantities (above 10 mg. boric acid per litre) retarding germination of wheat.

3. Does boron stimulate higher plants?

Of recent years a few investigators have thrown out hints as to the stimulant action exerted by boron compounds on plants. Roxas indicated that M/100,000 (M = molecular weight) of boric acid exercised a favourable action on rice. Nakamura (1903) tested the point by means of pot cultures. Peas and spinach plants were grown in soil which received 1 and 5 mg. borax per kgm. With peas the 1 mg. exerted evident stimulant action, as determined by the increase in height of the shoot over that of the control, 5 mg. seeming to be slightly depressant in action. With spinach a stimulation was observed both in weight and height with a dose of 5 mg. borax per kgm.

	Average weight	Average length of leaves
5 mg. borax	10.35	38.2
Control	7.2	34.0

Agulhon (1910 c and d) took the matter up still more definitely and made many tests of various kinds, in water, sand and pot cultures.

(a) Water cultures.

His water cultures were made under sterile conditions, the seeds when possible being sterilised with corrosive sublimate, the germinating apparatus being also sterilised. With wheat a stimulant action was evident, maximum growth being obtained with between 2.5 and 10 mg. boric acid per litre, though the dry weight increase did not quite keep pace with that of the fresh weight, a fact to which previous reference has been made. The chief improvement is in the root, the stem/root ratio falling to 5, as against 6 in the control series. Visual observation indicated that the roots of plants receiving 5—10 mg. boric acid per litre are longer than the others, though they are less rich in adventitious roots. The increased dry weight due to boron may amount to as much as 30 %.

(b) Sand cultures.

Agulhon again observed stimulation in this case. 2 kgm. of sand were moistened with 500 c.c. nutritive solution, varying quantities

of boric acid being added in addition. 1 mg. boric acid per litre of N.S. (.05 mg. per pot) gave an increase of 25 % fresh weight, and 7.5 % dry weight. The stimulating doses seem to be weaker than in the experiments with liquid media, probably because the evaporation from the sand increases the concentration of the boric acid at the surface. It was also noticed that the increase of weight varied in experiments made at different times. With oats the stimulating influence is greater than with wheat, showing that some plants are more sensitive than others to the influence of boron. With radish 1 mg. boric acid per litre exercised a stimulating effect, the enormous average increase of 61 % in fresh weight occurring with this strength, though this only represented an average increase of 9.6 % dry weight.

(c) *Soil cultures.*

Here again the stimulating action was evident with higher concentrations than in sand cultures, and Agulhon obtained good results with strengths that are toxic in sand. The evaporation from earth is not so rapid as from sand, so that the concentration is not increased, and also some of the boric acid is withdrawn from the solution by interaction with the soil, so that the stimulating concentration rises in the scale.

In field experiments Agulhon found that peas were more sensitive to the toxic action of boric acid than is maize. A strength of boric acid (= 1 gm. B. per sq. metre) that poisoned peas, gave an increase of 61 % fresh weight and 39 % dry weight with maize; half the strength proved to be indifferent for peas, the improvement with maize equalling 56 % increase fresh and 50 % increase dry. Curiously enough, judging by appearances in the first experiment, an unfavourable influence was at work, though in reality a great stimulation was being caused. Colza gave a good increase with similar strengths, but with turnips 1 gm. B. per sq. metre only favoured the aerial parts, while .5 gm. B. per sq. metre only increased root development. Agulhon concluded that it is as yet impossible to determine with any precision the exact part that boron plays in the plant economy. He suggests that boron is a "particulier" element characteristic of a certain group of individuals or of life under particular conditions. In his summary he argues that each series of individuals adapted to different environments has doubtless need of particular elements, and that perhaps chemical causes and morphological differences are very closely connected. Boron may be of this "particulier élément" type in the higher plants of the vegetable

kingdom, and it may be useful commercially as a manurial agent, the "catalytic manure" of Bertrand and Agulhon.

While the higher concentrations of boric acid proved definitely toxic to both peas and barley in the Rothamsted water cultures, some evidence of stimulation was obtained with the lower strengths. With barley the question of stimulation is still an open one, as below the toxic limit growth seems fairly level in most of the experimental series. The lower limit of toxicity varies from 40—4 parts boric acid per 10,000,000 according to circumstances. Below this critical concentration the boric acid has apparently no action, either depressant or stimulant, unless the stimulation should prove to begin at a dilution of 1/50,000,000, but the evidence on this point is not sufficiently well marked or consistent to be conclusive. This failure to detect stimulation was somewhat unexpected, as when judged by the eye the plants treated with the lower concentrations of boric acid seemed better than the controls, and also exhibited a particularly healthy green colouration.

Peas on the other hand are definitely stimulated with traces of boric acid, concentrations of 1/100,000 and less causing an improvement in growth, while under some experimental conditions even higher amounts of boric acid were beneficial. All the stimulated plants showed the characteristic dark green colour which seems to be associated with the presence of minute traces of boron in the nutritive solution. An interesting morphological feature was the strong development of small side shoots from the base of the plants in the presence of medium amounts of boric acid, from 1 part in 100,000 downwards. This gave rise to a certain bushiness of growth, which was less evident as the concentration of the stimulant decreased. The general outcome of the tests seems to be that boric acid needs to be supplied in relatively great strength to be fatal to pea plants, and that the toxic action gives place to a stimulative one high up in the scale of concentration. As far as experiments have already gone it seems as though the stimulation is not a progressive one, as the effect of 1/100,000 boric acid is as good as that of 1/20,000,000, a flat curve connecting the two. This, however, needs confirmation.

Yellow lupins also give some evidence of stimulation with concentrations of about 1/50,000 boric acid, the improvement being far more strongly marked in some sets of experiments than in others.

III. EFFECT OF BORON COMPOUNDS ON CERTAIN OF THE LOWER PLANTS.

Our knowledge of the action of boron on the lower plants is less definite and complete than with regard to the higher plants. Morel (1892) found that boric acid acts as a strong poison to the lower fungi and similar organisms, their development being completely arrested by very weak solutions of the acid. He suggested, on this account, that boric acid might be used in the same way as copper to attack such diseases as mildew, anthracnose, &c., which attack useful plants.

On the other hand Loew (1892) stated that such algae as *Spirogyra* and *Vaucheria* showed no harmful influence for many weeks when the culture water contained as much as .2% ($=1/500$) boric acid. This may be supplemented by a recent observation at Rothamsted, in which certain unicellular green algae (unidentified), were found growing at the bottom of a stoppered bottle containing a stock solution of 1/100 boric acid.

Agulhon (1910 a) dealt chiefly with yeasts and certain ferments, and found that yeasts grown in culture solutions are not influenced favourably or unfavourably by relatively large quantities of boric acid up to 1 gram per litre, while all development is checked with 10 grams per litre. The presence of boron affects the action of yeast on glucose and galactose. Galactose alone is not attacked even after 40 days in the presence of .66% boric acid. When glucose is mixed with the galactose the latter is said to be at first left untouched, but later it disappears very slowly.

Boric acid exercises an antiseptic action on lactic ferments, 5 gm. per litre checking their action sufficiently to enable milk to remain uncoagulated. Lactic acid is still produced even with as much boric acid as 10 gm. per litre. The microbe is not actually killed by the boric acid, but its development is so arrested that reproduction cannot take place. The same phenomenon was observed with yeast. With moulds again, while no stimulation could be obtained with small quantities of boric acid, yet the toxic action does not begin to set in until 5 gms. boric acid per litre are present.

Thus it appears that such lower organisms as yeast, lactic ferment and *Aspergillus niger* are remarkably indifferent to the action of boric acid, as is shown by the fact that the toxic dose is remarkably high, while stimulation effects cannot be observed even in the presence of the smallest quantities yet tried.

Conclusion.

Boric acid is less harmful to the growth of higher plants than are the compounds of copper, zinc, and arsenic. Evidence exists that below a certain limit of concentration boron exercises a favourable influence upon plant growth, encouraging the formation of stronger roots and shoots. This stimulation is more strongly marked with some species than with others, peas responding more readily than barley to the action of boric acid. Fungi are very indifferent to boron, whether it is present in large or small quantities, and there is evidence to show that certain of the green algae can also withstand large quantities of it.

CHAPTER VII

EFFECT OF MANGANESE COMPOUNDS

I. PRESENCE OF MANGANESE IN PLANTS

THE presence of manganese as a constituent of plant tissues has been known for many years, and in view of the close association between iron and manganese it was natural that the early investigators should seek for the latter element. De Saussure (1804) gives one of the earliest references to manganese in plant ash, stating that it occurs in the seeds in less great proportion than in the stems, and also that the leaves of trees contain less in autumn than in spring. At first oxides of iron and manganese were put together as "metallic oxides" and little or no attempt was made to separate them so as to get an idea of their relative abundance. John (1814) gives a number of rough analyses of plants and indicates the presence of manganese in many plants, including *Solanum tuberosum*, *Brassica oleracea viridis* L., *Conium maculatum*, *Aesculus* (in outer bark), and *Arundo Sacchar*. No further references presented themselves until 1847, as probably manganese was overlooked and always classed with iron in any analyses made during that time. Kane (1847) found traces of manganese in the ashes of some samples of flax, but none in others, and examinations of the soils on which the plants were grown gave similar results. Mayer and Brazier (1849) confirmed this result. Herapath (1849) analysed the ashes of various culinary vegetables, finding manganese in cauliflowers, swede turnips, beetroot, and in one variety of potato (Forty fold).

Malaguti and Durocher (1858) tried to investigate the matter quantitatively. The oxides of iron, manganese, and aluminium were all classed together, and the mean percentage of the three varied from 85 %—5.06 % according to the varieties of plants concerned, Cruciferae possessing least and Leguminosae most. Different mean results with the same plant were obtained from different soils.

Wolff (1871) made other quantitative analyses including *Trapa*

natans (·15 % Mn_2O_3), *Acorus Calamus* (1·52 % Mn_2O_3), *Alnus incana* (trace—·73 % Mn_2O_3), *Pyrus communis* (2·15 % Mn_2O_3). Many other plants were mentioned by Wolff as containing manganese.

Campani (1876) found manganese in ash by a method in which it was detected as phosphate of manganese, and he claimed to be the first to discover manganese in wheat ash. Warden (1878) found traces of Mn_2O_3 in the ash of opium from Behar.

Dunnington (1878) detected manganese in the ash of wheat, ·00144 gm. (as Mn_2O_3 ?) in 300 grams of "Dark Lancaster" variety, equivalent to ·027 % of the pure ash. The ash was exhausted with nitric acid, and after separating the iron the ammonium sulphide precipitate was found to contain manganese, and gave by fusion with nitre and sodium phosphate a violet coloured mass. Andreasch (1878) found slight traces of Mn_2O_3 in the flowers of *Dianthus caryophyllus*, none occurring elsewhere, while in *Rosa remontana* it appeared in both leaves and flowers.

Maumené (1884) tested many food plants and concluded that some quantity of manganese is frequently present in potato, rice, barley, carrot, lentil, pea, beetroot, asparagus, chicory, most fruits, tea, and also in some fodder plants, as lucerne, oats, and sainfoin. Ricciardi (1889), Hattensaur (1891) also added to the list of plants proved to contain manganese. Guerin (1897) studied the manganese content of woody tissues. Sawdust was treated with distilled water containing 1 % caustic potash, expressed, and filtered after two or three days. A brown coloured liquid was obtained, which when treated with a slight excess of hydrochloric acid gave an abundant flocculent precipitate. This precipitate proved to be soluble in pure water, so it was washed with slightly acidulated distilled water, and after further purification was analysed. No trace of iron was obtained, but about ·402 % Mn was found. Guerin regarded the precipitate as a "nucleinic" combination, which he supposed to occur generally in wood and to contain the manganese present in the woody tissues of all plants.

Schlagdenhauffen and Reeb (1904) detected manganese in a petrol extract of such cereals as barley, oats, and maize, and since inorganic salts of manganese are not soluble in such liquids as ether or petrol they concluded that the manganese must be present in the plant in organic combination, thereby upholding Guerin's view. Loew and Seiroku Honda (1904) give a table of Mn_2O_3 in the ashes of certain trees. This is very high in some cases, rising to 11·25 % in the ash of beech leaves, 6·73 % in birch leaves, and 5·48 % in chestnut fruits.

Gössl (1905) gives lists of the distribution of manganese in plants, both Thallophytes and Phanerogams, indicating the presence of much or little of the element. As a rule, he states, marsh and water plants gather up more manganese than do land plants.

The Gymnosperms seem to be particularly rich in their manganese content. Schröder (1878) tested for the element in firs and pines and found the following amounts of Mn_2O_4 .

In 100 parts ash.		In 1000 parts dry matter.	
Fir	Pine	Fir	Pine
33.18	13.46	2.76	.77

He gave a table of detailed analyses showing the differing proportions of manganese in the different parts of the fir.

Baker and Smith (1910) paid special attention to manganese in their exhaustive work on the Pines of Australia. They state that "in the anatomical investigations of the timber, bark, and leaves of the various species, there was found to be present, in a more or less degree, a naturally brownish-bronze coloured substance, which invariably stained dark brown or almost black with haematoxylin." This substance on careful investigation proved to be a compound of manganese. The quantity present varies with the species and also with the plant organs. The different species of the genus *Callitris* show variable percentages of manganese from a maximum of 0.230 % in *C. gracilis*, to a minimum of 0.010 % in *C. robusta*. The percentage of manganese in Australian Coniferae other than *Callitris* is given by the authors in the following table:

Ash of timber of <i>Agathis robusta</i>	0.145 % Mn.
" " <i>Araucaria Cunninghamii</i>	0.054 % "
" " <i>Araucaria Bidwilli</i>	0.077 % "
" " <i>Actinostrobus pyramidalis</i>	0.077 % "
" " <i>Podocarpus elata</i>	0.002 % "
" " <i>Dacrydium Franklini</i>	0.129 % "
" " <i>Athrotaxis selaginoides</i>	0.019 % "
" " <i>Phyllocladus rhomboidalis</i>	0.145 % "
Air-dried black gum of <i>Agathis robusta</i>	0.0046 % "
" " <i>Araucaria Cunninghamii</i>	0.0038 % "

Baker and Smith assume that manganese is essential to the production of the most complete growth of Coniferae. The element is found in these plants even when they grow on soils containing only traces of manganese and it is suggested that possibly the excess or deficiency of manganese in the soil helps to govern the location of certain

of the Australian Coniferae. The authors conclude that manganese may be essential to the growth of these plants, and that its association with plant life may be considered to date back to past geological time, as is indicated by plates illustrating fossil woods.

II. EFFECT OF MANGANESE ON THE GROWTH OF HIGHER PLANTS.

1. *Toxic effect.*

(a) *Toxic action of manganese compounds in the presence of soluble nutrients.*

Little work seems to have been done on the action of manganese compounds in water cultures. Knop (1884) just indicated that manganese compounds had no effect on maize, but gave no details. Japanese investigators touched on the matter in the course of their extensive experiments with this element. Asō (1902) found that the greater concentrations of manganese sulphate exercised an injurious influence on barley. Even in solutions with as little as $\cdot 002\%$ manganese sulphate ($= 1/50,000 \text{ MnSO}_4$) the roots gradually turned brown, the lower leaves following suit. The brown colour was concentrated at certain points of the leaves, and microscopical examination showed that the membranes of the epidermal cells, and in some cases the nuclei, were stained deeply brown. The greatest concentration endured by barley without injury seemed to be about $\cdot 01$ per 1000 $= 1/100,000$. The presence of iron in the food solutions seems to counteract the effect of the manganese to some extent by delaying the yellowing of the leaves. Wheat proved very similar to barley in its reactions, though more iron is necessary to give good healthy growth. Asō states that wheat is able to overcome the injurious action of manganese much more readily than is barley. With peas the yellowing of the leaves was delayed, probably on account of a sufficient supply of iron in the reserve stores of the seeds.

Loew and Sawa (1902) found that $\cdot 25\% = 1/400 \text{ MnSO}_4$ (anhydrous) kills pea plants within five days and that the green colour is gradually affected with more dilute solutions. Barley and soy beans were grown in nutritive solutions with either iron sulphate or manganese sulphate or both ($\cdot 01\% \text{ FeSO}_4$, $\cdot 02\% \text{ MnSO}_4$, $\cdot 01\% \text{ FeSO}_4 + \cdot 02\% \text{ MnSO}_4$). At first the growth was increased by the action of two salts together, but eventually the shoots turned yellowish, and assimilation was depressed, so that decreased nutrition led to relaxation in the speed of growth, indicating the toxic action due to the manganese sulphate.

The Rothamsted experiments supported Asō's work on the action of manganese sulphate on barley, concentrations of the salt above 1/100,000 having a retarding influence on the growth, the roots being coloured brown and the leaves also showing discolouration. At an early stage in growth the lower leaves of the plants receiving the most poison began to be flecked with brown spots, which were at first attributed to an attack of rust. Suspicion was soon aroused, however, and a closer microscopic investigation showed that no disease was present, but that the cells in the affected spots were dead and brown, though they retained their shape. The dead cells at first occurred in small patches, which spread and coalesced until ultimately the whole leaf was involved. Some of the affected leaves were detached and fused with a mixture of sodium carbonate and potassium nitrate. On dissolving up the resulting mass with water a green colouration was obtained, indicating the presence of manganese in the leaves. This shows that the manganese is taken up by the roots, transferred to the leaves and then deposited in them, the lower leaves being the first affected.

The presence of manganese in the nutritive solution retarded the ripening of the grain to some extent, as when the grains from the control plants were hard and ripe, those from plants treated with 1/10,000 MnSO_4 were green, those with 1/100,000 were a mixture of ripe, half-ripe, and green grains, while plants which had received 1/1,000,000 MnSO_4 possessed ripe grains.

Peas give similar results to barley so far as the vegetative growth is concerned, the same retardation with the higher concentrations being observed, while the brown discoloured patches in the lower leaves are much in evidence. All traces of manganese in the leaves disappear when the concentration falls to 1/250,000. On the whole peas are more sensitive to manganese poisoning than is barley, and the higher strengths of manganese prove more deleterious to them.

(b) *Toxic action of manganese compounds in sand cultures.*

Little work has been done on this aspect of the problem. Prince de Salm Horstmar (1851) grew oats in sand with various combinations of nitrogenous substances and inorganic mineral salts. He stated that until the time of fruit formation manganese does not seem to be essential to the oat unless iron is in excess in the substratum.

(c) *Toxic action of manganese compounds in soil cultures.*

A large body of work has been done with manganese in soil cultures, but the toxic effect is hardly indicated, possibly because it is

less manifest under soil conditions, possibly because the observation of the toxic action has been almost completely overshadowed by the interest in the stimulation observed under the same circumstances. Namba stated that 5 gm. MnSO_4 added to 8 kgm. Japanese soil exerted a depressing influence on the growth of various plants. The Hills Experiments (1903) indicated some toxic effect. Various soluble and insoluble salts of manganese were added to soil in pots at the rate of 2 cwt. per acre, wheat being sown. On the whole the plants from untreated pots were as good as any with manganese except those that received manganese nitrate or phosphate. Manganese iodide distinctly retarded growth. The plants that grew did well eventually, but development of the ear was greatly or entirely retarded. If the seeds were soaked in the iodide, a concentration of 10 % was found to be harmful, 5 % allowing normal growth. Similar experiments with barley showed that plants treated with manganese carbonate and sulphate were both inferior to the untreated plants; with iodide less plants were obtained and their development was abnormal. Soaking the seeds in the iodide, even in 10 % solution, did not do damage as it did with wheat. The oxides were apparently innocuous, but gave no increase either in corn or straw.

Kelley (1909) found that on soils in Hawaii in which excessive quantities of manganese are present (5.61 % Mn_2O_3) pineapples do not flourish, but turn yellow and produce poor fruits, and also that if rather less manganese is present (1.36 % Mn_2O_3) the pineapples show the toxic effect by yellowing during the winter months, but they recover completely during the hot summer months. Kelley also observed that the deleterious effect is hardly noticeable during the first twelve months of growth, and that after a time a darkening occurs in the colour of the soil, which he attributes to some change in the constitution of the manganese compounds.

Some interesting observations were made by Guthrie and Cohen (1910) on certain Australian soils. A bowling green that was initially covered with a healthy mat of couch grass developed a number of small patches after about three years growth, on which the grass died off. No reason was apparent for this phenomenon, as the cultural conditions were uniform and to all appearances the soil over the whole area was similar in character. Analyses of soil samples from the dead patches and from the neighbouring healthy parts of the green showed that the chemical composition in both cases was practically the same, except that while no manganese occurred in the soil from the unharmed part,

as much as 254 % Mn_2O_3 was found in that from the dead patches. As no other differences were found it was argued that the manganese, present in such large quantities, acted as a toxic agent and killed off the grass. Other instances of manganese poisoning in which wheat and barley were affected are quoted by these authors, the analytical results indicating that possibly barley is able to withstand without injury a greater quantity of manganese compounds in the soil than is wheat.

2. *Effect of manganese compounds on germination.*

Nazari (1910) rolled wheat grains in a paste of manganese dioxide, iron sesquioxide (both with and without organic matter), and in what he terms "artificial oxydases." The seeds rolled in the last-named showed the greatest energy in germination, while those with manganese gave an appreciable acceleration. The presence of organic matter decreased the action of manganese. The plants from the manganese seedlings gave an increased yield in both straw and grain, while those treated with sesquioxide of iron showed no gain over the check plants.

The Hills Experiments yielded some information as to the differing effects of various compounds of manganese on germination. With wheat plants in pot experiments manganese oxide (MnO_2) distinctly retarded germination when applied at the rate of 2 cwt. per acre. With barley MnO_2 , manganese carbonate and sulphate all retarded germination, while with the iodide 50 % of the seeds were entirely prevented from germinating.

3. *Does manganese stimulate higher plants?*

With manganese the evidence in favour of stimulation is more weighty than with such poisons as copper, zinc and arsenic, and the literature on the subject is correspondingly plentiful.

(a) *Stimulation in water cultures.*

While Asō (1902) asserted that plants can develop normally in water cultures in the absence of any trace of manganese, he further stated that manganese compounds exercise both an injurious and a stimulant action on plants. With increasing dilution of the compound the deleterious action diminishes, while the stimulant action increases, and a dilution can be reached in which only the favourable influence of the manganese becomes obvious. The addition of 0.002 % manganese sulphate (= 1/50,000) to culture solutions stimulated radish, barley,

wheat and peas. The intensity of the colour reaction of the oxidising enzyme of the manganese plants was found to exceed that of the control plants, at least with regard to those leaves on the manganese plants which had turned a yellowish colour.

Loew and Sawa (1902) obtained an initial increase of growth with barley and soy beans in nutritive solutions + 01 % ferrous sulphate + 02 % manganese sulphate, but this initial stimulation was followed by depression. These authors support Asō's contention that manganese exerts both an injurious and a stimulative action upon plants, and that the promoting effect is still observable with manganese compounds in high dilution, while the injurious effects disappear under this condition.




Fig. 17. Curve showing the mean value of the dry weights of ten series of barley plants grown in the presence of manganese sulphate and nutrient salts. (Feb. 5th—March 29th, 1909.)

The Rothamsted experiments with barley show a decided stimulation with 1/100,000 MnSO_4 and less. Care was taken to utilise sublimed FeCl_3 to avoid error due to the introduction of manganese into the control solution through the agency of this salt. It is interesting to notice that concentrations that are weak enough to stimulate the vegetative growth still show a depressing action in that they retard the ripening of the grain, a fact which supports Loew and Sawa's contention that manganese exerts both a toxic and a stimulative action at one and the same time, the balance showing itself according to the concentration (Fig. 17). In the later experiments the plants were not allowed to form ears, but similar results were obtained, except that when dealing with

the vegetative growth only, a definite stimulus was obtained with a higher concentration than in those experiments in which the plants were allowed to form seed. This may or may not be significant, as it is possible that seasonal variation and individuality of the plants may have played some part. Barley seems to be most extraordinarily sensitive to the action of manganese, as even 1 part in 100,000,000 was found to exercise a beneficial action (Fig. 18). With peas the evidence of stimulus is less well marked. No sign of stimulation is obtained until a greater dilution is reached than is necessary with barley. Even so the resulting curves are not sufficiently conclusive to warrant the definite statement that manganese does act as a stimulant to peas when present in very small quantities (Fig. 19).

(b) *Stimulation in soil cultures.*

Roxas carried out pot experiments with rice in soil to which was added varying proportions of manganese sulphate, with and without the addition of nutrient salts of ammonium, potassium, and calcium. The criterion of stimulation was the length of the growing leaves as measured daily, a strength of $M/1000 \text{ MnSO}_4$ (M = molecular weight) giving a favourable result.

In the Hills Experiments (1903) an increase of produce was obtained with wheat by manuring with manganese phosphate, chloride, sulphate, or oxide (MnO_2), while an increase of straw was gained with nitrate, though this compound decreased the yield of corn. With barley no evidence of stimulation is set forth for any compound, except that the root growth was improved by the addition of manganese iodide, in spite of the general unfavourable action this substance exerted upon germination and growth.

Bertrand (1905) whose work will later be considered in detail, experimented on arable land, adding quantities of manganese sulphate (?) equivalent to about 1.6 gm. Mn to each square metre, growing oats from February to May. Increase of weight was found in the plants growing on the manganese plots, the differences in favour of manganese being

For total crops	22.5 %.
„ grain only	17.4 %.
„ straw only	26.0 %.

A certain alteration in the quality of the grain was also noted from the manganese plots, the weight per hectolitre exceeding that




Fig. 18. Photograph showing the action of manganese sulphate on barley plants grown in the presence of nutrient salts.
(Feb. 5th—March 29th, 1909.)

1. Control.	4. 1/1,000,000	manganese sulphate.
2. 1/10,000	manganese sulphate.	" "
3. 1/100,000	" "	" "
	5. 1/10,000,000	" "
	6. 1/100,000,000	" "



Fig. 19. Photograph showing the action of manganese sulphate on pea plants in the presence of nutrient salts. (Oct. 2nd—Dec. 20th, 1912.)

- | | | | |
|----|-------------|---------------------|---|
| 1. | Control. | | |
| 2. | 1/5,000 | manganese sulphate. | |
| 3. | 1/10,000 | „ | „ |
| 4. | 1/25,000 | „ | „ |
| 5. | 1/50,000 | „ | „ |
| 6. | 1/100,000 | „ | „ |
| 7. | 1/250,000 | „ | „ |
| 8. | 1/500,000 | „ | „ |
| 9. | 1/1,000,000 | „ | „ |

from the untreated plot, the % of water and of total nitrogen being somewhat lower than that from the untreated, while the ash and the quantity of manganese present was the same in the grain from both plots. Bertrand suggested that these results might indicate a new line to follow in the study of the causes of the soil fertility.

Strampelli (1907) tested the effect of manganese dioxide, carbonate, and sulphate, and of a manganiferous mineral from the Argentine upon wheat, and found that while all four substances exercised a favourable influence on the vegetation, the best result was obtained with the sulphate. When however other manures were used in conjunction with the manganese compounds the balance of improvement shifted. With nitrogen, applied as nitrate of soda, manganese dioxide proved the most beneficial, with farmyard manure the manganiferous mineral¹, and with blood the carbonate. It was also found that a manganese compost did not increase production when phosphatic manure was applied as basic slag.

Feilitzen (1907) indicated that the nature of the soil plays its part in determining whether manganese acts as a stimulant or not. His experiments were made in the field on poor moor soil, which carried a little Sphagnum turf and Eriophorum, and which was poor in food salts. The soil was prepared and manured and then the plots were watered with a solution of .1 gm. $\text{MnSO}_4 \cdot 4\text{H}_2\text{O}$ per litre at the rate of 10 kgm. sulphate per hectare, six control plots being left untreated. Oats were sown and the soil rolled. During growth no difference was noted between the various plots, and after harvesting the weights of the different crops showed that the manganese had not caused increase of crop in either grain or straw on this poor moor soil.

The great bulk of the work on this problem has been carried out by various Japanese investigators, whose work extends over several years. Loew and Sawa (1902) found that small quantities of manganese sulphate in soil cultures stimulated the growth of rice, pea, and cabbage. They suggested that soils of great natural fertility contain manganese in an easily absorbed condition, and that this forms one of the characteristics of such soils.

Nagaoka (1903) dealt with plots in the rice fields which had not been manured for the three previous years and which were then treated with manure at the rate of 100 kgm. ammonium sulphate, 100 kgm.

¹ As no analysis of the mineral is given it is obviously impossible to say to what constituent the increase is due in this case.

potassium carbonate and 100 kgm. double superphosphate per hectare. Twelve series were worked in triplicate and received manganese sulphate in varying quantities, equivalent to 0—55 kgm. Mn_2O_3 per hectare, one set of three being left untreated. The cultivation was normal and the application of manganese was found to influence the yield of rice. 25 kgm. per hectare gave the best result and increased the harvest of grains by one-third; higher doses of Mn_2O_3 gave no better crop. The percentage of grain relative to the straw was also increased. The increase in both respects was evident all through the series from 10 to 55 kgm. Mn_2O_3 per hectare. The conclusion was reached that the application of this salt to soils poor in manganese would be a commercial advantage.

The next year (1904) the experiments were extended to observe the after effects of the initial doses of manganese sulphate. The harvest of grain was greatest in those plots that had received 30 kgm. Mn_2O_3 per hectare, while it was approached very closely by that from the plot with 25 kgm. Mn_2O_3 , which had proved the best in the first year's experiments. The maximum increase of yield over the unmanured plots in the first year was 37 %, while in the second year it dropped to 16.9 %.

Asō (1904) also obtained an increase of one-third in produce of grain when 25 kgm. Mn_2O_3 per hectare (as manganous chloride) was applied to rice. The development of the plants was improved and the treated plants flowered about four days before the untreated ones.

Loew and Honda (1904) grew *Cryptomeria japonica* in beds, treating the soil with various manures and with iron or manganese sulphate. The latter favoured increase in height, and within 1½ years the cubic content of the trees had increased to double.

Fukutome (1904) grew flax in pot cultures, each pot containing 8 kgm. soil, to which was added .4 gm. $MnCl_2 \cdot 4H_2O$ and .4 gm. $FeSO_4 \cdot 7H_2O$. This mixture had a marked effect on the growth of the flax, but the individual salts in doses of .4 gm. per 8 kgm. soil had but little effect.

Namba (1908) applied manganese salts to onion plants in pots with a considerable measure of success. Pots containing 8 kgm. loamy soil were manured and received:

- (1) no manganese,
- (2) .1 gm. $MnSO_4 \cdot 4H_2O$,
- (3) .2 gm. $MnSO_4 \cdot 4H_2O$,

the manganese sulphate being applied in high dilution as top dressing.

The bulbs and leaves were considerably stimulated by small doses of manganese sulphate, the best results being obtained from (2), which represents a manuring of 22 kgm. MnSO_4 per hectare. An increase of the dose lessens the beneficial effect, as the toxic action begins to come into play. The actual figures obtained may prove of interest.

	Wt. leaves	Wt. bulbs & roots	Total weight		Bulbs & roots leaves
	gm.	gm.	Absolute	Relative	
1.	29.5	8.5	38.0	100.0	.28
2.	38.0	22.5	60.5	159.2	.59
3.	35.5	16.5	51.0	134.2	.46

Uchiyama (1907) carried on a variety of experiments with manganese sulphate on several plants on different soils, both in the field and in pots, and found that the compound exercised a favourable action in most cases when applied in appropriate quantities. In summarising his results he stated that both manganese and iron stimulate the development of plants, different plants varying in their susceptibility to the action. Sometimes a joint application of the two salts is the most beneficial, sometimes an individual application is the better, in which case manganese sulphate is generally better than ferric sulphate in its action. The stimulating action of manganese varies greatly with the character of the soil, and the mode of application also affects results. As a general rule the manganese acts best when applied as a top dressing rather than when added together with the manure. Further the stimulating action differs greatly with the nature and reaction of the manurial mixture. Uchiyama concludes that 20—50 kgm. per hectare of crystallised manganese sulphate is a good general amount to apply.

Takeuchi (1909) corroborates the statements of the various writers that plants differ in their response to the manganese manuring. Pot cultures, in each of which 8 kgm. soil were similarly manured, received .2 gm. $\text{MnSO}_4 \cdot 4\text{H}_2\text{O}$ applied as a solution of 1/100 strength, the controls receiving the same amount of water. The manganese increased the green weight of spinach by 41 %, while the dry weight of barley, peas and flax rose 5.3 %, 19.4 %, and 13.9 % respectively above that of the untreated. The control plants of flax were behind the manganese plants in growth and flowering, while barley was the least stimulated of all the test-plants. Other observations seemed to show that Leguminosae and Cruciferae are more susceptible to manganese stimulation than are the Gramineae.

III. EFFECT OF MANGANESE COMPOUNDS ON CERTAIN OF THE LOWER PLANTS.

The information on this point is exceedingly meagre, possibly because of the diversion of general attention to the higher plants in view of the commercial interests involved.

Richards (1897) carried out experiments with various nutritive media with the addition of certain metallic salts, including those of zinc, iron, aluminium and manganese. The fungi tested were *Aspergillus niger*, *Penicillium glaucum* and *Botrytis cinerea*. His general conclusion was that fungi may be stimulated, though it must not be concluded without further investigation that all fungi react in the same degree to the same reagent, but this conclusion is traversed by Loew and Sawa (1902). These writers state that fungi are *not* stimulated by manganese, and take this as a proof that the improvement in the growth of phanerogams, induced by manganese compounds, is not due to direct stimulation of the protoplasmic activity, but to some other more obscure cause.

IV. PHYSIOLOGICAL CONSIDERATIONS OF MANGANESE STIMULATION.

The physiological cause of the stimulation exerted by manganese compounds has raised much controversy. Loew and Sawa suggested that the action of the sun's rays upon a normal plant puts a certain check on growth, arising out of the action of certain noxious compounds which they supposed to be produced in the cells under the influence of light. The stimulation of the manganese compounds may be due to a supposed increase in the oxidising powers of the oxidising enzymes, so that destruction of the checking compounds can be accomplished as quickly as they are formed, so enabling growth to continue more rapidly.

Asō (1902) had previously stated that colorimetric tests for oxidising enzymes indicate that the yellowish leaves from plants treated with manganese compounds give reactions of higher intensity than the green leaves from control plants, the difference between the reactions being specially marked in barley, and less so in radish.

Bertrand has devoted much time to the consideration of this and allied problems. In 1897 (a, b, c) he proceeded to investigate the essential nature of manganese in the economy of the plant, his

experiments showing its constant presence in a ferment (laccase) obtained from plants. He also extracted from lucerne a substance very poor in manganese, which was somewhat inactive, but which regained or increased its activity on the addition of manganese. Bertrand stated that manganese was apparently not to be replaced by another metal, not even by iron, and that the small quantity of it occurring was no reason for regarding it as a *secondary* element in the composition of plants. The view was also put forward that in the presence of certain organic substances, such as hydroquinone, pyrogallol or similar bodies, manganese is capable of fixing free oxygen from the air, the volume of oxygen absorbed varying according to the compound of manganese used. Bertrand was led to conceive the oxydases as special combinations of manganese in which the acid radicle, probably protein in nature and variable according to the ferment considered, would have just the necessary affinity to maintain the metal in solution, i.e. the form the most suitable for the part it has to play. The manganese would then be, according to his view, the true active element of oxydase, which functions as the "activator"; the albuminous matter, on the other hand, gives to the ferment those special characters, which show themselves in their behaviour with regard to reagents and physical agents. From this point of view manganese could no longer be considered as a non-essential element, but as a substance of vital necessity to the functions of plant-life. The name "complementary" manure was suggested for compounds of such elements as manganese, which exert a physiological action and which were proposed for use as manures. Later (1905) Bertrand considered that he had still further proved the indispensable nature of manganese. The absence or insufficiency of one essential element arrests or diminishes growth. This applies not only to those substances which are present in the greatest abundance, such as C, P, N, &c., but also to those elements like manganese, boron, and iodine, which only occur in traces. These elements are usually specialised in function, and for them the name "catalytic" elements was suggested, in view of the work they are held to do. As late as 1910 the rôle of manganese in the functioning of the oxidising enzymes was again insisted on. It was concluded that manganese intervenes as a catalytic agent in the material changes of which plants are the seat, and that it participates in an indirect manner in the building up of the tissues and in the production of organic matter.

Conclusion.

Manganese exerts a toxic influence upon the higher plants, if it is presented in high concentration, but, in the absence of great excess of the manganese compounds, the poisoning effect is overshadowed by a definite stimulation. As is the case with boron, manganese stimulates some species more than others, the action on barley being more evident than that on peas. It seems probable that manganese may prove to be an element essential to the economy of plant life, even though the quantity usually found in plants is very small.

CHAPTER VIII

CONCLUSIONS

IN the foregoing chapters a very limited number of plant poisons have been considered, yet there is sufficient evidence to show that even these few differ considerably in their action upon plant-life. This action is most variable, and it is impossible to foretell the effect of any substance upon vegetative growth without experiments. The degree of toxicity of the different poisons is not the same, and also one and the same poison varies in the intensity and nature of its action on different species of plants. While certain compounds of copper, zinc and arsenic are exceedingly poisonous, compounds of manganese and boron are far less deleterious, so that a plant can withstand the presence of far more of the latter substances than of the former. Again, the tested compounds of copper, zinc and arsenic do not seem to stimulate growth, even when they are applied in the smallest quantities, whereas very dilute solutions of manganese and boron compounds decidedly increase growth. But, differentiation occurs even in this stimulative action, for while manganese is the more effective in stimulating barley, boric acid is far more potent for peas, the shoots being particularly improved.

A consideration of the experimental work that has been done on this subject of poisoning and stimulation leads one to the inevitable conclusion that it is not true to maintain the hypothesis that *all* inorganic plant poisons act as stimulants when they are present in very small quantities, for while some poisons do increase plant growth under such conditions, others fail to do so in any circumstances. It is probable that what has been found true with the few substances tested would prove to be similarly true over a much wider range of poisons, and at any rate the hypothesis must be dismissed in its universal application. A more accurate statement would be that some inorganic poisons act as stimulants when present in small amounts, the

stimulating concentrations varying both with the poisons used and the plants on which they act.

It is quite possible for a stimulation in one respect to be correlated with a retardation in another. In the Rothamsted experiments on the action of manganese sulphate on barley the weaker concentrations of the salt improved the vegetative growth, as was shown by the increase in the dry weights, but with the same strengths of the poison the ripening of the grain was retarded, so that, while certain of the physiological functions were expedited, others were hindered by the action of the poison.

Thus it is evident that it is exceedingly difficult sharply to characterise either toxic or stimulant action. In neither case is the reaction simple—many factors may come into play and many processes are concerned, while the effect of a so-called poison may vary in respect of each of the functions and processes concerned. If the poison is presented in great strength the toxic action is dominant, and probably affects many functions in the same sense, so that the action is, so to speak, cumulative. Lower down in the scale of concentration differentiation of action may set in, and while some processes may still be hindered, others may be stimulated. If the two actions balance one another an apparent indifference may be manifested, so that it seems that such strengths of the poison have no effect on growth, either harmful or beneficial. At still lower concentrations, with certain plants and certain poisons, the stimulative action overpowers the toxic effect, so that in some respect or other improvement occurs in growth.

It is quite conceivable, however, that some poisons are truly indifferent in weak concentrations, as no stimulation makes itself evident under any circumstances. In these cases one is inclined to suspect that the action is somewhat more simple, in that the toxic effects gradually diminish until no poisonous action is manifest at very weak concentrations, and as no stimulation is present to bring the growth above the normal with these very weak concentrations the plant is similar to those grown without any addition of the poison.

The *modus operandi* of these stimulative agents is not yet fully understood. Perhaps at the present time two main theories hold the field: (1) that they act as catalytic agents, being valueless on their own account, but valuable in that they aid in the procuring of essential food substances; (2) that the stimulants themselves are of integral value for nutrition. The French school, with Bertrand at the head, hold strongly to the catalytic theory, maintaining that

manganese and boron compounds are able to increase growth if they are present in small quantities, as they act as "carriers" whereby the various functions of the plant are expedited by the increased facility with which the essential nutritive elements are supplied. The manganese in laccase, for instance, is held to be an oxygen carrier, whereby the oxygen is first absorbed and then released for the benefit of the plant, the manganese being regarded as essential for the functioning of the enzyme. But, if these elements are *essential*, this theory seems to stop short of the truth. If certain functions are dependent for their very occurrence upon the presence of even minute traces of any element, then surely that element is as essentially a nutrient element, as vital to the well-being of the plant as is such an element as carbon or nitrogen or phosphorus, even though the latter occurs in far greater quantity. It is necessary that one should free one's mind from the idea that the quantity of an element present in a plant is an index of its value to the plant. Naturally enough, in the early days of plant physiology, the most abundant elements first engaged the attention of investigators, and they were divided into essential and non-essential, ten elements being classed in the former category. More recent work is beginning to show that other elements are constantly present in plants, but in such small quantities that the older and cruder methods of analysis failed to reveal them, so that until lately they have been completely overlooked in work on plant nutrition. Even yet we do not know which of these other elements are essential and which are merely accidental. While we do know that the ten essential elements (C, H, O, N, S, P, K, Mg, Fe, Ca) are necessary for the well-being of all plants, it is conceivable that these other substances which only occur in very small quantities may be more individual in their action, and that while a trace of a certain element may be absolutely essential to one plant, that same element may be quite indifferent for another species. If one takes a broad outlook, the two theories seem to be in reality only parts of one, the "nutrition" theory carrying matters a little farther than the "catalytic" idea, broadening its scope and extending its application.

It seems probable that all the experimental work that has been discussed will prove to be simply preliminary to a far greater practical application of the principle of stimulation or increased growth. While the physiologists have been feeling their way towards the conclusions put forth on this subject, the agriculturists have been discovering and

extending the application of artificial manures, until at the present time such manuring is coming into its own and is receiving more of the widespread attention that it deserves. The possibility now exists that in some respects the two lines of work are converging and that the more purely scientific line will have a big contribution to make to the strictly practical line. Artificial manuring aims at improvement of the soil and crop by the addition of food substances that are needed in a particular soil, a result that used to be obtainable only by the use of the bulky farmyard manure, seaweed, &c. Apart from any other aspect of the matter the artificials, when intelligently used, are far more easy to handle and to regulate in supply, and they yield excellent results, especially in conjunction with a certain proportion of organic manures. The further prospect now opened up is the possibility of utilising some of these stimulating compounds as artificial manures. As only small traces are beneficial, larger amounts being poisonous, it is obvious that only small quantities would be needed, and, as the compounds are not usually very expensive, a considerable increase of crop for a relatively small outlay might be anticipated if no complicating factors intervened. Very much work will be required in the field to test the value of these substances, as their action may be influenced by the nature of the soil, climatic conditions, general conditions of manuring, and the crops grown. Some tests have already been made, especially in Japan, with boron and manganese, and these indicate a promising field for investigation.

Above all, it is most important to realise that one is approaching an entirely unexplored field, and that it is inevitable that the results of the initial experiments will be contradictory, at least in appearance, so that it is necessary to keep an open mind on the subject, being ready to modify one's ideas as circumstances require, as improved experimental methods lead on to more accurate results.

BIBLIOGRAPHY

The references are to pages on which authors are mentioned. Papers to which no page-references are appended are not dealt with in the text.

	PAGE
ARBA, F. Ueber die Feinheit der biologischen Methode beim Nachweis des Arseniks. Centr. Bakt. Par. Abt. 2, iv, 806—8. (1898)	63
ADERHOLD, R. Zur Frage der Wirkung des Kupfers auf die Pflanze. Ber. Deut. bot. Gesell. xxiv, 112—8. (1906)	—
AGULHON, H. Recherches sur la présence et le rôle du bore chez les végétaux. Thèse. Paris. (1910 a)	68, 70, 72, 73, 76
AGULHON, H. Accoutumance du maïs au bore. Compt. rend. cli, 1382—3. (1910 b)	72
AGULHON, H. Emploi du Bore comme Engrais catalytique. 7th Inter. Cong. Applied Chem. Sect. vii, Agric. Chem. 165—6. (1910 c)	71, 73
AGULHON, H. Emploi du bore comme engrais catalytique. Compt. rend. cli, 288—91. (1910 d)	73
AMOS, A. Effect of fungicides upon the assimilation of carbon dioxide by green leaves. Journ. Agric. Sci. ii, 257—66. (1907—8)	33 ✓
ANDREASCH, R. Ueber die Zusammensetzung der Asche der Gartennelke und der Gartenrose. Journ. prakt. Chem. xviii, 204—7. (1878)	79
ARCHANGELI, G. Sopra l' azione dell' acido borico sul germogliamento dei semi. Proc. verb. Soc. Toscana sci. nat. Pisa. v, 25—9. (1885)	67, 72
ASO, K. On the physiological influence of manganese compounds on plants. Bull. Coll. Agric. Tokyo, v, No. 2, 177—85. (1902)	81, 84, 90 -
ASO, K. On the practical application of manganous chloride in rice culture. Bull. Coll. Agric. Tokyo, vi, No. 2, 131—3. (1904)	88
BAKER, R. T. and SMITH, H. G. A Research on the Pines of Australia. (1910)	80
BAUMANN, A. Das Verhalten von Zinksalzen gegen Pflanzen und im Boden. Landw. Versuchs-Stat. xxxi, 1—53. (1885)	39, 42
BAUMANN, E. Ueber das normale Vorkommen von Iod in Thierkörper. Zeitschr. physiol. Chem. xxi, 319—330. (1895)	2
BAUMERT, G. Zur Frage des normalen Vorkommens der Borsäure im Weine. Ber. Deut. chem. Gesell. xxi, 3290—2. (1888)	65
BECHI, M. E. Sur la présence de l'acide borique dans les végétaux. Bull. Soc. Chim. Paris, iii, 122. (1890)	66
BECHI, E. Intorno alla diffusione dell' acido borico. Atti R. Accad. Econom. Agrar. Georgofili di Firenze, xiv, 240—50. (1891)	66
BERLESE und SOSTEGNI. Untersuchungen über die Wirkung der Kupfersalze auf die Vegetation des Weinstockes und auf den Boden. Rev. internat. viticult. et oenol. (1895)	26

	PAGE
BERTRAND, G. Sur l'intervention du manganèse dans les oxydations provoquées par la laccase. <i>Compt. rend.</i> cxxiv, 1032—5. (1897 a)	90
BERTRAND, G. Sur l'action oxydante des sels manganoux et sur la constitution chimique des oxydases. <i>Compt. rend.</i> cxxiv, 1355—8. (1897 b)	90
BERTRAND, G. Nouvelles recherches sur les ferments oxydants ou oxydases. <i>Ann. Agronom.</i> xxiii, 385—99. (1897 c)	90
BERTRAND, G. Sur la recherche et sur l'existence de l'arsenic dans l'organisme. <i>Ann. Inst. Pasteur</i> , xvi, 553—61. (1902)	51
BERTRAND, G. Les engrais complémentaires. 5th Internat. Kong. angew. Chem. Berlin, iii, 839—40. (1903)	91
BERTRAND, G. Sur l'emploi favorable du Manganèse comme engrais. <i>Compt. rend.</i> cxli, 1255—7. (1905)	86, 91
BERTRAND, G. Sur les Engrais catalytiques. 7th Internat. Cong. Applied Chem. Sect. vii, Agric. Chem. 159—62. (1910)	91
BOKORNY, T. Uebereinstimmendes Verhalten der Metalle der Kupfergruppe (Kupfer, Quecksilber, Silber) gegen Zellen der niederen Pflanzen. <i>Chem. Zeit.</i> xxix, 2, 1201—2. (1905)	35
BOUILHAC, R. Influence de l'acide arsénique sur la végétation des algues. <i>Compt. rend.</i> cxix, 929—31. (1894)	62
BRAND, J. Die Borsäure ein steter Begleiter des Bieres und ein wesentlicher Bestandtheil des Hopfens. <i>Zeitschr. ges. Brauwesen</i> , xv, 426—8. (1892)	66
BREAZEALE, J. F. Effect of certain solids upon the growth of seedlings in water culture. <i>Bot. Gaz.</i> xli, 54—63. (1906)	23
BRENCHLEY, W. E. The influence of copper sulphate and manganese sulphate upon the growth of barley. <i>Ann. Bot.</i> xxiv, 571—83. (1910)	20, 82
BRENCHLEY, W. E. On the action of certain compounds of zinc, arsenic, and boron on the growth of plants. <i>Ann. Bot.</i> xxviii, 283—301. (1914)	40, 46, 54
BURLINGHAM, G. S. A study of the influence of magnesium sulphate on growth of seedlings. <i>Journ. Amer. Chem. Soc.</i> xxix, 1095—112. (1907)	1
CAMPANI, G. Il manganese nelle ceneri si manifesta facilmente sotto la forma di fosfato manganico. <i>Gaz. chim. ital.</i> vi, 464—6. (1876)	79
CAMPANI, G. Sull' esistenza del manganese nelle piante. <i>Gaz. chim. ital.</i> xiv, 515—6. (1884)	—
CERNÝ, K. Ueber das Vorkommen von Arsen im thierischen Organismus. <i>Zeitschr. physiol. Chem.</i> xxxiv, 408—16. (1901)	51
CHATIN, A. Études de physiologie végétale faites au moyen de l'acide arsénieux. <i>Compt. rend.</i> xx, 21—9. (1845)	51, 52, 59
CHUARD, E. et PORCHET, F. L'action des sels de cuivre sur les végétaux. <i>Arch. Sci. Phys. Nat.</i> xiv, 502—5. (1902)	31
CHUARD, E. et PORCHET, F. L'action des sels de cuivre sur les végétaux. <i>Arch. Sci. Phys. Nat.</i> xv, 91. (1903)	31
COLIN, H. and LAVISON, J. Absorption comparée des sels de Baryum, de Strontium et de Calcium par la plante vivante. <i>Revue Gén. Bot.</i> xxii, No. 261, 337—44. (1910)	5

	PAGE
COLLINS, S. H. The absorption of Arsenic by Barley. Journ. Soc. Chem. Ind. xxi, 221—2. (1902)	52
COPELAND, E. B. and KAHLENBERG, L. The influence of the presence of pure metals upon plants. Trans. Acad. Sci. Arts and Letters Wisconsin, xii, Part 2, 454—74. (1900)	19
COUPIN, H. Sur la toxicité des sels de cuivre à l'égard des végétaux supérieurs. Compt. rend. cxxvii, 400—1. (1898)	18
COUPIN, H. Sur la nutrition du Sterigmatocystis nigra. Compt. rend. cxxxvi, 392—4. (1903)	49
CRAMPTON, C. A. Borsäure als Bestandtheil der Pflanzen. Ber. Deut. chem. Gesell. xxii, 1072—6. (1889)	65
CSAPODI, S. Das Vegetiren der Schimmelpilze auf festen Arsenverbindungen. Bot. Centr. lvii, 101—2. (1894)	63
DANDENO, J. B. An investigation into the effects of water and aqueous solutions of some of the common inorganic substances on foliage leaves. Trans. Canadian Inst. vii, 237—350. (1900—1903)	32, 47
DAUBENY, C. Memoir on the degree of selection exercised by plants, with regard to the earthy constituents presented to their absorbing surfaces. Trans. Linn. Soc. xvii, 253—66. (1833)	5
DAUBENY, C. On the power ascribed to the roots of plants of rejecting poisonous or abnormal substances presented to them. Journ. Chem. Soc. xiv, 209—30. (1862)	5, 57
DAVY, E. Presence of Arsenic in plants cultivated for food. Gard. Chron. Sept. 10th, 739—40. (1859)	51, 58, 60
DE SAUSSURE. Recherches chimiques sur la végétation. Paris. (1804)	5, 78
DIEULAFAIT. Sur la présence normale du cuivre dans les plantes qui vivent sur les roches de la formation primordiale. Compt. rend. xc, 703—5. (1880)	15
DUBOIS, R. Sur les moisissures du cuivre et du bronze. Compt. rend. cxi, 655—7. (1890)	33
DUNNINGTON, F. P. Manganese in the Ash of Wheat. Proc. Amer. Chem. Soc. ii, 141. (1878)	79
EHRENBERG, P. Wirkungen des Zinks bei Vegetationsversuchen. Chem. Zeit. xxxii, 937. (1906)	43
EWERT, Dr. Der wechselseitige Einfluss des Lichtes und der Kupferkalkbrühen auf den Stoffwechsel der Pflanze. Landw. Jahrb. xxxiv, 233—310. (1906)	31
FEILITZEN, H. von. Kann man auf dem freien Felde einen günstigen stimulierenden Einfluss auf die Entwicklung der Kulturpflanzen durch kleine Mengen Mangansalze wahrnehmen? Journ. Landw. lv, 289—92. (1907)	87
FITCH, R. The action of insoluble substances in modifying the effect of deleterious agents upon the fungi. Ann. Mycologici, iv, 313—22. (1906)	23
FLICHE ET GRANDPAU. Ann. Chim. Phys. 354. (1874)	71
FRANK, B. und KRÜGER, F. Ueber den Reiz, welchen die Behandlung mit Kupfer auf die Kartoffelpflanze hervorbringt. Ber. Deut. bot. Gesell. xii, 8—11. (1894)	30

	PAGE
FREYTAG, M. Ueber den Einfluss des Zinkoxyds und seiner Verbindungen auf die Vegetation. Mitth. König. landw. Akad. Poppelsdorf, 82—99. (1868)	37, 38, 42, 43
FREYTAG, M. Die schädlichen Bestandtheile des Hüttenrauchs der Kupfer-, Blei-, und Zink-hütten und ihre Beseitigung. Landw. Jahrb. II, 315—57. (1882)	—
FUKUTOME, T. On the influence of manganese salts on Flax. Bull. Coll. Agric. Tokyo, VI, No. 2, 137—8. (1904)	88
GAUTIER, A. et CLAUSMANN, P. Origines alimentaires de l'arsenic normal chez l'homme. Compt. rend. cxxxix, 101—8. (1904)	51
GIRARD, A. Sur l'accumulation dans le sol des composés cuivriques employés pour combattre les maladies parasitaires des plantes. Compt. rend. cxx, 1147—52. (1895)	—
GORUP-BESANEZ, E. von. Ueber das Verhalten der vegetirenden Pflanze und der Ackererde gegen Metallgifte. Ann. Chem. Pharm. cxxvii, 243—56. (1863)	25, 41, 58
GOSIO, B. Einwirkung von Microphyten auf feste Arsenverbindung. Mitt. aus den Lab. sci. della Direzione di Sanità. Abst. in Ber. Deut. chem. Ges. xxv, Vol. III, 346. (1892)	63
GOSIO, B. Zur Frage, wodurch die Giftigkeit arsenhaltiger Tapeten bedingt wird. Ber. Deut. chem. Gesell. xxx, Bd. 1, 1024—6. (1897)	63
GOSIO, B. Weitere Untersuchungen über die Biologie und den Chemismus von Arsenschimmelpilzen. II Policlinico, x. (1900). Abs. in Bot. Centr. lxxxvii, 131—3. (1901)	63
GÖSSL, J. Ueber das Vorkommen des Mangans in der Pflanze und über seinen Einfluss auf Schimmelpilze. Beih. Bot. Centr. xviii, 1, 119—32. (1905)	80
GUERIN, G. Sur un composé organique, riche en manganèse, retiré du tissu ligneux. Compt. rend. cxxv, 311—2. (1897)	79
GUSTAVSON, G. Chemische Rolle der Mineralsalze in der organischen Natur. Mitt. Landw. Forstwirthsch. Akad. Petrowskoß-Rasumowskoß. Heft 3, 1—15. Moskau. (1881.) Abst. in Just. Bot. Jahresber. I, 38. (1882)	45
GUTHRIE, F. B. and COHEN, L. Note on the occurrence of manganese in soil and its effect on grass. Agric. Gaz. New South Wales, xxi, 219—22. (1910)	83
GUTHRIE, F. B. and HELMS, R. Pot Experiments to determine the limits of endurance of different farm crops to certain injurious substances. Part 1. Wheat. Ag. Gaz. N.S.W. xiv, 114—20. (1903)	60
GUTHRIE, F. B. and HELMS, R. Ibid. Part 2. Maize. Ag. Gaz. N.S.W. xv, 29—32. (1904)	60
GUTHRIE, F. B. and HELMS, R. Ibid. Part 3. Barley and Rice. Part 4. Rye. Ag. Gaz. N.S.W. xvi, 853—60. (1905)	60
HALL, A. D. The Book of the Rothamsted Experiments. (1905)	—
HALL, A. D., BRENOHLEY, W. E. and UNDERWOOD, L. M. The soil solution and the mineral constituents of the soil. Phil. Trans. Roy. Soc. 204. B. 307. 179—200. (1913)	8

	PAGE
HASELHOFF, E. Ueber die schädigende Wirkung von kupfersulfat- und kupfernitratthaltigem Wasser auf Boden und Pflanzen. Landw. Jahrb. xxi , 263—76. (1892)	25
HASELHOFF, E. Versuche über die Einwirkung Schwefliger Säure, Zinkoxyd und Zinksulfat auf Boden und Pflanzen. Ber. Versuchs-Stat. Marburg. 1903—4. Abst. in Jahresb. Agrik. Chem. vii , 261. (1904)	—
HATTENSAUR, G. Zur chemischen Zusammensetzung von <i>Molinia caerulea</i> Mönch von Königsberg bei Raibl. Ber. Kais. Akad. Wissens. Wien. xcix , 2 b. 29—31. (1891)	16, 37
HATTORI, H. Studien über die Einwirkung des Kupfersulfats auf einige Pflanzen. Journ. Coll. Sci. Tokyo, xv , 371—94. (1901)	31, 34
HEALD, F. D. On the toxic effect of dilute solutions of acids and salts upon plants. Bot. Gaz. xxii , 125—53. (1896)	22
HECKEL, E. De l'action de quelques composés sur la germination des graines (bromure de camphre, borate, silicate et arséniate de soude). Compt. rend. lxxx , 1170—2. (1875)	60, 72
HERAPATH, T. J. Analyses of the ashes of some esculent vegetables. Quart. Journ. Chem. Soc. ii , 4—24. (1849)	78
"HILLS" Experiments. Influence of Manganese salts on wheat and barley. Journ. Roy. Agric. Soc. Eng. lxiv , 348—57. (1903)	83, 84, 86
HILTNER, L. and GENTNER, G. Untersuchungen über die Ernährungsverhältnisse unserer Kulturpflanzen. Landw. Jahrb. Bayern. No. 10, pp. 41—62. (1913)	10
HOLDEFLEISS. (Discussion on zinc in soils and its effect on plant life.) Landw. Versuchs-Stat. xxviii , 472. (1883)	42
HOTTER, E. Ueber das Vorkommen des Bors im Pflanzenreich und dessen physiologische Bedeutung. Landw. Versuchs-Stat. xxxvii , 437—58. (1890)	65, 67
HOTTER, E. Ueber den Borsäuregehalt einiger Obstarten. Zeitschr. Nahrungsmittel Hyg. Waar. ix , 1—4. (1895)	65
JAVILLIER, M. Sur l'influence favorable de petites doses de zinc sur la végétation de <i>Sterigmatocystis nigra</i> V. Tgh. Compt. rend. cxlv , 1212—5. (1907)	49
JAVILLIER, M. Sur la fixation du zinc par le <i>Sterigmatocystis nigra</i> , V. Tgh. Compt. rend. cxlvi , 365—7. (1908 a)	49
JAVILLIER, M. Le Zinc chez les plantes. Recherches sur sa présence et son rôle. Ann. Inst. Pasteur, xxii , 720—7. (1908 b)	49
JAVILLIER, M. Recherches sur la présence et le rôle du zinc chez les plantes. Thèse. Paris. (1908 c)	38, 47
JAVILLIER, M. Le Zinc chez les plantes et son emploi comme Engrais complémentaire. 7th Internat. Cong. Appl. Chem. Sect. vii , Agric. Chem. 163—4. (1910)	46
JAVILLIER, M. Sur la substitution au zinc de divers éléments chimiques pour la culture du <i>Sterigmatocystis nigra</i> . Compt. rend. clv , 1551—2. (1912)	—
JAY, H. Sur la dispersion de l'acide borique dans la nature. Compt. rend. ccxi , 896—9. (1895)	66

	PAGE
JENSCH, E. Beiträge zur Galmeiflora von Oberschlesien. Zeitschr. angew. Chem. 14—5. (1894)	37, 43
JENSEN, G. H. Toxic limits and stimulation effects of some salts and poisons on wheat. Bot. Gaz. XLIII, 11—44. (1907)	24, 39, 46
JOHN, J. F. Chemische Tabellen der Pflanzenanalysen. Nürnberg. (1814)	78
KAHLENBERG, L. and TRUE, R. H. On the toxic action of dissolved salts and their electrolytic dissociation. Bot. Gaz. XXII, 81—124. (1896)	19, 22, 68
KANDA, M. Studien über die Reizwirkung einiger Metallsalze auf das Wachstum höheren Pflanzen. Journ. Coll. Sci. Tokyo, XIX, Art. 13, 1—37. (1904)	28, 46, 47
KANE, R. Researches on the composition and characters of certain soils and waters belonging to the flax districts of Belgium and on the chemical constitution of the ashes of the Flax plant. Proc. Roy. Dublin Soc. LXXXIII, 153—172. (1847)	78
KELLEY, W. P. Manganese in some of its relations to the growth of pine-apples. Journ. Ind. Eng. Chem. I, 533—8. (1909)	83
KLOPSCHE. Ueber die Aufnahme von Zink durch die Pflanzen. Kulturtechniker, 223—6. (1908)	38, 47
KNOP, W. Ueber die Aufnahme verschiedener Substanzen durch die Pflanze, welche nicht zu den Nährstoffen gehören. Jahrb. Agrik. Chem. VII, 138—40. (1884)	24, 53, 62, 67, 81
KRAUCH, C. Ueber Pflanzenvergiftungen. Journ. Landw. XXX, 271—91. (1882)	39, 43
LABAND. Zur Verbreitung des Zinkes im Pflanzenreiche. Zeitschr. Nahrungs- und Genussmittel, IV, 489—92	—
LECHARTIER, G. et BELLAMY, F. Sur la présence du Zinc dans le corps des animaux et dans les végétaux. Compt. rend. LXXXIV, 687—90. (1877)	37
LECLERC, M. A. Dosage du manganèse dans les sols et dans les végétaux. Compt. rend. LXXV, 1208—14. (1872)	—
LEHMANN, K. B. Hygienische Studien über Kupfer. 1. Die Bestimmung kleiner Kupfermengen in organischen Substanzen. Arch. Hyg. XXIV, 1—83. (1895)	16
LEHMANN, K. B. Ibid. 4. Der Kupfergehalt von Pflanzen und Thieren im kupferreichen Gegenden. Arch. Hyg. XXVII, 1—7. (1896)	16
LE RENARD. Du chémauxisme des sels de cuivre solubles sur le Penicillium glaucum. Journ. Bot. XVI, 97—107. (1902)	—
LIEBIG, J. Die Chemie in ihrer Anwendung auf Agricultur und Physiologie. (1840)	1
LINDSAY, J. The elimination of Algae in lochs and ponds. Trans. Edinburgh Field Nat. Micros. Soc. VI, Part 5, 422—31. (1913)	35
LIPPMAN, E. O. von. Ueber einiger seltenere Bestandtheile der Rübensaache. Ber. Deut. chem. Gesell. XXI, 3492—3. (1888)	16, 65
LOEB, J. The toxic and antitoxic effects of ions as a function of their valency and possibly their electrical discharge. Amer. Journ. Physiol. VI, 411—33. (1902)	44
LOEW, O. Sind Arsenverbindungen Gift für pflanzliches Protoplasma? Pflüger Arch. Physiol. XXXII, 111—3. (1883)	62

	PAGE
LOEW, O. Bemerkung über die Giftwirkung des destillirten Wassers. Landw. Jahrb. xx, 235. (1891)	10
LOEW, O. Ueber die physiologischen Functionen der Calcium- und Magnesium-salze im Pflanzenorganismus. Flora, LXXV, 374. (1892)	76
LOEW, O. On the treatment of crops by stimulating compounds. Bull. Coll. Agric. Tokyo, vi, No. 2, 161—75. (1904)	—
LOEW, O. ASO, K. und SAWA, S. Ueber die Wirkung von Manganverbindungen auf Pflanzen. Flora, xci, 264—73. (1902)	—
LOEW, O. und HONDA, S. Ueber den Einfluss des Mangans auf Waldbäume. Bull. Coll. Agric. Tokyo, vi, No. 2, 125—30. (1904)	79, 88
LOEW, O. and SAWA, S. On the action of manganese compounds on plants. Bull. Coll. Agric. Tokyo, v, No. 2, 161—72. (1903)	81, 85, 87, 90
MALAGUTI et DUROCHER. Sur la répartition des éléments inorganiques dans les principales familles du règne végétal. Ann. Chim. Phys. LIV, 257—97. (1858)	78
MAUMENÉ, E. J. Sur l'existence du manganèse dans les plantes et son rôle dans la vie animale. Bull. Soc. Chim. Paris, XLII, 305—15. (1884)	79
MAYER, J. E. and BRAZIER, J. S. Analyses of mineral constituents of the Flax plant, and of the soils on which the plants had been grown. Quart. Journ. Chem. Soc. II, 78—90. (1849)	78
MEISSNER, W. Versuche über den Kupfergehalt einiger Pflanzenaschen. Schweigger's Journ. Chem. Phys. XVII, 340—54. (1816)	15
MIANI, D. Ueber die Einwirkung von Kupfer auf des Wachstum lebender Pflanzenzellen. Ber. Deut. bot. Gesell. XIX, 461—4. (1901)	28
MICHEELS, H. Sur les stimulants de la nutrition chez les plantes. Bull. Soc. Roy. Belgique, XLII, Part 2, 233—9. (1904—5)	27
MICHEELS, H. Influence de la valence des métaux sur la toxicité de leur sels. Compt. rend. CXLIII, 1181—2. (1906)	44
MIYAJIMA, M. On the poisonous action of Copper upon various plants. Bot. Mag. Tokyo, xi, 417—27 (1897). Ref. in Just's Bot. Jahresb. II, 187—8. (1898)	27
MOLISCH, H. Ueber lokale Membranfärbung durch Manganverbindungen bei einigen Wasserpflanzen. Sitz. Kais. Ak. Wiss. Wien, cxviii. 1427—39. Abst. in Knowledge, vii, 448. (1909)	—
MORREL, J. Action de l'acide borique sur la germination. Compt. rend. cxiv, 131—3. (1892)	72, 76
NAGAOKA, M. On the stimulating action of Manganese upon Rice, I. Bull. Coll. Agric. Tokyo, v, No. 4, 467—72. (1903)	87
NAGAOKA, M. On the stimulating action of Manganese upon Rice, II. Bull. Coll. Agric. Tokyo, vi, No. 2, 135—6. (1904)	88
NÄGELI, C. Ueber oligodynamische Erscheinungen in lebenden Zellen. Denkschr. Schweiz. Natur-gesell. xxxiii, 1—43. (1893)	28
NAKAMURA, M. Can Boric Acid in high dilution exert a stimulant action on plants? Bull. Coll. Agric. Tokyo, v, No. 4, 509—12. (1903)	71, 73
NAKAMURA, M. Can salts of Zinc Cobalt and Nickel in high dilution exert	

	PAGE
a stimulant action on agricultural plants? Bull. Coll. Agric. Tokyo, vi, No. 2, 147—52. (1904)	46
NAMBA, I. On the behaviour of Onion to stimulants. Bull. Coll. Agric. Tokyo, vii, No. 5, 635—6. (1908)	83, 88
NAZARI, V. Azione di alcune ossidasi artificiali e di diversi composti metallici, sulla germinazione e sull' accrescimento delle piante. Staz. sper. agrar. Ital. XLIII, 667—86. (1910)	84
NAZARI, V. Influence of some artificial oxydases and some metallic compounds on the growth of wheat. (1910.) Ref. in Exp. Stat. Rec. XXIV, p. 532. (1911)	84
NOBBE, F. BAESSLER, P. und WILL, H. Untersuchungen über die Giftwirkung des Arsens, Blei und Zink im pflanzlichen Organismus. Landw. Versuchs-Stat. XXX, 380—423. (1884)	43, 53, 59
ONO, N. Ueber die Wachstumbeschleunigung einiger Algae und Pilze durch chemische Reize. Journ. Coll. Agric. Tokyo, XIII, 141—85. (1900)	34, 48, 62, 63
ORLOWSKI, S. F. Ueber die Wirkung des Arsens auf das Wachstum und die chemische Zusammensetzung von Aspergillus niger. Petersburg. Dissert. (1902). Abst. in Biochem. Centr. I, 329. (1902—3)	63
OTTO, R. Untersuchungen über das Verhalten der Pflanzenwurzeln gegen Kupfersalzlösungen. Sorauer Zeitsch. Pflanzenkrankh. III, 322—34. (1893)	17, 26
PASSERINI, N. Ricerche chimico-agricole sui ceci. Cicer arietinum L. Presenza del boro, del litio e del rame nella pianta. Staz. Sper. Agrar. Ital. XXI, 20—30. (1891)	16, 66
PELIGOT, E. De l'action que l'acide borique et les borates exercent sur les végétaux. Compt. rend. LXXXIII, 686—88. (1876)	71
PHILLIPS, F. C. The absorption of metallic oxides by plants. Chem. News, XLVI, 224—6. (1882)	24, 42, 51, 58
PHILLIPS, Effets du cuivre sur la végétation. Ann. Chim. Phys. XIX, 76. (1821)	15
RAULIN, J. Etudes chimiques sur la végétation. Ann. Sci. Nat. XI, 139—40. (1869)	48
RIOCIARDI, L. Sulla diffusione dell' allumina nei vegetali. Gaz. chim. Ital. XIX, 150—9. (1889)	79
RICHARDS, H. M. Die Beeinflussung des Wachstums einiger Pilze durch chemische Reize. Jahrb. wiss. Bot. XXX, 665—88. (1897)	50, 80
RICHTER, A. Zur Frage der chemischen Reizmittel. Die Rolle des Zink und Kupfer bei der Ernährung von Aspergillus niger. Centr. Bakt. Par. Abt. 2, VII, 417—29. (1901)	34, 49
RISSE, H. Quoted in Sachs "Experimental-Physiologie der Pflanzen." 153—4. (1866)	36
ROXAS, M. The effect of some stimulants upon rice. Philippine Agric. and Forester, I, No. 5, 89—97.	47, 86
SALM HORSTMAR, Prince de. Recherches sur la nutrition de l'avoine, particulièrement en ce qui concerne les matières inorganiques qui sont nécessaires à cette nutrition. Ann. Chim. Phys. XXXII, 461—507. 1851)	82

	PAGE
SCHLAGDENHAUFFEN et REEB. Sur les combinaisons organiques des métaux dans les plantes. <i>Compt. rend.</i> cxxxix, 980—3. (1904)	79
SCHREINER, O. and REED, H. S. Power of Sodium Nitrate and Calcium Carbonate to decrease toxicity in conjunction with plants growing in solution cultures. <i>Journ. Amer. Chem. Soc.</i> xxx, 85—97. (1908)	4
SCHRÖDER, J. etc. Chemische Zusammensetzung der Pflanze. A. Anorganische Bestandtheile. <i>Jahresber. Agrik. Chem.</i> 105 et seq. (1878)	80
SEGALE, M. Untersuchungen über das Vorhandsein von Arsen in den normalen Geweben vermittelst der biologischen Methode. <i>Zeitschr. physiol. Chem.</i> xlii, 175—80. (1904)	63
SEYNES, M. J. de. Résultats de la culture du <i>Penicillium cupricum Trabut.</i> <i>Bot. Soc. France</i> , xlii, 451—5. (1895)	34
STOKLASA, J. Ueber die Bedeutung des Arsens in der Pflanzen-production. <i>Casopis pro prumsyl chemicky</i> , 5, 311, 379, 407 (1895). 6, 182 (1896). <i>Abst. in Jahresb. Agrik. Chem.</i> xix, 246—7. (1896)	53, 60
STOKLASA, J. Ueber die physiologische Bedeutung des Arsens im Pflanzen-organismus. <i>Zeitschr. landw. Versuchswes. Oesterreich.</i> i, 155—93. (1898)	53, 57, 58, 60
STORP, F. Ueber den Einfluss von Kochsalz- und Zinksulfathaltigen Wasser auf Boden und Pflanzen. <i>Landw. Jahrb.</i> xii, 795—844. (1883) 40, 42, 43, 44	
STRAMPPELLI, N. Azione dei diversi composti di manganese ed in particolare del minerale manganesifero del Monte Argentario, usati nella concimazione delle piante. 6° Cong. internat. Chim. appl. Roma, iv, 14—7. (1907)	87
SWAIN, R. E. and HARKINS, W. D. Arsenic in vegetation exposed to smelter smoke. <i>Journ. Amer. Chem. Soc.</i> xxx, 915—28. (1908)	52
TAKEUCHI, T. On differences of susceptibility of plants to stimulation. <i>Journ. Coll. Agric. Tokyo</i> , i, No. 2, 207—10. (1909)	89
TRABUT, M. L. Sur un <i>Penicillium végétant</i> dans des solutions concentrées de sulfate de cuivre. <i>Bull. Soc. Bot. France</i> , xlii, 33—4. (1895)	34
TREBOUX, O. Einige stoffliche Einflüsse auf die Kohlensäureassimilation bei submersen Pflanzen. <i>Flora</i> , xcii, 56—8. (1903)	32, 48
TRUE, R. H. and GIES, W. J. On the physiological action of some of the heavy metals in mixed solutions. <i>Bull. Torr. Bot. Club</i> , xxx, 390—402. (1903)	20, 40, 45
TRUE, R. H. and OGLEVEE, C. S. The effect of the presence of insoluble substances on the toxic actions of poisons. <i>Science</i> , xix, 421—4. (1904)	22
TRUE, R. H. and OGLEVEE, C. S. The effect of the presence of insoluble substances on the toxic action of poisons. <i>Bot. Gaz.</i> xxxix, 1—21. (1905)	22
UCHIYAMA, S. Influence of stimulating compounds upon the crops under different conditions. <i>Bull. Imp. Cent. Agric. Expt. Stat. Japan</i> , i, No. 2, 37—79. (1907)	89
UNDERWOOD, L. M. vide HALL, BRENCHLEY and UNDERWOOD	8
VEDRÖDI, V. Das Kupfer als Bestandtheil der Sandböden und unserer Culturgewächse. <i>Chem. Zeit.</i> xvii, 1932. (1893)	16

	PAGE
VEDRÖDI, V. Das Kupfer als Bestandtheil unserer Vegetabilien. <i>Chem. Zeit.</i> xx , 399—400. (1896)	17 ✓
VERSCHAFFELT, E. Mesure de l'action des poisons sur les plantes. <i>Archiv. Néerland. Sci. Exact. Nat. Haarlem</i> , x , 1—7. (1905)	26 ✓
WARDEN, C. J. H. Analysis of Behar Opium ash. <i>Chem. News</i> , xxxviii , 146. (1878)	79
WEHMER, C. Pflanzenstoffe. (1911)	52
WIELER, A. Die Wirkung metallischer Gifte im Boden auf das Pflanzenwachstum. <i>Pflanzenwachstum und Kalkmangel im Boden</i> , 177—235. (1912)	—
WITTSTEIN, Dr und APOIGER, F. Entdeckung der Borsäure im Pflanzenreiche. <i>Ann. Chem. Pharm.</i> ciii , 362—64. (1857).	65
WOLFF, E. Aschenanalysen von landwirthschaftlichen Producten, Fabrikabfällen und wildwachsenden Pflanzen. Berlin. (1871).	78

INDEX OF PLANT-NAMES

The symbols after the plant-names represent the elements referred to on the pages indicated.

- Acorus Calamus Mn 79
 Actinostrobilus pyramidalis Mn 80
 Aesculus Mn 78
 Agathis robusta Mn 80
 Ageratum Cu 24; Zn 42
 Alder As 53
 Algae As 62, 64; B 66, 77
 Allium (*see* Onion) Zn 47
 Alnus incana Mn 79
 Aloe Cu 26
 Amomum sp. (Paradieskörner) Cu 15
 Ampelopsis Cu 32; Zn 47
 Anaboena Cu 85
 Angiosperms B 66
 Anthracnose B 76
 Apple B 65, 66
 Apricot Cu 16
 Araucaria Bidwilli Mn 80
 Cunninghamii Mn 80
 Armeria sp. Zn 88
 vulgaris Zn 36, 37
 Arundo Sacchar Mn 78
 Asparagus Mn 79
 Aspergillus Cu 33, 34
 Aspergillus niger (= Sterigmatocystis nigra)
 Zn 48, 49, 50; As 68; B 76; Mn 90
 Athrotaxis selaginoides Mn 80

 Barley 11, 18; Sr 5; Cu 16, 17, 20,
 29; Zn 37, 39, 40, 44, 46; As 52,
 54, 55, 57, 60, 61; B 66, 69, 75; Mn
 79, 81, 82, 83, 84, 85, 86, 89, 90, 92,
 93, 94
 Beans Cu 16, 17, 26; Zn 47
 Beech Mn 79
 Beetroot (Beta vulgaris) Cu 16, 26; Zn
 37, 39; Mn 78, 79
 Beet, sugar B 65
 Betula alba B 66
 Birch Mn 79
 Botrytis cinerea Mn 90
 Brassica oleracea Mn 78
 Buckwheat 11; Cu 16, 17, 29, 30; As 53
 (*see* Polygonum Fagopyrum)

 Cabbage Sr 5; As 51, 52; Mn 87
 Cacao Cu 16
 Callitris gracilis Mn 80
 robusta Mn 80
 Cannabis B 72
 sativa B 66
 Capsella Bursa-pastoris Zn 37
 Cardamomum minus Cu 15

 Carrot Mn 79
 Cauliflower Mn 78
 Cherry B 65
 Chestnut Ca 71; Mn 79
 Chickpea Cu 16; B 66
 Chicory Mn 79
 Chrysanthemum B 66
 Clover Zn 42, 44
 Colea Cu 24; Zn 42; As 58
 Collinsia B 72
 Coniferae Zn 38
 Conium maculatum Mn 78
 Colza B 74
 Couch grass Mn 83
 Cow pea Cu 18
 Cruciferae Mn 78, 89
 Cryptomeria japonica Mn 83
 Curcuma longa Cu 15
 Currant Cu 31

 Daerydium Franklini Mn 80
 Dianthus caryophyllus Mn 79

 Elodea canadensis Cu 32; Zn 48

 Fagopyrum esculentum Cu 29
 Ferns B 66
 Fig Zn 42; B 65, 66
 Fir Mn 80
 Flax Mn 78, 88, 89
 Fungi Zn 44, 50; As 64; B 66, 77

 Geranium Cu 24; Zn 42; As 58
 Gramineae B 72; Mn 69
 Grasses Zn 39, 40, 42
 Gymnosperms B 66; Mn 80

 Haricot B 71, 72
 green As 52
 white Zn 37
 Hemp Sr 5
 Hop B 66
 Hordeum distichum As 54
 vulgare Zn 39, 47 (*see* Barley)

 Iberis B 72

 Laminaria saccharina B 66
 Leguminosae B 72; Mn 78, 89
 Lentil Mn 79
 Lichen As 59
 Linseed Cu 16, 17
 Linum B 72

- Love-apple B 66
 Lucerne Mn 79, 91
 Lupin Cu 17, 19; As 59
 white As 61; B 67, 70 (*see* *Lupinus albus*)
 yellow B 70, 75
 Lupinus albus Cu 19, 20, 22; Zn 45;
 B 68 (*see* White Lupin)

 Maesa picta B 65
 Maize Cu 16, 17, 19, 24, 26, 27; Zn 37,
 44; As 53, 54, 60; B 67, 68, 71,
 72, 74; Mn 79, 81
 Menyanthes trifoliata Cu 35
 Mildew B 76
 Molinia caerulea Cu 16; Zn 37
 Mould B 76
 Mucor mucedo As 59, 63
 Mushroom B 66
 Mustard Cu 17

 Nasturtium Cu 17
 Nuphar lutea Cu 35

 Oak Cu 16; Zn 42
 Oak Cu 16, 17, 19; As 53; B 74; Mn 79,
 82, 86, 87
 Onion B 66; Mn 88
 Onobrychis sativa Zn 39
 Opium Mn 79
 Oscillatoria Cu 35

 Panicum italicum Cu 26; As 58
 Pansy Cu 24; Zn 42; As 58
 Paprika Cu 16, 17
 Paradieskörner (*Amomum* sp.) Cu 15
 Pea (*see* *Pisum sativum*)
 sweet Cu 17
 Pear Cu 16; B 65
 Penicillium Cu 33, 34
 brevicaule As 63
 cupricum Cu 34
 glaucum Cu 23; As 59, 63; Mn 90
 Phaseolus vulgaris Cu 17; As 53
 Phormidium Valderianum As 62
 Phyllocladus rhomboidalis Mn 80
 Pine Mn 80
 Pineapple Mn 83
 Pisum arvense Cu 29
 sativum Cu 17, 18, 26, 27, 29; Zn 41,
 47; As 58
 ("Pea") 3, 11, 13, 93; Cu 17, 26,
 29, 30; Zn 40, 46; As 51, 54, 55,
 56, 58, 61; B 67, 73, 74, 75, 93;
 Mn 79, 81, 82, 85, 86, 87, 89, 92
 Plantago lanceolata Zn 37
 Podocarpus elata Mn 80
 Polygonum amphibium Cu 35
 aviculare Zn 37, 38
 Fagopyrum Cu 26, 39; Zn 41; As 54,
 58 (*see* Buckwheat)
 Persecaria Cu 5; As 54
 Poplar Cu 15

 Potato Cu 16, 26, 27, 30; As 52; Mn
 78, 79
 Protococcus infusionum As 62
 sp. As 63
 Pyrus communis Mn 79

 Radish Sr 5; B 74; Mn 84, 90
 Raphanus B 72
 sativus Zn 39
 Raspberry As 65
 Rice Zn 47; B 66, 73; Mn 79, 86, 87, 88
 Rosa remontana Mn 79
 Rubus B 66
 Rye Cu 16; As 60, 61

 Sainfoin Mn 79
 Secale cereale Cu 26; Zn 41; As 58
 Silene inflata Zn 36, 37
 Solanum tuberosum Mn 78
 Soy beans Cu 17, 19; B 67; Mn 81, 85
 Spinaoh 41; B 73; Mn 89
 Spergula arvensis Zn 39
 Spirogyra Cu 35; As 62; B 76
 Stichococcus bacillaris As 62
 Sterigmatocystis nigra Zn 48, 49 (*see*
 Aspergillus niger)
 Sugar cane B 65

 Taraxacum officinale Zn 37
 Tea Mn 79
 Thlaspi alpestre Zn 36
 sp. Zn 38
 Tobacco B 66
 Trapa natans Mn 79
 Trifolium pratense Zn 39
 Triticum vulgare Cu 17; B 67 (*see* Wheat)
 Tropaeolum Lobbianum Cu 17, 18
 Turnip As 51, 52; B 74
 swede Mn 78
 Tussilago Farfara Zn 37, 38

 Ulothrix tenerrima As 62
 Ustilago Cu 28

 Vaucheria B 76
 Vicia Faba Sr 5; Cu 27, 29
 sativa B 67; Zn 39
 Viola sp. Zn 38
 tricolor Zn 36
 Vine Cu 31
 Vitis vinifera As 52

 Watercress B 66
 Water-melon B 65
 Wheat Cu 16, 17, 23; Zn 37, 44, 46; As
 52, 60; B 66, 70, 72, 73; Mn 79,
 81, 83, 84, 85, 86, 87
 Willow Zn 39, 40

 Yeast Zn 50; B 76

 Zea japonica Cu 17, 18
 Mays (*see* Maize)

GENERAL INDEX

- Absorption capacity of soils for zinc 41
 - of poisons by plants 25
- Accelerators 45
- Action of heavy metals in mixed solutions 20
- Adsorption 8, 23
- Aeration in water cultures 8
- Algae, assimilation of arsenic by 62
 - clearing ponds of 35
 - effect of arsenic on 62
 - effect of boron on 76
 - effect of copper on 35
- Aluminium 45, 78
- Arbutin 4
- Arsenate, potassium 53, 62, 63
 - sodium 55, 57, 61
- Arsenates 53, 57
- Arsenic acid 53, 54, 60, 61, 62, 64
 - acid v. arsenious acid 53
 - acid v. phosphoric acid 53, 62
 - elimination of 59
 - gas liberated by moulds 63
 - in soil, effect of 58
 - in superphosphate 58
- Arsenious acid 53, 54, 57-61, 64
 - immunity of plants to 58
- Arsenite, sodium 55, 56, 61
- Arsenites 53, 57
 - v. arsenates 57
- Artificial oxydases 84
 - soil 24, 46
- Assimilation, reduction in water plants 48
- Barium 44
- Borate, calcium 71
 - potassium 71
- Borates 72
- Borax 71, 73
- Bordeaux mixture 30
 - blocking of stomata by 33
 - on assimilation, effect of 33
- Boric acid 1, 65-76, 93
- Boromannitic acid 68
- Boron, antiseptic action of 70
 - colour due to 75
 - distribution in plants 66
 - poisoning, indication of 68, 69
 - rôle in plant economy 74
- Cadmium 31
- Calamine 37
 - plants 38
 - soils, flora of 37
- Calcium carbonate 4, 23, 25
 - chloride 20, 59
 - sulphate 20, 44, 45
- Carbon black 23
 - dust 10
- Catalytic elements 49, 91
- Chlorophyll 44, 60
- Complementary manures 47, 91
- Conditions of plant life 7
- Copper, acetate 19
 - action on plant organs 30
 - bi-carbonate 26
 - bromide 19
 - chloride 19, 20
 - compounds, corrosive action on plant roots 5, 27
 - distribution in tissues 16
 - mode of action on plants 25
 - nitrate 13, 25
 - oxide 15, 25
 - quantity in certain plants 17
 - salts, injection into plant tissue 31
 - sprays, effect on leaves 30, 32
 - sulphate 5, 19, 20, 22-27, 29-35, 41
- Cumarin 4
- Distilled water, preparation of 10
- Double decomposition in soil 25
- Duration of experiments 13
- Experimental methods, comparison of 14
- Ferric chloride, sublimed 86
 - hydrate 23
- Fungi, effect of arsenic on 63
 - effect of boron on 76
 - effect of copper on 33, 34
 - effect of manganese on 90
 - effect of zinc on 48
- Galactose 76
- Glucose 76
- Germination, effect of arsenic on 60
 - effect of boron on 72
 - effect of copper on 27, 28
 - effect of manganese on 84
 - effect of zinc on 43
 - of seeds in sawdust 11
- Grading of seeds 11
- Growth in copper-distilled water 17
 - of peas in water cultures 11
- Hydrochloric acid 22

- Hydroquinone 91
 Hypothesis of universal stimulation 98
 Iodine 2, 91
 Individuality of plants, error due to 13
 of species 61
 Interaction between soil and poison 9
 Iron 31, 49
 oxide 78
 sesquioxide 84
 sulphate 48, 81, 85, 88
 Laccase 91, 95
 Lack of control over field experiments 9
 Lead 10, 26, 42, 44
 Magnesium carbonate 83, 84, 87
 chloride 20
 sulphate 1
 Manganese as top-dressing 89
 chloride 86, 88
 commercial value of 88
 cytological action of 81, 82
 dioxide 84, 87
 essential to Coniferae 80
 in Australian soils 88
 in leaves, deposition of 82
 in organic combination 79
 iodide 83, 84
 manuring, after-effects of 83
 nitrate 83, 84
 oxide 78, 79, 83, 84, 86, 88
 phosphate 79, 83, 86
 retardation of ripening by 82, 85
 sulphate 81-89, 94
 Masking effect of inorganic food salts 4, 20
 Mercuric chloride 22
 oxide 41
 Mercury 26
 Metallic oxides 78
 Methods; field experiments 9
 sand cultures 8
 soil cultures in pots 9
 water cultures 7, 11
 Mode of entry of poisons into plants 4
 Nickel 24, 50
 Nucleinic combination 79
 Nutrient solutions, composition 13
 Oligodynamic action 28
 Over-mineralisation of plants 71
 Phosphoric acid 53, 54, 62, 64
 Photosynthesis, effect of copper on 82
 Potassium hydrate 22
 Presence of arsenic in animals 51
 in plants 51
 of boron in plants 65
 of copper in plants 15
 of manganese in plants 78
 of zinc in plants 36
 Pyrogallol 91
 Raulin's solution 49
 Reproduction of poisoned plants 40
 Silver nitrate 22
 Sodium chloride 20, 44
 hydroxide 22
 nitrate 4
 Sterile cultures 24
 Stimulation, by injection of copper solu-
 tions 31
 by small doses of poisons 2
 definition of 2
 local 47
 of *Aspergillus niger* 50
 of fungi by copper 34
 of plants by arsenic 61
 of plants by boron 73
 of plants by copper (negative) 28
 of plants by manganese 84
 of plants by zinc 45-47
 physiological considerations of man-
 ganese 90
 Strontium sulphate 5
 Sugar 22, 31, 48, 49, 50, 68
 Sulphur, flowers of 10
 Thymol 22
 Toxic action, effect of arsenic 52
 effect of boron 67
 effect of copper 17
 effect of light on 44
 effect of manganese 81
 effect of zinc 38
 equivalent 18
 limits of plant poisons, estimation of 26
 Toxicity, of nutrient salts 1
 of organic compounds 4
 of poisons, cause of 22
 of positive ions in copper compounds
 19, 22
 reduction of 39, 44
 reduction of, by carbon black and ferri-
 hydrate 23
 reduction of, by insoluble substances 22
 Toxin and nutrient, distinction between 8
 Transmission of power of resistance 72
 Valency, effect on toxicity 44
 Vanillin 4
 Variation in results on different substrata
 24
 Zinc, absorption by roots 42
 carbonate 88, 42, 43
 effect of, on lower plants 48
 effect of, on plant and soil 41
 fixation of 49
 mode of action on plants 43
 oxide 37, 47
 oxide on leaves, deposition of 47
 storage in seeds 43
 sulphate 38-49
 sulphide 42

CAMBRIDGE AGRICULTURAL MONOGRAPHS

GENERAL EDITORS: T. B. WOOD, M.A., Draper's Professor of Agriculture in the University of Cambridge, and E. J. RUSSELL, D.Sc., Director of the Rothamsted Experimental Station, Harpenden, Herts.

Each volume of this series will contain a summary of the present position on some particular aspect or branch of agricultural science by an expert of acknowledged authority.

The treatment will be critical and impartial, and sufficiently detailed on all points of fundamental importance to be of use alike to all readers, but especially to those who are not in touch with an institution possessing a well equipped reference library. Full references will be given, and a bibliography attached for the benefit of those who wish to follow up any particular point.

The following volumes are in preparation:

The Strength of Wheat Flour. By Professor T. B. WOOD, M.A.

The Constitution of the Soil. By E. J. RUSSELL, D.Sc.

Disease Resistance. By R. H. BIFFEN, M.A., F.R.S., Professor of Agricultural Botany in the University of Cambridge.

Poisonous Plants. By H. C. LONG.

THE CAMBRIDGE FARM INSTITUTE SERIES

GENERAL EDITORS: Professor T. B. WOOD, M.A., and E. J. RUSSELL, D.Sc.

The volumes of this series are intended to meet the needs of the many Farm Institutes already in existence or about to be formed. They are intended for the average student whose object is to farm, rather than for the exceptional man who wishes to become an agricultural expert.

Every endeavour will be made to attain a high standard educationally, by training students to take an intelligent interest in their daily work and to appreciate the beauty of the common objects among which their life will be passed. On the other hand the fact that farm students must earn their living on the land will not be lost sight of.

The following will be among the first volumes:

Farm Accounts. By C. S. ORWIN. [Now ready]

Plant Life in Farm and Garden. By Professor R. H. BIFFEN, M.A.

The Feeding of Farm Animals. By Professor T. B. WOOD, M.A.

A Student's Book about Soils and Fertilizers. By E. J. RUSSELL, D.Sc.

Common Fungus and Insect Foes. By F. R. PETHERBRIDGE, M.A.

Cambridge University Press
C. F. Clay, Manager: Fetter Lane, London

SELECTION FROM THE GENERAL CATALOGUE
OF BOOKS PUBLISHED BY
THE CAMBRIDGE UNIVERSITY PRESS

THE CAMBRIDGE BRITISH FLORA

By C. E. Moss, D.Sc., F.L.S., assisted by specialists in certain genera.
Illustrated from drawings by E. W. HUNNYBUN. The work will be
completed in about ten volumes. Volume II is now ready.

The styles of binding and the prices will be as follows:

	Published Price per volume	Price per volume to subscribers to the whole work
Paper boards, with canvas back and paper label, each volume in two parts, the first containing the text and the second the plates	£2 10s net	£2 5s net
Quarter morocco, in two parts divided as above	£6 net	£5 5s net
Paper boards, with canvas back and paper label, in one volume, the plates mounted on guards and bound interspersed with the text	£3 net	£2 15s net
Quarter morocco, in one volume, the plates mounted on guards and bound interspersed with the text	£6 net	£5 5s net

"The appearance of Dr Moss's work has been anticipated by British botanists with the greatest interest; not only to them does it appeal, for its completeness and attention to detail entitle it to rank among works of Continental importance. The Cambridge University Press has been fortunate in securing the services of Dr Moss, than whom no one more competent for the task could be found. By a combination as admirable as it is rare, Dr Moss is at once an acute field botanist, a diligent investigator of herbaria, and a student of botanical literature....Mr Hunnybun's drawings are all made from living plants, so that the work may be regarded as representing more fully than has been hitherto done our knowledge of British Botany at the present day."—*Journal of Botany*

Genera of British Plants. Arranged according to Engler's *Syllabus Der Pflanzenfamilien* (Seventh edition 1912), with the addition of the Characters of the Genera. By H. G. CARTER, M.B., Ch.B. Crown 8vo. 4s net.

British Rust Fungi (Uredinales). Their Biology and Classification. By W. B. GROVE, M.A. Demy 8vo. With 290 figures. 14s net.

Types of British Vegetation. By members of the Central Committee for the Survey and Study of British Vegetation. Edited by A. G. TANSLEY, M.A., F.L.S. Crown 8vo. With 86 plates and 21 figures. 6s net.

The Production and Utilisation of Pine Timber in Great Britain. Part I. Production. By E. R. BURDON, M.A., and A. P. LONG, B.A.

No. 1. Sample Plots of Scots Pine at Woburn. Demy 8vo. Paper covers. 1s 6d net.

No. 2. Sample Plot of Scots Pine at King's Lynn. Demy 8vo. Paper covers. 9d net.

The Journal of Agricultural Science. Edited by R. H. BIFFEN, M.A., F.R.S., A. D. HALL, M.A., F.R.S., E. J. RUSSELL, D.Sc., and T. B. WOOD, M.A. Vols. I, II, III, IV and V now ready. In four parts. Paper covers. 15s net per volume. Bound in Buckram, 18s 6d net per volume.

Price to subscribers, 15s net per volume, post free, payable in advance. The price of each part sold separately will be 5s net.

Cambridge University Press
C. F. Clay, Manager: Fetter Lane, London

**THIS BOOK IS DUE ON THE LAST DATE
STAMPED BELOW**

**AN INITIAL FINE OF 25 CENTS
WILL BE ASSESSED FOR FAILURE TO RETURN
THIS BOOK ON THE DATE DUE. THE PENALTY
WILL INCREASE TO 50 CENTS ON THE FOURTH
DAY AND TO \$1.00 ON THE SEVENTH DAY
OVERDUE.**


DEC 20 1936

DEC 21 1936

LD 21-106m-2, '34

u2a x
pneum

YC 20922



100-100

